

Dakota Access Pipeline
South Dakota Reroute Options at/near Sioux Falls

Alternative	Length of Reroute (mi)	Powerline Crossings	Pipeline Crossings	Existing Utilities Colocation Distance (mi)	NHD Lake/Pond Crossings	NHD Lake/Pond Total Distance Crossed (ft)	NHD Stream Crossings	NWI PEM Wetlands Crossed	PEM Wetland Total Crossing Distance (mi)	Cultural Resources	
										Site ID	NRHP Status
Option 1	14.64	6	3	0	0	0	11	17	0.42	None	N/A
Option 2	14.73	6	3	0	1	94	13	19	0.43	39LN2007 (Historic RR)	Eligible
										39LN2013 (Historic RR)	Eligible
Option 3	14.97	6	3	0	2	588	14	25	0.73	None	N/A
Option 4	14.95	6	3	0	1	506	13	21	0.58	None	N/A
Preferred Route	13.90	6	3	3.1	0	0	11	6	0.12	None	N/A
Landfill – Original Route	1.2	0	0	0	0	0	0	0	0	None	N/A
Landfill – Adjusted route	1.4	0	0	0.50	0	0	2	0	0	None	N/A

