


SD PUC Route Shift Filing Summary

Route Shift	2/18/2016 Structure Reference	Map/Book Page	Parcel ID(s)	Shift Description
1	057 - 061	1	128-64-24-A	The SD Facility was straightened along 388th Avenue by removing angles for about 0.5 miles. The original route was developed to avoid impacts to trees and a former gravel pit that the landowner was thinking of using again. However, after discussions with the landowner, the landowner preferred a straight route to minimize impacts to farming.
2	067 - 069	2	128-63-31-C 128-64-36-B	Structure 068 (former Structure 068-P) was moved to the west side of 388th Avenue to avoid a cultural resources site, moving the road crossing about 0.2 miles south. The landowner of 128-64-36 had no objections to the route adjustment.
3	078 - 080	3	127-63-07-C	Structure 079 (former Structure 078.1-P) was moved to the east side of 388th Avenue to avoid potential wetland impacts, moving the road crossing about 0.3 miles south. The landowner of 127-63-07-C had no objections.
4	131 - 137	4	125-64-12-A 125-63-07-D 125-63-07-C 125-64-13-A 125-63-18-B 125-63-07-B	SD Facility Route was modified by removing a 90 degree corner near the intersection of 120th Street and 388th Avenue in 125-64-13 and the route was adjusted to a diagonal route through 125-63-07. This route adjustment was made to accommodate landowner request to increase distance from a farmstead and reduce routing on a landowner's property who opposed the Project. The landowners were agreeable to the route adjustment.
5	184 - 189	5	124-62-06-D 124-62-06-A 124-62-05-D	The SD Facility was modified by angling Structures 184 to 189 (former Structures 180-P to 183-P) to accommodate a landowner request to increase distance from a newly built home in 124-62-6, to avoid potential impacts from Elm River overland flooding and erosion by not having multiple crossings of the river, place structures around cultural resources sites, and to limit tree removal in a shelter belt. The route adjustment was agreeable to landowners.
6	228 - 230	6	124-62-36-D 124-62-36-H	The SD Facility was shifted to avoid potential impacts to NRCS and USFWS easements. Landowners were agreeable to the route adjustment.
			120-56-08-H 120-56-08-D	Structures 468 to 470 (former Structures 453-P, 454-P and 455-P) were moved about 300 feet east to accommodate the landowner's planned agricultural outbuildings. This created





SD PUC
Route Shift Filing Summary

Big Stone South to Ellendale		1	120-56-08-G	an angle between Structures 467 to 470 (former Structure 451-P and 456-P). The landowner was agreeable to the adjustment.
8	493 - 497	8	120-56-14-B 120-56-13-C 120-56-13-B	Structures 495 and 496 (former Structures 479-P and 480-P) were moved to the south and Structure 494 (former Structure 478-P) was moved slightly north. This route adjustment was made to avoid potential cultural resource site impacts and to reduce impacts to a treed shelter belt. The route adjustment was based on landowner discussions and the adjustment is agreeable with the landowners.