

EL18-003 - In the Matter of the Application by Dakota Range I, LLC and Dakota Range II, LLC for a Permit of a Wind Energy Facility in Grant County and Codrington County, South Dakota, for the Dakota Range Wind Project

Public input hearing on the Application on March 21, 2018, at 5:30 p.m., CDT, at Waverly-South Shore School Gymnasium, 319 Mary Place, Waverly, S.D.

(George L. Holborn)

The wind developers paid experts have claimed for years:

“What you can’t hear can’t hurt you”. No surprise, they are wrong!

The Wind Industry has known this for more than 35 years.

Dr. Neil Kelly found people complained as far away as 1.8 miles about sleeplessness, headaches, nausea, etc. Those kinds of misery were linked to a 2.0MW turbine.

In this application, I’m told the wind developer is proposing turbines as large as 4.2MW. There are no 4.2 MW turbines operating in SD or MN.

Steven Cooper has taken Dr. Kelly’s studies a step further.

He found “dba does not work”. It is correlated well with wind speed but not with noise from the turbine.

This is so important:

“It was not until we tried the complaints versus the infrasound that the sensation came out as the major impact.”

“We tried plotting the Greatest Level of Sensation (when the residents actually left their properties or wanted to leave) & found Patterns of Disturbance related to power output...”

I understand someone suggested installing fewer larger turbines & feathering (depowering). Cooper’s work seems to indicate this may not be a good idea. You would be using non-participants as test subjects without their knowledge.

This is crucial, as Cooper continues: “What we have found is that we can present to people inaudible wind turbine noise & get a reaction whilst we can provide inaudible road traffic noise or wind noise at similar levels & not get any reaction.”

“For the people who are adversely affected by wind turbines to the extent that it affects their daily lives and in extreme cases causes them to abandon their homes, it is clearly a problem...”

So, Cooper has identified & can reproduce the IWT signature.

This next quote is so crucial: “It appears the residents’ report a greater sleep disturbance over time & more people have had to abandon their homes.”

Because of Cooper’s research, medical studies are now able to confirm the actual impact on people that live among the turbines. Until those studies are completed, the precautionary principle should be applied.

That being a moratorium/do no harm.

People need to come before profits. For example at a County Commission Meeting in Clear Lake, S.D. a wind developer representative talked on and on about 30 hours of flicker. Finally, one of the commissioners asked him “If it is such a small amount, why don’t you turn the turbines off?” After a brief pause, the wind developer replied “That would affect the profitability of the project.”

What about the profitability and adverse health effects of the people who are forced to live among the turbines?

Until the regulatory agencies use other than wind paid experts & Government bias reports to justify harmful government mandates, the misery of rural communities will continue in countless more ways than I have noted here.

Cooper concludes with seven questions that need to be answered by Regulatory Authorities in relation to the criteria that those authorities have issued to permit wind turbines to operate in proximity to residential receivers.

- 1. Please provide studies upon which the wind turbine farm criteria have been developed?**
- 2. Please identify the noise source(s) that have been used in the studies related to question 1?**
- 3. Please provide the dose-response data related to wind turbine/farms on which the criteria are based, and the corresponding level that represents 10% of the population that is highly affected?**
- 4. The most common complaint from residents relates to sleep disturbance. Please provide the studies of wind farm noise that identifies the noise (in any relevant acoustic index) that gives rise to sleep disturbance?**
- 5. Please provide studies of wind farm noise that identify the noise level (in any relevant acoustic index) that will not give rise to sleep disturbance.**
- 6. Please provide studies of wind farm noise that identifies the noise level that would protect the acoustic amenity of residents in proximity to wind farms.**
- 7. In light of the above, please identify who would be liable (in a damages claim) for the consequences of adverse impacts.**

References

National Wind Watch December 14, 2017 "In the Shadows of Wind Farms"
Emily Le Coz & Lucille Sherman, Gate House Media

Master Resource: "Sensing but Not Hearing: The Problem of Wind Turbine Noise" (Sherri Lang
Interview with acoustician Steven Cooper, AU Feb. 18, 2018)

Proceedings of Meetings on Acoustics Volume 30
173rd Meeting of Acoustical Society of America and 8th Forum Acusticum
Boston, Mass. June 25-29, 2017
"Subjective perception of wind turbine noise" by Steven Edwin Cooper

Acoustical Society of America Dec. 2017 Volume 31 174th Meeting of the Acoustical Society of
America "Subjective perception of wind turbine noise – The stereo approach" by Steven Edwin
Cooper and Chris Chan

George L. Holborn


Gary, SD 57237



48.GHR.L1:MSC

27th February, 2018

Mr George Holburn

[REDACTED]
GARY SD 57237

USA

Dear Sirs,

PERMISSION TO REFER TO
TWO PUBLICATIONS PREPARED BY S COOPER AND ISSUED BY THE ACOUSTICAL
SOCIETY OF AMERICA, AND AN INTERVIEW BY SHERRI LANGE
IN RELATION TO A SUBMISSION REGARDING THE CROCKER WIND FARM AND
TRANSMISSION PERMIT APPLICATION

You have provided to me a copy of a letter from the South Dakota Public Utilities Commission identifying the need for a commenter relying upon material authored by another requires proof of the right to redistribute that material.

You have requested permission from me to distribute the following material recently placed in the public domain:

- "Subjective perception of wind turbine noise", being Proceedings of Meetings on Acoustics (Vol 30, Acoustics'17 Boston) published by the Acoustical Society of America
- "Subjective perception of wind turbine noise – The stereo approach", being Proceedings of Meetings on Acoustics (Vol 31, 174th Meeting) published by the Acoustical Society of America
- "Sensing but Not Hearing: The Problem of Wind Turbine Noise (Interview with acoustician Steven Cooper, AU) published by MasterResource (<https://www.masterresource.org/windpower-health-effects/sensing-not-hearing-problem-wind-turbine-noise-interview-acoustician-steven-cooper-au/>)

The first two items are papers I presented to the Acoustical Society of America Wind Turbine Working Group in which the copyright is held by the ASA. As both papers are available in the public domain and if reproduced in full contain the copyright symbol at the bottom of the title page then I have no objection to you referring to those two peer reviewed papers.

The Interview was placed in the public domain by MasterResource and I have no objection to that interview being included in your submission with the following qualification:

- In the response to the 6th Question in providing the reciprocal of the pulsing frequency the timing in an earlier version stated 1.77 seconds. That was corrected to 1.177 seconds. Accordingly, the submission should have that current version to correct that error (and some other typos).
- The public forum should be directed to the section on sleep disturbance and the seven questions that I have raised. As these questions are critical to the assessment of wind farms, answers to those questions must be provided by the Commission to safeguard the community from adverse sleep and health effects.

Yours faithfully,

THE ACOUSTIC GROUP PTY LTD



STEVEN E. COOPER



Acoustical Society of America
Suite 300, 1305 Walt Whitman Road, Melville, NY 11747-4300
(516) 576-2360; asa@acousticalsociety.org

Transfer of Copyright Agreement

Authors who submit manuscripts for any of the publications of the Acoustical Society of America (ASA) are required to read this document and to take appropriate actions during electronic submission. The Society desires the right to disseminate material which it publishes to the fullest extent and desires the right to restrict publication by third parties who might illegally profit from the investments that the ASA has made in its publications. To insure that this is possible and to conform with U.S. copyright laws, it is desirable that the copyright be held by the Society. Electronic signature certifying agreement and acknowledgment that the corresponding author has read this document constitute a transfer of copyright, to the fullest extent of which the author is authorized to do so.

The implied transfer of copyright is for the original article that is being submitted and subsequent, if necessary, errata, and the abstract forming part thereof, the transfer being to the Acoustical Society of America for the full term thereof throughout the world, subject to the Author Rights (described below) and to acceptance of the Article for publication. The transfer of copyright includes all material to be published as part of the Article (in any medium), including but not limited to tables, figures, graphs, movies, and other multimedia files. Given that the author has the authority to transfer such copyright, the ASA shall have the right to register copyright to the Article in its name as claimant, whether separately or as part of the journal issue or other medium in which the Article is included.

The terms of the transfer agreement are such that the author(s) are reserved certain rights to additionally disseminate the work via outlets other than those of the Acoustical Society of America. These rights are as follows:

1. All proprietary rights other than copyright, such as patent rights.
2. The right, six or more months after publication by the ASA, to post copies of the article as published on the author(s) institutional internet web sites or on governmental web sites, to whatever extent is required by the author(s) institution or by whoever funded the research reported in the paper. The author also has the sole right to grant any other category of third party the right to republish fragments of the paper, but not the entire paper. (If any such third party seeks to republish the entire paper, the ASA will grant them permission only if there is clear evidence that the author approves of the republication. The authority to make the decision is reserved by the ASA. The granting of such permissions is administered by the Office of Rights and Permissions of the American Institute of Physics on behalf of the Acoustical Society of America.) Any such republication must give a complete citation to the article originally published by the ASA and must describe any modifications that have been made to the original.
3. The right, after publication by the ASA, to use all or part of the article, including the ASA-formatted version, in personal compilations or other publications of the author's own works, including the author's personal web pages, and to make copies of all or part of the article for the author's use for lecture or classroom purposes. Any such use must give a complete citation to the article and describe any modifications that have been made to the original. Any such use that purports to be the original ASA article must be identical to the ASA-formatted version. Any electronic posting of the article must include a link to the on-line publication of the article.
4. If the article has been prepared by an employee within the scope of his or her employment, the employer shall have the right to make copies of the article for the employer's own internal use. If the article was prepared under a U.S. Government contract, the government shall have the rights under the copyright to the extent required by the contract.

The author(s) agree that, insofar as they are permitted to transfer copyright, all copies of the article or abstract shall include a copyright notice in the ASA's name. The author(s) represent and warrant that the article is original with them, that it does not infringe any copyright or other rights in any other work, or violate any other rights. If the work is such that governmental laws forbid it to be copyrighted, and that it is free for open dissemination, then the author's electronic signature attests to such being the case. If there is more than one author, then the corresponding author's electronic signature attests to that individual having the authorization to sign for and on behalf of all the other authors.

Subjective perception of wind turbine noise

Steven Edwin Cooper

Citation: *Proc. Mtgs. Acoust.* **30**, 040011 (2017);

View online: <https://doi.org/10.1121/2.0000639>

View Table of Contents: <http://asa.scitation.org/toc/pma/30/1>

Published by the *Acoustical Society of America*



Acoustics `17 Boston



173rd Meeting of Acoustical Society of America and 8th Forum Acusticum

Boston, Massachusetts

25-29 June 2017

Noise: Paper 4aNSb1

Subjective perception of wind turbine noise

Steven Edwin Cooper

Head Office, The Acoustic Group, PTY, Ltd., Lilyfield, NSW, 2040, AUSTRALIA; dnoise@acoustics.com.au

The evaluation of wind turbine noise impacting upon communities is generally related to external noise environments and has a problem with separating wind turbine noise from ambient noise (which includes the presence of wind) which is not normally the case for general environmental noise. Subjective testing of wind turbine noise to examine amplitude modulation and subjective loudness has tended to use large baffle speaker systems to produce the infrasound/low-frequency noise and one high-frequency speaker - all as a mono source. Comparison of mono and stereo recordings of audible wind turbine noise played back in a test chamber and a smaller hemi-anechoic space provides a distinct different perception of amplitude modulation of turbines. A similar exercise compares use of high-quality full-spectrum headphones with the two different sound files applied to just the ears is discussed.



1. INTRODUCTION

Measurements conducted in proximity to wind turbines, generally at ground level, permit identification of noise characteristics that reveal a variation in the noise levels over time and under different wind conditions.

Figure 1 presents the statistical results in one third octave bands for a 10-minute sample at a position 150 m from the base of a 3 MW turbine tower, where the orientation of the microphone is to the side of the turbines and on a line at 90° to the wind direction [1].

In the low-frequency and infrasound region of the spectra there is a significant difference between the ambient L90 background noise level and the Leq noise level of the turbines, whilst a small increment for the mid band and high frequency components.

Of significance with respect to low frequency and infrasound components is the greater difference between the L1 levels attributed to the operation of the turbine versus the background level. One would expect maximum peak levels to be higher than shown in Figure 1.




Figure 1: Statistical Results near turbine – 10-minute sample.

The operation of turbines at residential receivers often contains a modulation of the A-weighted value that occurs at the rate of the blade pass frequency of the turbine. Interference/phasing effects between multiple turbines can lead to significant changes in measured levels over time.

Access to individual turbines in the nearfield identifies by use of acoustic cameras and objective assessments, a maximum noise level to occur at about a 2 o'clock position when looking from the upwind side of the turbine.

Depending upon the power output of the turbine, related to the available wind speed at the time [2], the depth of the modulation can vary significantly (Figure 2).




Figure 2 – Different power settings – CBW Study – ref [2]


2. AUDIBLE CHARACTERISTICS OF WIND TURBINES

Narrowband (FFT) Leq analysis of turbine noise indicates in the infrasound region, a signature showing the presence of the blade pass frequency, with multiple harmonics of that frequency, with narrowband tones (with side bands) in the region of 23 to 33 Hz (depending upon the make and model of the turbines) and broadband noise at higher frequencies.

The presence of periodic pulses of noise emitted from the turbine (at an infrasound rate) that can be seen in the time domain, have consistently identified the level of FFT derived “infrasound” at residential receivers (determined by FFT analysis) to be significantly below the threshold of hearing. The presence of infrasound (or not) in the real wave file signals does not appear to address the perception of the operation of turbines when such signals are played back on systems designed to replicate (or “synthesise”) such pulsations.

Common complaints in relation to the subjective nature of wind turbine noise identify a general low-frequency tone or broadband drone commonly expressed as “like the sound of the plane that never lands”, whilst other observers refer to periodic pulsation of the noise which typically may be identified as a “swish” noise which tends to be broadband mid frequency noise that varies in its amplitude at an infrasound rate being the blade pass frequency. The amplitude modulation of the total noise as a variation in pressure to the body (and not just the ears) has been suggested as triggering the startle reflex [3] [4].

Dependent upon different wind speed conditions, the depth of the modulation of the swish noise can vary significantly on a subjective basis. Subjective testing in relation to this component has focused on what has been described as the amplitude modulation for turbines as a “special audible characteristic”.



Simulated tests of amplitude modulation have tended to use test subjects in a controlled environment. In an endeavour to obtain sufficient energy in terms of a balanced spectrum have utilised large speaker installations such as shown in Figure 3, with the assessment in that study reporting the A-weighted value correlation with the noticeable impacts of the turbine noise and that frequencies below 100 Hz do not create impacts in terms of subjective loudness [5].

Figure 3: Subjective Testing – Tachibana ref [5]

With respect to the debate of infrasound generating sensation/perception of noise for residents, the baffle situation by Tabinachi [5] was implemented in a 126-cubic metre reverberation room that also evaluated audibility of infrasound and low-frequency noise with pulsations.




Figure 4: TAG Test Room 1

The difficulty in undertaking that work was obtaining a relatively flat response of the speaker system, clean reproduction of the sound signal, and appropriate signal-to-noise ratios, where the digital to analogue converter and amplifier combination generated its own self noise that interfered with the results.

General analysis of frequency spectrum associated with wind turbine noise utilise free running averaging triggers. Walker [6] [7] has utilised a triggered result based upon the blade pass frequency pulses to identify patterns of periodic noise in the spectra and the groupings of those patterns identified as “haystacks”.

Focusing on the issue of infrasound and low-frequency noise for the detection of wind farms, Walker has normally utilised a speaker with a synthesised infrasound signal for evaluation with test subjects. However, in one instance Walker [7] presented the use of external wave files with an adjustment for outside to inside attenuation, then being synthesised and an evaluation of different combinations of frequency cut-offs with test subjects.

Walker identified that the presence of infrasound made no difference to the test subjects. However, about two thirds into the paper there is a remarkable acknowledgement of the sensation of the turbines was more apparent when frequencies above 80 Hz were evident.

Walker [6] refers to use of the FFT spectrum from the Cape Bridgewater study [2] with a derived synthesis of the pressure wave. However, the derived synthesis does not agree with the original time signal noting that the original time signal includes discrete peaks in the low frequency component of the audio spectrum that also influence the time signal. Audible comparison, spectral analysis and time analysis of the original time signal and the Walker synthesised presented in Figure 12 of reference 7 found they were different.

The original CBW signal presented in Figure 12 of reference [7] represented an internal level of 18 dB(A). The provision of an additional 50 dB gain to present a clearly audible signal found on a subjective basis the synthesised signal was vastly different to the original signal.

The Cape Bridgewater study conducted in 2014 [2] was not a matter of a compliance test but was a specific study with a brief to investigate and determine certain wind speeds and sound levels that related to complaints from specific local residents.

Simultaneous indoor/outdoor monitoring at a number of houses occurred over a nine-week period, resulting in over 9 TB of data which in some instances are still being processed three years later. Figure 5 presents simultaneous outdoor/indoor measurements in Pascals for a standard 10-minute sample for a vacant room in a house 1.6 km from the nearest turbine.

Figure 5 includes an expanded timescale view for both locations that indicate the presence of modulation in the pressure waveform that is not so obvious when converted into a trace of Linear (unweighted) decibels over time.

Figure 6 presents the one third octave 10-minute Leq inside the bedroom for the outside versus inside. The outside results do not reveal any distinct peaks. The left-hand graph presents the two 1/3 octave band results in a linear weighting whilst the right-hand graph presenting the results as A-weighted one third octave values.

There are limitations in terms of the dynamic range of the measurements that were recorded, based upon Pulse IDE module which has a maximum of 80 dB dynamic range and the instrumentation set to ensure maximum levels with wind gusts did not overload the system.




FIGURE 5: Simultaneous Inside and Outside pressure traces. Upper traces 10 minute sample, lower traces 10 second extract, ref [2]




Figure 6: 1/3 Octave Band Results for Figure 5 (10 minute sample)

Utilising a UK method of assessing amplitude modulation by identifying peak 1/3 octave bands and then viewing those bands in the time domain would indicate focus on the peaks at 80 Hz, 125 Hz and 250 Hz, and basically ignore the other components in their modulation technique is looking for distinct peaks (see Figure 7).

However, the expanding the spectra in Figure 6 indicates that there are other peaks in the region of 800Hz to 4000 Hz that in themselves have higher A-weighted values but do not stand out as distinct peaks because there is a broadband increase rather than the concept of peaks on a double sided 1/3 octave band analysis.

The interesting matter about this dwelling and the results, is that the residents could detect the operation of the turbines during the test program, but the author was unable to identify any such noise.

Listening to the broadband wave file signals with some 50 dB gain did not detect any appreciable noise or characteristics inside the bedroom.

Utilising the actual wave files and adjusting the spectrum with a graphic equaliser enabled by eliminating the frequencies below 500 Hz and above 2 kHz (and with the benefit of some 50 or 60 dB gain) one could easily hear the swish of the turbines occurring in the audio signal.

Similarly, enhancing the frequencies between 25 Hz and 60 Hz found that on comparing the wind farm on and off tests (within half an hour under the same wind conditions) there was a rumble when the turbines were operating that was not present when they were off.

Based upon the audibility testing, the individual 1/3 octave band results were extracted for comparison with the A-weighted value. Figures 7 & 8 compare the A-weighted value with the 80 Hz and 1 kHz one third octave band time spllices to show that the fluctuations in the A-weighted level tend to have agreement with the individual 1/3 octave bands and that the fluctuations in the 1 kHz band are at or above the threshold of hearing.




Figure 7: 80Hz 1/3 Octave vs dBA inside bedroom (from Figure 5)




Figure 8: 1kHz 1/3 Octave vs dBA inside bedroom (from Figure 5)

For evaluating the perception of wind turbine noise additional measurements were conducted in proximity to the Capital Wind Farm, about a three and half hour drive SW of Sydney, where measurements conducted at 800 m from the nearest turbine included in one sample for a relatively short period of time the presence of audible amplitude modulation, barely audible amplitude modulation, and no audible amplitude modulation. The dominant peak in the low frequency regions was 25 Hz (see Figure 9).

Extraction of the 25 Hz 1/3 octave band found different levels of with modulation of the 25 Hz one third octave band that was masked by the broadband noise (see Figures 10 & 11).

The exercise in looking at the 1/3 octave bands during the audible swish (the amplitude modulation) revealed relationship between the A-weighted value and the frequencies between 600 Hz and 1.6 kHz.




Figure 9: 1/3 Octave Band Spectra for Audible Modulation, Barely Audible Modulation and No Audible Modulation.




Figure 10: 25 Hz 1/3 octave band – audible swish




Figure 11: 25 Hz 1/3 octave band – barely audible swish

On a subjective basis, listening to music with the big baffle speaker system found that the clarity of low-frequency noise was subject to phasing issues and simply was not of an appropriate quality when compared to the placement of a single full-spectrum system in the same room. This observation questioned the Tachibana method for a subjective assessment.

Preliminary experiments by use of a small anechoic room indicated that a better appreciation of the differences in audibility of wind farm noise occurs in such a listening environment.

Persons familiar with audio recording techniques would know of the different methodologies for obtaining a stereo signal with a preference for an AB testing of individual instruments having a relatively short space between the microphones so as to not create a wide and unrealistic stereo image.

Different combinations of recording techniques were tried on several occasions at the Capital Wind Farm using a standard reference location, leading to different sampling speeds and different analysis resolutions being obtained.



Figure 12: Multiple microphone setup

There are standards in relation to the measurement of wind turbines that look to the preference of grazing incidence for the sound source (similar is that to aircraft noise) so that the diaphragm does not alter the signal.

The results which have the best promise for subjective testing involved a set up that incorporated four simultaneous measurements at a time where two microphones were placed 180° apart, but parallel to the wave front of the wind turbines, to have the sound passing the microphone at grazing incidence (see figure 12). A microphone was placed in a vertical orientation to obtain grazing incidence, and a fourth microphone pointed directly towards the windfarm and thereby not having grazing incidence.

Whereas the recording industry may use microphones with cardioid patterns, to have a focus on the noise source, in the acoustic industry one uses omnidirectional microphones with a precise linear frequency response. The use of the combination of precision microphones described above permits one to undertake normal acoustic testing and provide accurate signals recorded by the microphones. The directional response for the two microphones used for the stereo locations show that there was general consistency in the frequencies although there is slight variation in the high-frequency region which is not dissimilar to the human ear.

Utilising the wind farm microphone setup for the same sample, revealed an audible difference between the vertical microphone versus horizontal microphone. However, with the nearest turbine being to the left of the microphone position the use of the stereo sample was most significant in its perception of turbines and audible amplitude modulation that varies during the sample in response to variations in the wind.

The sound field that is recorded for subjective listening on headphones is different to that for listening on speakers and must take account of the difference in directivity that the ear experiences, particularly with the ear having an emphasis in the high-frequency region.

When running the same exercise by use of headphones where the single microphone result of a sound level recording becomes mono in both ears is an entirely different perception of the stereo signal.




Figure 12 Spatial Orientation from Stereo Signals

3. CONCLUSIONS

Experiments with the method of large speaker baffles for the subjective perception of infrasound and low-frequency sound associated with wind turbine noise found difficulties in relation to accurately reproducing a signal which is discussed in another paper.

In looking at the subjective perception of wind turbine noise, it would appear that in the case of rural residents in Australia there is a perception of a pulsating noise source. The pulsations in some instances is described as a “swish”, when in proximity to the turbine, but when removed from the turbine and subject to substantial amplitude modulation has a reduction in the high-frequency noise and is described as a “thump”. In the UK, there is “amplitude modulation” and “excessive amplitude modulation”.

Multiple experiments at a set position for the Capital Wind Farm under different wind conditions (over 12 months) found the presence of amplitude modulation under certain wind conditions and at other times there being no audible amplitude modulation yet in discreet frequencies amplitude modulation was always present.

In relation to the A-weighted value the major contributor to the audible modulation was found to be associated with the mid-band frequencies between 500 Hz and 1.6 kHz.

In seeking to reproduce a sound in a laboratory situation that may be used for audible tests, the use of a hemi-anechoic room with line array speakers in stereo mode provided a more realistic situation and permits the detection of amplitude modulation more easily than in the use of a mono (single) speaker system. Use of stereo speakers with a mono signal is not recommended.




Figure 12: TAG hemi-anechoic room with line array speakers

Compliance testing of wind farms has required post-processing to assess “special audible characteristics”.

Listening on headphones to a mono signal from a sound level meter automatically reduces the ability to assess the noise to that that would have been obtained in-situ.

Most of us listen with two ears and most people in gaining a high-quality perception of, or listening to high-quality music listen using speakers. The use of stereo recordings played in a hemi-anechoic space was vastly superior to the large baffle system in the lined reverberation room.

The use of headphones for monitoring purposes or evaluating the perception of wind turbine noise requires a different measurement procedure to that for using speakers.

The next stage in the investigations is to evaluate recordings using manikins versus parallel microphone 180° apart, and a set of microphones 1.9 m apart (to agree with the line array speaker systems) being directly pointed towards windfarm.

4 REFERENCES

1. Cooper S.E., “Hiding Wind Farm Noise in Ambient Measurements – Noise Floor, Wind Direction and Frequency Limitations”, 5th International Conference on Wind Turbine Noise, Denver 2013
2. The Acoustic Group, “The Results of an Acoustic Testing Program, Cape Bridgewater Wind Farm”, Dec 2014 <http://waubrafoundation.org.au/resources/cooper-s-acoustic-group-resultscape-bridgewater-acoustic-investigation/2>
3. Cooper S.E., Can inaudible and audible low level infrasound and low frequency noise be an acoustic trigger of the startle reflex?”, Acoustical Society of America Meeting, Hawaii, December 2016
4. Cooper S. E., “A new methodology for investigating ILFN Complaints”, ICBEN 2017, Zurich. June 2017
5. Yokoyama S, Kobayashi T, Sakamoto S & Tachibana H “Subjective experiments on the auditory impression of the amplitude modulation sound contained in wind turbine noise”, International Meeting on Wind Turbine Noise, Glasgow 2015.
6. Walker B, Celano J, “Progress Report on Synthesis of Wind Turbine Noise and Infrasound”, 6th International Meeting on Wind Turbine Noise, Glasgow 2015.

7. Hansen K, Walker B, Zajamsek B & Hansen C "Perception and annoyance of low frequency noise versus infrasound in the context of wind turbine noise", 6th International Meeting on Wind Turbine Noise, Glasgow 2015.

Subjective perception of wind turbine noise - The stereo approach

Steven Edwin Cooper, and Chris Chan

Citation: *Proc. Mtgs. Acoust.* **31**, 040001 (2017);

View online: <https://doi.org/10.1121/2.0000653>

View Table of Contents: <http://asa.scitation.org/toc/pma/31/1>

Published by the *Acoustical Society of America*



174th Meeting of the Acoustical Society of America

New Orleans, Louisiana

04-08 December 2017

Noise: Paper 4pNS5

Subjective perception of wind turbine noise - The stereo approach

Steven Edwin Cooper

Head Office, The Acoustic Group, PTY, Ltd., Lilyfield, NSW, 2040, AUSTRALIA; drnoise@acoustics.com.au

Chris Chan

The Acoustic Group, PTY, Ltd., Lilyfield, NSW, 2040, AUSTRALIA; chris@acoustics.com.au

The conduct of stereo measurements for both playback in high-quality headphones and in a hemi-anechoic room has been undertaken for a number of wind farms and other low-frequency noise sources as an expansion of the material previously presented at the Boston ASA meeting. The results of the additional monitoring, evaluation, and subjective analysis of this procedure are discussed and identifies the benefits of monitoring noise complaints and assessments of wind farm noise in stereo. The laboratory mono subjective system was used to reproduce the audio wave file obtained in a dwelling. The test signal, being inaudible, was presented as a pilot double blind provocation case control study to 9 test subjects who have been identified as being sensitized to wind turbine noise and low frequency pulsating industrial noise. All test subjects could detect the operation of the inaudible test signal. The use of a stereo manikin to investigate detected inaudible "hotspots" is discussed.



1.0 INTRODUCTION

The subjective assessment of wind turbine noise, and in particular the perception of amplitude modulation, have been undertaken using a mono noise source that may be generated by multiple speakers mounted on a baffle [1], [2] or use of a three-sided speaker located in a corner of the room as an extension to the use of that speaker for the generation of synthesised infrasound [3], where in the main the source being reproduced is an external signal.

Reproduction of an internal signal has tended to use a synthesised signal (rather than an actual signal recorded inside a dwelling) with an assumption of building attenuation and disregarding the influence of room mode or building element resonances.

In relation to the accurate reproduction of wind farm noise over the infrasound region and the low frequency region the use of actual wave files is preferred, once one overcomes the technical challenges that are presented [4].

Having conducted measurements and assessments at residential premises in proximity to wind farms, on a subjective basis our experiments have found a significant difference on comparing the reproduced signals to the actual sound of wind turbines observed in the field.

Our previous paper on this topic presented at the Boston ASA meeting [5] identified an overwhelming support by test subjects for the use of stereo recordings for the subjective evaluation of external wind turbine noise.

The use of line array speakers in a hemi-anechoic room for a mono signal (from a precision sound level meter) versus a stereo signal from precision microphones set 1.9 m apart found a dramatic difference in the perception of external wind turbine noise. For the test subjects that have experienced the comparison there is 100% agreement that one must use stereo assessment for subjective assessment of wind turbine noise and in particular when evaluating special audible characteristics.

Further evaluation of special audible characteristics and/or subjective assessment of wind turbine noise has been undertaken using headphones with a frequency response of 4Hz – 45 kHz [6] and a D Class amplifier. The previous presentation postulated the concept of using manikins to be superior to two microphones orientated 180° apart (back to back). The principal basis of the hypothesis was the omnidirectional characteristics of precision microphones versus the directional characteristics that occur for humans (and manikins), due to the attenuation of the head with respect to the individual ears/microphones.

Having an individual in a stationary position whilst listening to a person moving 360° around that individual, and continuously talking with the speaker's mouth oriented towards the listener is a simple method to identify the difference in the sound that an individual hears where that sound comes from different directions.

2.0 OBTAINING THE STEREO SOUND FIELD

The cost of professional head and torso systems used for the acoustic evaluation of headphones or room acoustics [7] is not one that lends itself to fieldwork with respect to unfunded investigations.

A cost-effective solution utilised hollow manikins with Type 1 precision microphones mounted in each pinna, utilising a microphone extension rod from older precision sound level meters (rather than an expensive 90° adapter), with preamplifiers on the end of each extension rod, is a practical solution (see Figures 1 & 2).

Field testing was undertaken of microphone set ups using two microphones spaced 1.9 m apart pointed directly towards the noise source, two microphones in line but 180° apart and parallel to the wavefront from the noise source of the investigation, and the stereo manikin concept identified in Figure 1. In all cases the microphones used are GRAS 40AZ with B & K 2669 preamps to a LANXI multichannel Pulse System with a sample recording rate of 113 kHz per second. The stereo wave file signals were compared directly with a wave file from a B & K 2250 Sound Level Meter using a B & K 4193 microphone. All system combinations permit full-spectrum monitoring down to and including the infrasound region.

Comparison of the stereo measurements versus the single mono channel measurement have for every test subject found the stereo material (when compared to mono) to be superior whether utilising speakers or headphones.




Figure 1 View of Microphone set up




Figure 2 Manikin mic in ear and preamp on extension rods

Utilising the headphones for playback, the manikin measurements were found in the opinion of all the test subjects to be superior in terms of its presentation of the stereo image, and the degree of subtle differences that did not arise from the use of omnidirectional precision microphones where there is no separation in terms of directivity from sound from the other side of the sound field that is present.

Table 1 presents the rankings from the subjective assessment of wind turbines using headphones versus the line arrays.

Ranking	Headphones	Line Arrays in Hemi-Anechoic Space
1	Manikin	Spaced mics towards source
2	Spaced mic towards source	Mics 180° apart
3	Mics 180° apart	Manikin
Do not use	2250 (mono)	2250 (mono)

Table 1: Stereo Subjective Assessment Recommendations for External Noise Sources

3.0 SENSATION INVESTIGATION

Because of a presentation by Dr Michaud at the ASA Salt Lake Meeting Wind Turbine Session in relation to the Health Canada investigations [8], discussions from other presentations [9] [10], and the session attendees, it appeared that several of the houses in the two study areas had been abandoned by residents, citing the issue of disturbance from wind turbines. Therefore, not all persons who may be considered sensitive to wind turbine noise were included in the Health Canada study [11].

Dr Michaud indicated to the attendees that in light of discussions in the Wind Turbine Session he would propose to Health Canada to undertake additional investigations of persons who had resided in the two study areas but had abandoned their houses because of disturbance, where such a study would be undertaken with the assistance of the community to obtain access to those individuals. The results of the suggested study had not been presented and as such, still left a question as to the relevance of sensitised people in terms of their ability to sense the operation of wind turbines.

To address the perception of persons who may be considered sensitised to wind turbine noise and examine the claim of residents sensing the operation of the turbines without actually hearing the noise, a series of experiments were undertaken utilising persons in Australia who have been identified as being sensitive to wind turbine noise, and low-frequency noise that exhibits pulsations occurring at an infrasound rate ("test group 1").

In 2013 Schomer proposed the possibility that a limited number of residents subject to noise from wind turbines may be experiencing motion sickness and suggested the construction of a test facility that utilise special transducers to extend down to very low frequencies (0.05 Hz or lower) [12]. Schomer proposed to undertake sensing tests that could then lead to further medical examinations on animals to develop an understanding why the phenomenon seems to affect some residents near wind farms and establish who are affected by wind turbine infrasonic emissions in various ways.

We have previously utilised one of our reverberation test chambers (having a volume of 126 m³) with twelve 15" sub-woofers mounted on in the aperture between the reverberation chambers to investigate threshold of sensation versus threshold of hearing in the infrasound region [13], investigations into the 'infrasound signature' from wind turbines [14], [15] & [16]. Those investigations were undertaken using pure tones or external (free-field) noise measurements of wind turbine noise.

The chamber has been used to investigate the generation of recorded wind turbine noise versus field measurements to identify the issue of pulsations across the entire spectrum and that the synthesis method that has been proposed for creating the source signal over a wide band of frequencies [17] and a concept of synthesising a digital signal from analysed Leq FFT results but limited to just the infrasound region [18]. Those investigations found the synthesised results did not agree with our analysis of the original external source data that has been obtained in the field. Utilising a synthesised signal from an averaged (Leq) FFT to produce a steady signal lacks the on/off transitions, transients and variations that existed in the original time record.

For the subject study the original wave files obtained at house 87 from the Cape Bridgewater study [19] was used with a focus on the region of 30 Hz – 1250Hz. The source wave file signal obtained from measurements inside dwelling 87 at Cape Bridgewater, that have been used by several authors as a reference FFT Leq spectrum, was reproduced in the chamber utilising the sound system described above and provided the 1/3 octave band spectra shown in Figure 3. For the frequency range of interest the reproduced signal approximated the original signal as a 10 minute Leq level.

As a pilot study, 9 persons identified as sensitive to wind turbine noise or pulsating low-frequency industrial noise (test group 1) have attended our test chambers to participate in an experiment along the lines of the sensing tests in the format described by Schomer. A control group of 9 persons not previously exposed to turbine noise or pulsating low-frequency industrial noise (including 4 acousticians) participated in the same tests.

The reverberation room, with the addition of acoustic absorption treatment, satisfies the requirements of European Broadcasting Union Technical Document 3276 *Listening Conditions for the Assessment of Sound Programme Material: Monophonic and Two-Channel Sound* [19]. The maximum noise level under that standard for a mono signal is set at 85 dB(A). The distribution of absorption around

the perimeter of the reverberation room leads to the absence of lateral reflections from wall surfaces. As the walls of the chamber are core filled blockwork, from sound intensity and vibration measurements it was established that neither the walls, floor or ceiling of the chamber are generating structure borne noise from the speakers mounted on the baffle in the aperture.




Figure 3: Spectra of Test Sample

The levels that were generated in the room approximate the 1/3 octave band levels obtained in house 87 (in the Cape Bridgewater study) [20] over the range of 40 – 1250 Hz. The response that falls off below 16 Hz reflects the absence of any graphics or parametric equalisation, and the limitations of the A-D convertor.

Table 2 presents the measured sound levels of the generated and ambient levels in the test chamber, with the derived sound level contributions in both the Leq level and the L90 level.

By any of the general measurement parameters used for wind farm assessments, the test signal contribution is at or below the ambient level. Of relevance to researchers of wind turbine noise, the testing had the wind turbine noise contribution as an Leq level of 12 dB(A) in a background level of 23 dB(A).

Weighting	Parameter	Ambient	Test Signal	Test Signal Contribution
Linear	Leq	69	69	60
	L90	57	57	49
dB(A)	Leq	24	24	12
	L90	23	23	9
dB(A) LF	Leq	8	10	8
	L90	-1	7	6
dB(C)	Leq	41	41	36
	L90	31	34	30

Table 2: Measured Levels and Derived Contributions of Test Signal

For the levels that were generated, the testing was undertaken in accordance with Australian Standard AS 1269.4 *Occupational Noise Management, Part 4: Auditory Assessment* [21] and the testing conducted in accordance with the ASA *Ethical Principles of the Acoustical Society of America for Research Involving Human and Non-Human Animals in Research and Publishing Presentations* [22]. An observer was present in the reverberation room during the testing.

The testing was conducted as multiple blind study tests. At no point in time were any of the participants advised what signal (if any) was being applied.

After a period of between 45 seconds to 3 minutes, all the 9 people in test group 1 could sense the presence of the wind turbine signal on 100% of the occasions in which the signal was presented, even though they were unable to hear the signal. At no point in time did any of these test subjects detect any audible signal.

One test subject (from the test group 1) identified a disorientation in the room where there was a perception of a tilt in the floor of about 20°.

The control group were exposed to the same test set up. After a period of some two minutes 2 people (including one a very distinguished Australian acoustician) could identify sensation, whilst the remainder of the control group never detected any sensation.

3.1 Observed Differences in the Sound Field – Hotspots

All the test group 1 subjects were requested to move around the room and identify any hotspots where there was a perception of a greater impact.

Two general areas were identified on either side of the radiating pattern for the baffle speaker systems (see Figure 4).

The test subjects identified the sensation that they were experiencing occurred in different parts of the body.

Seven people from test group 1 noise identified sensation in the back of the neck or the back of the head, and in four subjects there was also a tingling in the legs.

All the people from test group 1 were requested to rotate 360° to identify whether there was any position at which the sensation became stronger.




Figure 4 – Hotspots

In all cases except for two women (one person who has a hearing impairment), the test subjects identified that the greatest sensation occurred for an orientation where the back of the head was towards the speaker baffles but the body was turned at an angle of 45° so that the ear adjacent the baffle propagating sound field was closer to the speakers (see Figure 4).

The test subjects were then presented with audio headphones [6] that provide an SLC 80 attenuation of 11 dB, and then a set of hearing protectors [23] providing an SLC 80 of 26dB.

All test subjects (except the two women noted above) identified there was a difference in the perception of sensation in their head, but had difficulty expressing what that difference was. Both woman identified the test signal produced a sensation across the forehead. The headphones provided a slight difference but when using the ear muffs both participants felt the onset of nausea and the experiment was terminated. Does this result support the observation by Salt [24] of a greater Guinea pig ear response when there was less high frequency masking?

3.2 Manikin Investigation of Hotspots

The use of the manikin in the main chamber at the hotspots (identified by the subjects from test group 1) found no timing difference in terms of the arrival of pulsations for either ear, but that the orientation that produced the greatest level of disturbance to the test subjects revealed a slight pressure difference either side of the head.

For the two hotspot regions and the most sensitive angle to the sound field (135° for the LHS and 225° for the RHS – where 0° is facing the speakers, as shown in Figure 5) the differences were noticeable in the mid band region of 250Hz – 2000 Hz.




Figure 5: Manikin at RHS hotspot set at 0° position (facing speaker baffle)

A one third octave band analysis of the test signal revealed the following polar plots for the manikin (see Figure 5). This Leq pressure differential between the two ears as a result of the pulsating signal may be an area for further research (by others) as suggested by Schomer [11].




Figure 5 – Manikin at hotspots (degrees represent angle of nose to speakers)

3.3 Vibration on Hanging Perspex Panel

Testing of vibration levels inside dwellings in the Cape Bridgewater study, to evaluate whole-body vibration criteria, found insignificant levels of vibration with respect to the relevant Australian or British Standards [25] [26] that may be transmitted to the body.

If sensations are not just restricted to the inner ear and can also include response of the vestibular system of the body, a question arises as to the degree of vibration that may be induced into the body by way of the sound pressure field from turbines.

A perspex panel was suspended off the roof of the test chamber and could be seen to respond to the movement of people in the room and/or closing the nearest door to the panel. The panel required a long settling time (6 – 9 minutes) to return to a stationary position.

Observation of the panel with the application of the test signal found no perceptible vibration. However, examination of the shadow of the panel outline on the floor (from an elevated light) showed movement of the bottom of the panel.

Normal accelerometers cables used for vibration monitoring were found to be microphonic for the sound generated in the room (either by use of charge amplifier or voltage amplifier inputs). Higher sensitive accelerometers used for low-frequency seismic measurements were also found to have cables that resulted in pickup of the inaudible sound generated by the test signal and excessive mass that affected the damping of the panel, thereby presenting difficulty in obtaining vibration measurements using standard instrumentation.

However, the use of DC response accelerometers (Bruel & Kjaer Type 4575) [27] overcame that issue and found vibration levels obtained at the bottom of the swinging perspex panel were less than $1/50^{\text{th}}$ of the 31.5 Hz acceleration level and $1/20^{\text{th}}$ of the 4Hz acceleration levels suggested for the protection of the comfort of individuals subject to low-frequency vibration [25].

Further investigation into the response of the physical pressure wave on individuals is outside our expertise, and may be an area of interest to other researchers with access to the appropriate persons and instrumentation.

4. CONCLUSIONS

Testing of the response of individuals to audible wind turbine noise in recent years has typically utilised a mono noise source with a large bank of speakers in a modified reverberation room or listening environment.

Other testing purporting to assess the impact of infrasound from turbines, has not actually used the infrasound signal but has used either pure tones [28] [29] or a synthesised signal based a result of an FFT Leq analysis of the original signal and incorrectly claimed such noise sources as being “wind farm infrasound”.

Analysis of wind farm noise using wave files of actual wind farm noise (rather than any synthesised format or digitally designed signal) has found the typical FFT acoustical analysis is incorrect in terms of the fundamental formula of $BT=1$ for frequency analysis. That is, a finer resolution or small B requires a large T, and therefore a low temporal resolution to make the result valid. In the infrasound region the pulses are not present long enough to satisfy $BT=1$.

A modification of the Infrasound Logger from Huson Associates (Mark II) incorporates a modified filter and increased sample rate to address signal droop and obtain a faithful wave file to 150Hz.

Analysis of the wave files recorded at Cape Bridgewater reveals the presence of a dynamically pulsed amplitude modulation of the signal that occurs across the entire audible frequency band. The dominant bands where such noise is audible are in the low and mid frequency region.

All our field work to date that provides FFT or 1/3 octave band measurement data in relation to wind turbine infrasound, identified levels well below the nominal threshold of hearing. The limitation of instrumentation and sampling rates to provide an accurate and valid spectrum measurement in the infrasound region has been questioned ($BT=1$).

The previous work by the authors that identified the analysis/signature of pulses that occur at an infrasound rate, leads investigators to view the signal in the time domain and examine/describe/review the method of modulation with dynamically pulse amplitude modulation suggested as a more accurate description.

In endeavouring to reproduce an accurate signal in the time domain we have raised the issue of much higher sampling rates than normally encountered [31].

There are also issues with the creation of wind turbine “infrasound” in the laboratory [4].

The authors are of the opinion that experimental research limited to just wind turbine “infrasound”, whether tones or synthesised digital signals, is a waste of research time and money.

Reproducing and analysing the wind turbine signal including the audible range is an easier and simpler task to undertake and permits the essential work of identifying what creates sleep disturbance and physical impacts from wind turbine noise. Such research should be undertaken inside dwellings (in the field) and (subject to qualification of the sound field) may be undertaken in the laboratory.

Utilising wave files and playback of such signals at inaudible levels without requiring reproduction of infrasound is an easier and simpler task to undertake. The benefits of using a stereo signal for subjective assessment is clearly a superior method and a logical approach for any serious investigation into wind turbine noise.

Our previous paper into the stereo effect [2] found microphones spaced 1.9 metres apart for recording the signal and playback in a hemi anechoic space using line array speakers to be the preferred method by all test subjects for the subjective assessment of external wind turbine noise.

For utilising headphones, the recent testing has confirmed that the use of a stereo head torso (or in this exercise a cheaper version identified as a manikin) is the appropriate mechanism for undertaking further investigation into the subjective effects of wind turbines.

The application of the manikin to support the investigation of the subjective response of wind turbine affected persons in a mono generated sound field, utilising inaudible wind turbine noise, identified slight differences between the “ears” at the position identified by the test group as the hotspots (i.e. a greater perception of sensation with their backs to the sound source and one ear on an angle of 45° to the sound source).

The sensation perceived by the specific sensitive people (rather than the control group) was significantly stronger in the sound field exposed to the entire body when compared to just utilising headphones.

The results of the sensitivity testing require the expertise of other disciplines to explain the mechanisms by which the test subjects perceive the wind turbine noise to their entire body [30] and should be of interest to other researchers.

1. Yokoyama S, Kobayashi T, Sakamoto S & Tachibana H "Subjective experiments on the auditory impression of the amplitude modulation sound contained in wind turbine noise", International Meeting on Wind Turbine Noise, Glasgow 2015.
2. Kelley N.D, "A Proposed Metric for Assessing the Potential of Community Annoyance from Wind Turbines Low-Frequency Noise Emissions", Windpower '87, San Francisco, October 1987
3. Walker B, Celano J, "Progress Report on Synthesis of Wind Turbine Noise and Infrasound", 6th International Meeting on Wind Turbine Noise, Glasgow 2015.
4. Cooper S, "Reproduction of wind turbine infrasound and low frequency noise in a laboratory", Acoustical Society of America Meeting, Boston, June 2017
5. Cooper S, "Subjective perception of wind turbine noise", Acoustical Society of America Meeting, Boston, June 2017, ASA POMA Vol 30/10.1121/2.0000639
6. Audio-Technica, "ATH-M79x Studio Monitoring Headphones", <http://audio-technica.com.au/products/ath-m70x/>
7. Bruel & Kjaer., "Sound Quality Head and Torso Simulator Type 4100", <https://www.bksv.com/-/media/literature/Product-Data/bp1436.ashx>
8. Michaud D, "An evaluation of how nightly variations in wind turbine noise levels influence wrist actigraphy measured sleep patterns", Acoustical Society Meeting, Salt Lake City, May 2016
9. Nissenbaum MA, "Industrial wind turbines and adverse health effects: Where we are, where we need to go, and the need for regulations and predictive models to recognize human physiology" Acoustical Society Meeting, Salt Lake City, May 2016
10. McMurty R.Y, "Patient Centered Medicine and Soundscape – A bridge between clinicians and acousticians", Acoustical Society Meeting, Salt Lake City, May 2016
11. Health Canada, Wind Turbine Noise and Health Study: Summary of Results", <https://www.canada.ca/en/health-canada/services/environmental-workplace-health/noise/wind-turbine-noise/wind-turbine-noise-health-study-summary-results.html>
12. Schomer P.D, Erdreich J, Boyle P & Pamidighantam P, "A proposed theory to explain some adverse physiological effects of the infrasonic emissions at some wind farm site", 5th International Conference on Wind Turbine Noise, Denver August 2013
13. Cooper S, "Threshold of hearing v threshold of sensation for low frequency and infrasound", Acoustical Society of America Meeting, Salt Lake City, May 2016, ASA POMA vol 26/10.1121/2.0000432
14. Cooper S, "Reproducing wind farm infrasound for subjective testing – Just how accurate is the reproduced signal?", Acoustical Society of America, Salt Lake City, May 2016
15. Cooper S, "Wind Farm Infrasound – Are we measuring what is actually there or something else? (part 2)", Acoustical Society of America Meeting, Salt Lake City, May 2016
16. Cooper S, Chan C, "Can inaudible and audible low level infrasound and low frequency noise be an acoustic trigger of the startle reflex?", Acoustical Society of America Meeting, Hawaii, December 2016
17. Hansen K, Walker B, Zajamsek B & Hansen C, "Perception and annoyance of low frequency noise versus infrasound in the context of wind turbine noise", 6th International Meeting on Wind Turbine Noise, Glasgow April 2015
18. Tonin R & Brett J, "Response to Simulated Wind Farm Infrasound Including Effect of Expectation, International Meeting on Wind Turbine Noise, Glasgow 2015.
19. The Acoustic Group, "The Results of an Acoustic Testing Program, Cape Bridgewater Wind Farm", Dec 2014 <http://waubrafoundation.org.au/resources/cooper-s-acoustic-group-results-cape-bridgewater-acoustic-investigation/>
20. European Broadcasting Union Technical Document 3276 "Listening Conditions for the Assessment

- of Sound Programme Material: Monophonic and Two-Channel Sound, 1998
21. Australian Standard AS 1269.4 "Occupational Noise Management, Part 4: Auditory Assessment", Standards Australia, 2005.
 22. Acoustical Society of America, "Ethical Principles of the Acoustical Society of America for Research Involving Human and Non-Human Animals in Research and Publishing and Presentations", http://acousticalsociety.org/for_authors/ethical_principles
 23. "EMLU 60 Hearing Protector",
<https://www.scotssafety.com/en/anzp/DocumentandMedia1/Protector%20EMLU60%20HB%20Ear%20muffs%20Datasheet%20ANZ.pdf>
 24. Salt A. "Perception-based protection from low frequency sounds may not be enough", Internoise 2012, New York
 25. Standards Australia, "AS 2670.2-1990, Evaluation of human exposure to whole-body vibration, Part 2: Continuous and shock-induced vibration in buildings (1 to 80 Hz)", Standards Australia 1990.
 26. British Standard 6472-1992 "Guide to evaluation of human exposure to vibration in buildings (1Hz to 80 Hz)". British Standards Institute
 27. Bruel & Kjaer, "DC Response Accelerometer Type 4575", <https://www.bksv.com/-/media/literature/Product-Data/bp2170.ashx>
 28. Crichton F, Dodd G, Schmid G, Gamble G & Petrie K, "Can Expectations Produce Symptoms From Infrasound Associated With Wind Turbines?", *Health Psychology*, 33(4), 360-364 (2014)
 29. Crichton F, Dodd G, Schmid G, Gamble G, Cundy T & Petrie K, "The Power of Positive and Negative Expectations to Influence Reported Symptoms and Mood During Exposure to Wind Farm Sound?", *Health Psychology*, American Psychological Association 2013
 30. Cooper S.E, "Can inaudible and audible low level infrasound and low frequency noise be an acoustic trigger of the startle reflex?", Acoustical Society of America Meeting, Hawaii, December 2016
 31. Cooper S.E., "Are Sample Rates for Wave File Recordings Too Low for Transient Signals?", Acoustical Society of America Meeting, Boston, June 2017



Ruby Holborn <rubyholborn@gmail.com>

Copyright permission from Master Resource

7 messages

Ruby Holborn <rubyholborn@gmail.com>

Fri, Mar 30, 2018 at 4:07 PM

To: kodaisl@rogers.com

Cc: Ruby Holborn <rubyholborn@gmail.com>

Thank You Sherri for your permission, but the South Dakota Public Utilities rejected my information because I did not have the copyright permission from Master Resource, the publisher of the article.

I am not able to locate an email for Master Resource so could you please forward this to them?

Thank You ! :

I would like your permission **quickly** to reproduce material from Master Resource for the South Dakota Public Utilities Commission in the matter of the permitting process of industrial wind turbines. I need your copyright permission from Master Resource so that it can be placed on our SD docket. The article that I would like to reprint is the Sherri Lange & Steven E. Cooper interview:

Master Resource

Sensing but Not Hearing: The Problem of Wind Turbine Noise

(Interview with acoustician Steven Cooper, AU

February 2, 2018

I need your permission in just a few days, before the deadline to submit material to our SD PUC.

"Thank You!"

Regards,

George L. Holborn

Gary, South Dakota

rubyholborn@gmail.com

Sherri Lange <kodaisl@rogers.com>

Fri, Mar 30, 2018 at 4:38
PM

Reply-To: Sherri Lange <kodaisl@rogers.com>

To: Ruby Holborn <rbyholborn@gmail.com>, Rob Bradley
<rbradley@iertx.org>

Dear Ruby

I can foresee no problem whatsoever. Please consider this your formal permission to reprint, and use as you see fit.

I will copy Robert Bradley, who is the owner and publisher and had first permission to use the interview, and publish. It has since been picked up on various blogs, such as Friends Against Wind, in France.

February 2, 2017

Sensing but Not Hearing: The Problem of Wind Turbine Noise

**Sensing but Not Hearing: The Problem of
Wind Turbine Noise**

Interview with acoustician Steven Cooper, AU.

As far as I am personally concerned, as the author, you have full permission. It is my original work, and it was offered to Master Resource blog, and I regularly appreciate the offer of MR publishing my original un-compensated for, writing.

Let me know, and Rob, kindly copy me with your reply.

Kind regards,

Sherri

Sensing but Not Hearing: The Problem of Wind Turbine Noise (Interview with acoustician Steven Cooper, AU) - Master Resource

Sensing but Not Hearing: The Problem of Wind Turbine Noise (Interview with acoustician Steven Cooper, AU) - Master Re...

Editor Note: Steven Cooper has advanced our understanding of how people react to real recorded pressure pulsatio...

Sherri Lange
CEO, NA-PAW, North American Platform Against Wind Power
Executive Director, Canada, Great Lakes Wind Truth
VP Canada, Save the Eagles International
kodaisl@rogers.com
www.na-paw.org
Twitter: #torwinaction

Please note that messages to these lists are intended for the private members and invitees only. If the material is informational, please feel free to circulate. If posting, please consider copyright laws. Please note that not all the views contained in circulation of news are those of NA-PAW. If you have received this in error, please respond to the writer and delete the message.

Thank you!



From: Ruby Holborn <rubyholborn@gmail.com>
To: kodaisl@rogers.com
Cc: Ruby Holborn <rubyholborn@gmail.com>
Sent: Friday, March 30, 2018 5:07 PM
Subject: Copyright permission from Master Resource
[Quoted text hidden]

Rob Bradley <rbradley@iertx.org>

Fri, Mar 30, 2018 at 5:50 PM

To: Sherri Lange <kodaisl@rogers.com>, Ruby Holborn
<rubyholborn@gmail.com>

Permission granted, but we are really open source.

- Rob

From: Sherri Lange <kodaisl@rogers.com>

Sent: Friday, March 30, 2018 4:39 PM

To: Ruby Holborn <rubyholborn@gmail.com>; Rob Bradley
<rbradley@iertx.org>

Subject: Re: Copyright permission from Master Resource


Dear Ruby

I can foresee no problem whatsoever. Please consider this your formal permission to reprint, and use as you see fit.

I will copy Robert Bradley, who is the owner and publisher and had first permission to use the interview, and publish. It has since been picked up on various blogs, such as Friends Against Wind, in France.

February 2, 2017

Sensing but Not Hearing: The Problem of Wind Turbine Noise



**Sensing but Not Hearing: The Problem of
Wind Turbine Noise**

Interview with acoustician Steven Cooper, AU.

[Quoted text hidden]



Virus-free. www.avast.com

Sherri Lange <kodaisl@rogers.com>

Sat, Mar 31, 2018 at 8:33
AM

Reply-To: Sherri Lange <kodaisl@rogers.com>
To: Rob Bradley <rbradley@iertx.org>, Ruby Holborn
<rubyholborn@gmail.com>

Thanks, Rob.

Enjoy your Easter weekend!

Sherri

*Sherri Lange
CEO, NA-PAW, North American Platform Against Wind Power
Executive Director, Canada, Great Lakes Wind Truth
VP Canada, Save the Eagles International
kodaisl@rogers.com
www.na-paw.org
Twitter: #torwinaction*

Please note that messages to these lists are intended for the private members and invitees only. If the material is informational, please feel free to circulate. If posting, please consider copyright laws. Please note that not all the views contained in circulation of news are those of NA-PAW. If you have received this in error, please respond to the writer and delete the message.

Thank you!



From: Rob Bradley <rbradley@iertx.org>
To: 'Sherri Lange' <kodaisl@rogers.com>; 'Ruby Holborn' <rubyholborn@gmail.com>
Sent: Friday, March 30, 2018 6:50 PM
Subject: RE: Copyright permission from Master Resource
[Quoted text hidden]

Ruby Holborn <rubyholborn@gmail.com>
To: Sherri Lange <kodaisl@rogers.com>
Cc: Rob Bradley <rbradley@iertx.org>

Sat, Mar 31, 2018 at 9:46 AM

SD PUC Docket EL18-003 should now place this reference material on their website.

Thank You for your timely permission.

Regards,
George & Ruby Holborn
Gary, So.Dak.

Sent from my iPad

[Quoted text hidden]

[Quoted text hidden]
[Quoted text hidden]

[Quoted text hidden]
[Quoted text hidden]
[Quoted text hidden]
<image001.jpg>

<image002.png>

Sensing but Not Hearing: The Problem of Wind Turbine Noise

Interview with acoustician Steven Cooper, AU.

[Quoted text hidden]



Virus-free. www.avast.com

<image001.jpg>

<image002.png>

Sherri Lange <kodaisl@rogers.com>

Sat, Mar 31, 2018 at 3:06
PM

Reply-To: Sherri Lange <kodaisl@rogers.com>

To: Ruby Holborn <rubyholborn@gmail.com>

Cc: Rob Bradley <rbradley@iertx.org>

Thank you so much, Ruby. It is important that these pieces get around, and to the places where decisions are made.

Kind regards,

Sherri

Sherri Lange

CEO, NA-PAW, North American Platform Against Wind Power

Executive Director, Canada, Great Lakes Wind Truth

VP Canada, Save the Eagles International

kodaisl@rogers.com

www.na-paw.org

Twitter: #torwinaction

Please note that messages to these lists are intended for the private members and invitees only. If the material is informational, please feel free to circulate. If posting, please consider copyright laws. Please note that not all the views contained in circulation of news are those of NA-PAW. If you have received this in error, please respond to the writer and delete the message.

Thank you!



From: Ruby Holborn <rubyholborn@gmail.com>
To: Sherri Lange <kodaisl@rogers.com>
Cc: Rob Bradley <rbradley@iertx.org>
Sent: Saturday, March 31, 2018 10:46 AM

[Quoted text hidden]

[Quoted text hidden]

Sherri Lange <kodaisl@rogers.com>

Sat, Mar 31, 2018 at 3:13
PM

Reply-To: Sherri Lange <kodaisl@rogers.com>
To: Ruby Holborn <rubyholborn@gmail.com>

Is this the file? I would like to record that it is there, also, for our files. I did not see it yet.
Please let us know?

Kind regards,

Sherri

<http://puc.sd.gov/Dockets/Electric/2018/el18-003comments.aspx>

*Sherri Lange
CEO, NA-PAW, North American Platform Against Wind Power
Executive Director, Canada, Great Lakes Wind Truth
VP Canada, Save the Eagles International
kodaisl@rogers.com
www.na-paw.org
Twitter: #torwinaction*

Please note that messages to these lists are intended for the private members and invitees only. If the material is informational, please feel free to circulate. If posting, please consider copyright laws. Please note that not all the views contained in circulation of news are those of NA-PAW. If you have received this in error, please respond to the writer and delete the message.

Thank you!



From: Ruby Holborn <rubyholborn@gmail.com>

To: Sherri Lange <kodaisl@rogers.com>

Cc: Rob Bradley <rbradley@iertx.org>

Sent: Saturday, March 31, 2018 10:46 AM

[Quoted text hidden]

[Quoted text hidden]


#1 of 3

RECEIVED

MAY 03 2018

**SOUTH DAKOTA PUBLIC
UTILITIES COMMISSION**

To- Amanda Reiss



GateHouse Media™

To: South Dakota Public Utilities Commission Staff

Re: Consent to redistribute material ("In the Shadow of Wind Farms")

April 4, 2018

To whom it may concern,

I am the editor and one of the authors of the newspaper investigation titled, "In the Shadow of Wind Farms," that was published online and in print publications nationwide in December 2017.

I understand that George and Ruby Holborn wish to submit this investigation to the South Dakota Public Service Commission. I further understand that the Commission requires Mr. and Mrs. Holborn to obtain explicit consent from the copyright holder of "In the Shadow of Wind Farms," for the reproduction/redistribution of this work.

GateHouse Media holds the copyright to this work. As a top editor at GateHouse Media who is authorized to make this decision, I hereby provide Mr. Holborn consent on behalf of GateHouse Media to reproduce "In the Shadow of Wind Farms" in order that it may be submitted to your Commission.

Don't hesitate to contact me should you have further questions regarding the investigation or my consent to have this work submitted to the Commission.

Cordially,

Emily Le Coz



GateHouse Media™

To: South Dakota Public Utilities Commission Staff
Re: Consent to redistribute material ("In the Shadow of Wind Farms")

Feb. 26, 2018

To whom it may concern,

I am the editor and one of the authors of the newspaper investigation titled, "In the Shadow of Wind Farms," that was published online and in print publications nationwide in December 2017.

I understand that George Holborn wishes to submit this investigation to the South Dakota Public Service Commission and that my explicit consent for the reproduction/redistribution of my work for this purpose is required. **I hereby provide that consent.**

Don't hesitate to contact me should you have further questions regarding the investigation or my consent to have it submitted to your commission.

Cordially,

Emily Le Coz

National Data Projects Editor, GateHouse Media
(662) 871-4433
elecoz@gatehousemedia.com




December 14, 2017

Kansas, Michigan, New York, Oklahoma, U.S., Wisconsin

In the shadow of wind farms

BY EMILY LE COZ & LUCILLE SHERMAN, gatehousenews.com

A six-month GateHouse Media investigation found that wind developers representing some of the world's biggest energy companies divide communities and disrupt the lives of residents forced to live in the shadow of their industrial wind farms.



[1]

An industrial wind turbine stands 476 feet tall in Mason County, Michigan. | Lucille Sherman

Reporters interviewed more than 70 families living near three dozen current or proposed wind farms. They also spoke to 10 state and local lawmakers, read hundreds of pages of public-service-commission records about wind projects, reviewed court filings in seven wind-related lawsuits and inspected lease agreements from at least eight wind farms.

GateHouse Media also identified through public documents and media reports an additional 400 families living near industrial wind turbines that have publicly complained about

shadow flicker, noise, health problems and/or misleading statements by wind companies in an effort to solicit land agreements.

The investigation found that companies convince landowners to sign away their property rights for generations based on the promise of potential profits and the minimization of potential problems associated with wind turbines.

Those problems include shadow flicker, loud noises and low-frequency vibrations that have driven dozens of families from their homes. Many of them claim to have suffered serious health issues from the turbines before departing. Some say they'll never be the same.

The wind industry has known about these issues for years – many of its contracts contain clauses acknowledging these effects – but it denies turbines affect human health, even as complaints mount nationwide.

Landowners often overlook potential problems until it's too late. Many who sign contracts can't terminate the agreements, even if they later beg for relief from what they deem intolerable living conditions. Some covenants bar people from suing or even publicly criticizing the projects.

Those who don't sign agreements can face the same impact of living near wind turbines erected on neighboring properties. But they receive no compensation for the shadow flicker, noises and vibrations.

Many of these residents have become vocal opponents of the industry. Dozens of them, including the Shineldeckers, have sued the wind companies for destroying their quality of life.


Wind developers have settled more than a half-dozen such cases nationwide, even while admitting no wrongdoing. Among the companies to settle is Michigan-based Consumers Energy, which owns Lake Winds Energy Park. The Shineldeckers were among several neighbors who sued the company.

Consumers Energy spokesman Terry DeDoes declined repeated requests to answer questions for this story. The company previously denied the Shineldeckers' claims in court filings.

Proposed wind projects also have fractured rural communities across America, pitting neighbor against neighbor in fights over property rights and money.

Many worry about the impact these turbines will have on their homes – some families interviewed have moved out of their houses after wind farms started operating; others have stayed but suffer from shadow flicker, noises and vibrations.

Elected officials tasked with voting on these developments have, in many cases, signed their own contracts with the wind companies, raising concerns about conflicts of interest.



[2]

Cary and Karen Shindelcker in their Mason County, Michigan, home. | Lucille Sherman | GateHouse Media

Among the investigation's findings:


Despite a growing chorus of complaints, the wind industry has expanded largely unopposed. Ten years ago, less than 300 industrial wind farms dotted the U.S. landscape. Today, more than 1,000 exist. Much of the growth has been funded by American taxpayers. Billions of dollars in state and federal incentives have made wind farms so profitable that companies are racing to develop them before the handouts disappear.

Industrial wind turbines generate countless complaints nationwide about sleep disturbances, migraines, nausea, ear pressure, blurred vision, tinnitus and heart palpitations. Rampant reports about such effects from the Shirley Wind Farm in Brown County, Wisconsin, prompted the local Board of Health to declare the turbines a human health hazard.

Wind industry officials have denounced people who complain about these symptoms, calling them misinformed or "anti-wind." Some wind companies offer money or other concessions to frequent complainers, often in exchange for silence and a waiver for turbine-related claims. "I call it a shut-up clause," said Jim Miller of South Dakota, who refused to sign such an agreement with Florida-based NextEra.

Wind developers have used what some landowners describe as misleading tactics to get their contracts signed. Attorneys asked to review several such contracts called them one-sided, giving wind companies sweeping control over people's property with few rights for the landowner.

Wind farms have divided communities across America. Contracted landowners eyeing profits spar with neighbors opposing turbines near their backyards. Lifelong friendships can end. Families sometimes fray. Hopkinton, New York, resident Janice Pease said she stopped talking to relatives who support a proposed wind farm in their town. Pease adamantly opposes it.



[3]

Turbines from the Glacier Hills Wind Park in Columbia County, Wisconsin, churn in the late afternoon sun. | Arturo Fernandez | GateHouse Media

Wind industry denies claims

GateHouse Media reached out to seven wind energy companies, including some of the nation's largest, and two nonprofit groups that support the wind industry. Those representatives denied almost all of the investigation's findings.

Every wind industry official interviewed said that relatively few people complain about wind turbines compared to the thousands of Americans living peacefully among the structures.

"We have 1,300 turbines in operation across the United States," said Duke Energy spokeswoman Tammie McGee. Except for one wind farm in Wisconsin, "we don't see these types of complaints at our other turbines."

Many of the people who do complain, several representatives said, are well-known among industry insiders and comprise a small but vocal group of anti-wind activists.

"There are a good number of people who seem to pop up in different states and fight any wind project they can find," said Dave Anderson of the Energy and Policy Institute, a nonprofit [?] group that supports the renewable energy industry.

Some wind representatives questioned why GateHouse Media would write this story, citing study after study finding no evidence that wind turbines cause health problems.

When asked about the studies that do establish a link, those same wind officials disputed the validity of those papers and the credentials of the researchers.

People might be annoyed by wind turbines, several wind representatives said. But they're not getting sick from them.

"We do recognize that they can be bothersome to people, and our companies try to do things to minimize that both pre- and post-construction," said Mike Speerschneider, senior director of permitting policy and environmental affairs for the American Wind Energy Association in Washington DC. "But is it making people sick? Is it having physiological and medical impacts? No."

Rather than divide communities, they said their projects improve the lives of all residents. Some towns hold festivals commemorating their wind farms. Enyo Renewable Energy Principal Christine Mikell mentioned the Wind Fest in Spanish Fork, Utah, which hosts a nine-turbine wind farm.

"We have hundreds of landowners who are pleased to have us come to their communities," said Bryan Garner of Florida-based NextEnergy Resources, the biggest wind energy producer in America with more than 100 wind farms.

Wind representatives all declined to discuss specific contracts, saying they are private agreements between the companies and the landowners. In general, though, most officials called them relatively standard lease agreements.

Garner said NextEra even pays landowners the cost of hiring private attorneys to review the contracts.

Wind company representatives also said they follow all local, state and federal rules regarding wind farm development. They said they conduct extensive sound and environmental testing. And they said they reach out early and often to community members.

"We make an effort to be available to answer questions, to address concerns in a variety of forms, over the years-long process of development," said Paul Copleman, a spokesman for Spanish utility giant Iberdrola, one of the world's largest wind farm operators.

To be sure, wind farms harness a clean and renewable energy source that lessens the country's dependence on fossil fuel and foreign oil.

Improved technology has made today's turbines more efficient and thus cheaper to run, lowering energy costs for everyone.

Communities can also benefit financially from wind farms. The construction of these multi-million-dollar projects employs hundreds of temporary workers and adds new, taxable revenue to local and state coffers.

Some communities get fixed, annual payments instead of tax revenues. Barber County, Kansas, for example, earns \$500,000 a year in such payments from the Flat Ridge Wind Project. It also gets \$5,000 for every megawatt of electricity the project produces.

Landowners, too, can make a lot of money, receiving as much as \$14,000 annually for every turbine they host. Perry Burchill of Luverne, North Dakota, was able to retire from farming two years after the Ashtabula Wind Energy Center erected 13 turbines on his land.

Burchill said the turbines don't bother him.

His neighbor, Mark Askerooth, also hosts a turbine but says he notices the noise, and it bothers him.

"The wind farm is wonderful as far as the local economy goes," Askerooth said. "But if I'd have known at the time what I know now, I don't think I would have done it. They are not telling the truth when they say the sound doesn't affect you. They intimated when we signed the agreement that we wouldn't notice the noise. But we definitely notice it."

A booming industry

Wind energy development has soared in the past decade. Industrial turbines that once occupied mainly barren landscapes like California's Mojave Desert now stretch from the western plains to the rolling hills of New England.

The majority straddle the Midwest, where average wind speeds clock higher and stronger inside a column snaking from the Texas panhandle north to the Dakotas.

Residents accustomed to unimpeded vistas of prairie grass and farmland now see massive turbines churning in the breeze.

"When we turn to the west now, we're looking right at a forest of machines," said Geoffrey Standing Bear, principal chief of the Osage Nation in Oklahoma.

The Osage Nation has fought to block wind development on its ancestral lands, but its efforts failed to prevent construction of an 84-turbine project that started operations in 2015.

The tribe believes the turbines stand atop ancient burial grounds. They also say the structures violate their religious teachings, which hold the horizon as a sacred meeting place of heaven and earth.

They still worship the horizon in special, sunrise ceremonies. The turbines have ruined those gatherings, they said.

"It's really a fight between those who want to take advantage of the money and those who believe they're an eyesore and just interfere with a way of life," Standing Bear said. "It's not like Greenpeace versus the others. We're Native Americans; we consider ourselves environmentalists as well."

Ten years ago, just 300 wind farms comprising 15,000 turbines dotted the country, according to data from the U.S. Energy Information Administration.


Today, those numbers have swelled to more than 1,000 wind farms in 41 states representing over 53,000 turbines, EIA data show.

Osage Wind is one of more than 40 industrial wind farms in Oklahoma, which ranks third in the nation for wind energy production.

Only the Southeast, with its unfavorable wind conditions and lack of renewable energy targets, remains relatively free of industrial wind farms.

That's starting to change. Newer, taller turbines can harness wind where old technology couldn't. The first large-scale project in North Carolina went live last year – 104 turbines towering 500 feet now produce energy for the online retailer Amazon.

Developments like these catapulted wind energy's contribution to the nation's electrical grid. In 2007, wind provided less than 1 percent to the grid. In 2016, it rose to 5.6 percent. It's estimated to reach 10 percent by the end of the decade.



[4]

Left: Osage Nation Principal Chief Geoffrey Standing Bear | Geoffrey Standing Bear | Submitted | Right: Highlighted satellite imagery of a section of the Osage Wind Project. | Bing.Com/Maps | Used with permission from Microsoft | www.bing.com/maps

Incentives and mandates

Two factors fueled the boom.

First, states began mandating electricity from green sources. Renewable Portfolio Standards require utilities to either purchase or produce anywhere from 2 to 55 percent of their power from renewable energy.

Twenty-nine states now have mandatory standards; eight others have voluntary targets. The majority passed after 2000.

Second, the federal government started incentivizing wind energy development with the Renewable Energy Production Tax Credit in 1992.

Other programs followed, including the Investment Tax Credit, 1705 Energy Loan Guarantee, and Section 1603 Grants, all of which either started or expanded under the American Recovery and Reinvestment Act of 2009.

Wind companies will have benefited from an estimated \$32 billion in Production Tax Credits alone between 2008, when the industry exploded, and 2020 when the program is phased out, according to data from the U.S. Congressional Joint Committee on Taxation.

Companies have received an additional \$13 billion in Section 1603 payments since 2009, U.S. Treasury data show.

Although wind energy remains relatively new, its major developers are not. Established fuel titans like NextEra, Iberdrola, BP and Duke Energy are among the industry's biggest players.

By bundling federal giveaways with state and local subsidies, companies can slash wind farm development costs by more than half.

Taxpayers funded nearly two-thirds of Caithness Energy's Shepherds Flat Wind Farm. It has 338 turbines across 32,100 acres in northern Oregon.

The company received more than \$1.2 billion in state and federal incentives for the \$1.9 billion project, one of the largest in the nation.

Shepherds Flat was flagged in a memo to then-President Barack Obama by his advisors as an example of developers abusing the subsidies by "double dipping."

The 2010 memo also noted the connection between tax incentives and wind development: Each time wind tax credits expired, industry investment slowed, only to resume upon their renewal.

The Production Tax Credit program will expire again – and potentially forever – in 2020. But it's unlikely to slow the boom this time. Cheaper wind technology and increased demand for renewables will continue to drive the sector, said AWEA spokesman Evan Vaughn.



[5]

Sue Hobart, right, consoles Nancy Shea of Burlington, Vermont, during a wind-farm protest at the Falmouth Village Green in February 2016. | Merrily Cassidy | Cape Cod Times file

Forced to move

As the wind industry continues to expand, so do its critics.

Hundreds of residents nationwide have claimed industrial wind turbines make them sick. Several families say the structures have forced them from their homes.

Ed and Sue Hobart sold their retirement home in Falmouth, Massachusetts, after Notus Clean Energy erected a turbine near their property. They say it triggered nausea, dizziness, migraines and anxiety.

Dozens of other Falmouth residents reported similar symptoms to the town Board of Health.

“People don’t give up their homes for no reason,” Ed Hobart said, responding to claims the symptoms were all in his head. “It had financial and emotional and health impacts on me and my wife that we will never be fully recovered from.”

Jeff and Sandra Wolfe got sick after turbines from the Golden West Wind Energy Center started spinning near their property in Calhan, Colorado, the couple said.

The Wolfes moved 300 miles away to escape the tinnitus, headaches, anxiety and sleep disturbances they developed, said Sandra Wolfe. Three other families in the same wind farm told GateHouse Media they left their homes for similar reasons.

"There is no reason to hate them unless they make you sick," Sandra Wolfe said of the 145 turbines in the project, most of which she could see from her house. "And they made us sick."

Three families also left their homes in the Shirley Wind farm near Green Bay, Wisconsin, after complaining about numerous health issues and sleep problems they blamed on the eight-turbine project.

"We had to choose between our home and our health," said Susan Ashley, the matriarch of one of those families. "We chose our health."

Dozens of other residents also complained about Shirley Wind, so much so that the local board of health declared it a human health hazard in 2014.

"There is no question there are negative effects," said Jay Tibbetts, a physician and member of the Brown County Board of Health. "Even if you don't perceive any symptoms, it doesn't mean you're not affected. There are subtle changes that can take place in your body."

Duke Energy, which owns Shirley Wind, disputes its turbines constitute a human health hazard.

"These are very common symptoms," said Duke spokeswoman Tammie McGee. "They could be caused by anything."

Unlike the wooden windmills of Holland, industrial turbines are sleek structures that can reach heights of a 50-story skyscraper. A single blade can surpass the wingspan of a Boeing 747.

Some turbines can generate a noise likened to the engine of a jet airplane that never lands, a whooshing roar or a rhythmic "whomp, whomp, whomp."

The air-pressure change caused when their spinning blades pass their pedestals has been linked to migraines and sleep disturbances. In bats that fly too close, the effect can fatally burst the capillaries in their delicate lungs, killing them.

When the sun passes behind those blades, it creates a strobe-like phenomenon called shadow flicker that can disorient and nauseate those forced to live with it.

Shadow flicker

Shadow flicker forced Rod and Sandy Kok out of their ranch-style home in rural Randolph, Wisconsin.

The Koks had signed a lease agreement with NextEra subsidiary FPL Energy in 2004. In exchange for hosting an industrial wind turbine in their backyard, the retired couple would receive annual payments of \$5,000.

FPL representatives said they would “barely notice” the massive structure, the Koks recalled. They said Wisconsin-based WE Energies made the same claim after it purchased the wind development and land contracts from FPL in 2007.

But when the Glacier Hills Wind Park started operating in 2011, Sandy Kok said she developed nausea, headaches and vertigo from the persistent shadow flicker infiltrating nearly every room in the house.

The family logged 330 hours of the strobe-like effect the first year alone, according to a complaint filed with the Wisconsin Public Service Commission.

The flicker came not only from the turbine in their yard but from four others nearby. Sandy said she spent hours each day hiding in the basement until the sun shifted or the clouds came.

After the Koks discovered they couldn’t terminate the agreement, they begged WE Energies for relief.

The company tried several methods to mitigate the shadow flicker, but none of them worked to the couple’s satisfaction, according to a February 2013 Wisconsin Public Service Commission document.

WE Energies installed room-darkening shades on the family’s windows, but the flicker peeped through the cracks. The company also halted one of its turbines during the offending hours, but nearby turbines continued to spin and cast shadows.

WE Energies refused to stop the other turbines, estimating it would lose up to \$76,000 annually in profits, the state record shows.

So the flicker continued. And Sandy’s symptoms worsened.

WE Energies eventually purchased the Kok’s home in November 2013 so the couple could move away. The Koks said they got a fair price, but they never wanted to leave in the first place. They raised their children there. They planted every tree in the yard.

“It’s hard to talk about it,” Sandy said. “We try not to think about it anymore. But sometimes you go to these dark places. It still affects you.”

WE Energies spokeswoman Cathy Schulze said the company worked closely with the community and the state Public Service Commission on project development and turbine placement.

“We continue our commitment to being good neighbors, and work with any impacted homeowners one-on-one to mitigate concerns related to our operations,” Schulze said in an email.

Shadow Flicker



Shadow flicker infiltrated the Kok's home some 300 hours a year. It happened when the sun passed behind nearby turbines in the Glacier Hills Wind Park in Columbia County, Wisconsin. | The Koks | Submitted

Vibrations

Low-frequency sound waves from the Lake Winds Energy Park forced Cary and Karen Shineldecker to leave their home in Mason County, Michigan, the couple said.

The Shineldeckers had opposed Lake Winds prior to its construction; they worried about the effects its 56 turbines would have on nearby families, including their own.

Cary spoke at county meetings and urged local officials to pass tighter wind regulations, ones that would keep turbines away from his home.

His activism earned the family enemies in the community, especially among neighbors who signed up for the turbines, the couple said. They lost friends over the issue and believe someone poisoned their dogs in retaliation.

Despite Cary's efforts, Consumers Energy erected four turbines within a half-mile of the family's two-story farmhouse – the closest loomed less than 1,200 feet away.

The turbines began operating on Thanksgiving Day 2012, and the Shineldeckers immediately noticed problems, they said.

At first it was the noise – loud whistling and whooshing sounds. But soon they could feel thumping vibrations that resonated through the walls of their home like bass-heavy music from a distant, passing car.

This feeling, they said, bothered them during the day and kept them awake at night. They developed headaches, ear aches and pressure behind their eyes.

The couple described it as Chinese water torture – bearable in the moment but insufferable over time.

“You go months and months and months without sleep, and pretty soon, you’re not even the person you recognize,” Cary said. “I literally broke down and cried in front of people, and I’m not proud to say that.”

Karen, a middle-school science teacher started grinding her teeth at night; she had to wear bite splints. Cary, an engineer, started losing concentration during the day; he was demoted at his job.



They took sleeping pills and anti-anxiety medication. They moved their bedroom into the basement to hide from the effects, but they still couldn’t escape.

The Shineldeckers didn’t suffer alone. Consumers Energy received 128 complaints about its wind farm in the first year of operation, according to Mason County records.

After about two years living with the turbines, the Shineldeckers moved out. They stayed with a family friend until they could build a new house four miles away.

Consumers Energy spokesman Terry DeDoes repeatedly declined to answer questions for this story but emailed a written statement that touted the company’s renewable energy projects and community engagement.

“It was emotionally devastating to be forced out of your house,” Cary said. “We moved to that house when our oldest son was 5 years old. It was a really nice place to live and raise a family.”



[6]

Left: Cary and Karen Shineldecker stand outside their new home four miles from their previous home. | Lucille Sherman | GateHouse Media | Right: Cary and Karen

Shineldecker slept in their basement for two years to escape the low-frequency vibrations they said they could feel from nearby turbines in the Lake Winds Energy Park in Mason County, Michigan. | Cary Shineldecker | Submitted

Health impact debate

Even as wind farm inhabitants nationwide blame industrial turbines on a cascade of health problems, experts remain split on the veracity of their complaints.

Numerous researchers claim to have established a link between wind turbines and symptoms such as migraines, earaches, tinnitus, eye pressure, dizziness, nausea and sleeplessness; many other researchers conclude no such evidence exists.

“I wish it was something we could have gotten used to,” said Illinois resident Ted Hartke, who moved out of his home in the California Ridge Wind Farm. “You sit in bed and pray to God you can get used to the noise. But it got worse.”

But even as complaints mount across the nation, the wind industry steadfastly denies turbines impact human health.

“We are aware of some of the cases where individuals come to believe that wind turbines are the cause of their health concerns, and we feel great sympathy for anyone who is suffering from illness of any kind,” said Dahvi Wilson of Apex Clean Energy, which owns several wind farms nationwide.

But, Wilson said, science doesn’t support their claims. And until it does, the company will continue to build wind farms based on current best practices.

The wind industry frequently cites a 2014 Health Canada study that found no direct association between health problems and wind turbines. The study involved more than 1,200 residents in 18 wind farms.

But the same study also found wind turbines “highly annoy” about one in 10 people, especially those living closest to the structures and those exposed to turbine noises exceeding 35 decibels.

That annoyance is “statistically related” to reports of migraines, tinnitus, dizziness and high blood pressure.

“Although Health Canada has no way of knowing whether these conditions may have either pre-dated, and/or are possibly exacerbated by, exposure to wind turbines,” researchers said, “the findings support a potential link between long term high annoyance and health.”

Experts on the other side of the debate also cite the Health Canada study, saying it proves turbines sicken people – even if indirectly, because of their annoyance factor.

But they criticize the study’s use of only an A-weighted sound meter, which doesn’t measure the low frequencies blamed for some of the worst health problems.

To measure those frequencies, you need a C-weighted scale, said Jerry Punch, an audiologist and professor emeritus at Michigan State University who also has researched the issue.



“The A-weighting filter is used by all wind companies and everybody who studies wind turbine noise,” Punch said, “and it filters out the sounds that are really the most problematic.”

Researchers using low-frequency meters have found a link between wind turbines and “sensations of uneasiness and personal disturbance,” as well as “extreme pressure” and “headache or nausea or dizziness.”

One of the first to do this was Neil Kelley, a now-retired scientist from the National Wind Technology Center in Denver. The U.S. Department of Energy and NASA hired Kelley three decades ago to investigate complaints about their wind turbine near Boone, North Carolina.

Kelley and his colleagues determined after extensive testing that “the annoyance was real and not imagined,” the result of acoustic impulses.

Kelley did not return calls for comment.



[7]

Left: A drawing by Sophia Hartke when the family was still living in the wind farm. | Ted Hartke | Submitted | Right: The Hartke family (from left: Sophia, Ted, Jessica and Phillip) moved out of their home in Fithian, Illinois, after suffering sleepless nights and health problems they blamed on nearby turbines from the California Ridge Farm. | Ted Hartke | Submitted

Like motion sickness

These acoustic impulses – or low-frequency sound waves – stimulate parts of the inner ear responsible for balance, motion and spatial orientation and that they provoke symptoms similar to motion sickness, some researchers say.

“If you’re sitting still and something is causing the same fluids to move, your brain doesn’t know that it’s a false signal,” said Rick James, an acoustical engineer who has written papers on the subject. “But you open your eyes and say, ‘I’m sitting still, but I feel like I’m moving.’”

The Minnesota Department of Health noted the phenomenon in 2009 paper. It found low-frequency waves cause more problems inside a house than outside because, rather than block the pulsations, the walls amplify them.

Darlene Mueller wept as she described how turbines in the Blue Sky Green Field Wind Energy Center in Fond du Lac, Wisconsin, sickened her inside her home.

“I would pace the house like a lion in a cage,” she said. “I would leave the house at 2 or 3 in the morning and go to Walmart just to escape the noise. You go days and days and days without sleep, and it’s just madness.”

Other experts dispute the low-frequency claim. The Department of Energy, which hired Kelley for its North Carolina study, now says on its website that wind turbine sounds – including low-frequency and infrasound – have no direct human health impact.

Humans are biologically unique individuals, said physician Robert McCunney, an MIT researcher who has researched the issue. Perhaps some people suffer from noise sensitivity, he said, but that doesn’t mean wind turbines pose a human health hazard the way asbestos or lead does.

“Not to dismiss their complaints, because I believe these people are sincere,” McCunney said, “but there are other things that can cause these symptoms.”


Despite the lack of scientific consensus, acoustical engineer Paul Schomer said he believes wind turbines genuinely cause human suffering.

He also thinks wind companies truly believe their turbines are safe.

“I think there are enough people that work for the industry that have put out papers and stuff that the waters are muddy,” said Schomer, who has conducted work both for the wind industry and its opponents.

Instead of waiting for science to settle the debate – which Schomer said may never happen – the engineer thinks it’s time for a compromise.

Wind companies should admit turbine noise hurts some people and agree to greater setbacks and lower decibel limits, Schomer said. And wind farm opponents should accept reasonable sound limits and buffer distances instead of trying to outright ban turbines.



[8]

More than 100 wind turbines from two different projects – Noble Clinton and Noble Chateaugay – rise from the rolling hills of Franklin County in northern New York. | Lucille Sherman | GateHouse Media

Dragged through the mud

But some wind farm residents who spoke out about their problems said the industry belittles them. It dismisses their complaints as unfounded or labels them troublemakers, multiple people said.

It has silenced many of their neighbors whom they said suffer the same symptoms but fear the consequences of speaking out.

Falmouth, Massachusetts, resident Todd Drummey bemoaned the problem in 2012 at a public meeting about the town's controversial wind turbines.

"I have spoken to several people who have watched the events of the last two years," Drummey told the board at the time, "and simply concluded no point in subjecting themselves to this type of punishment."

After Cary Shineldecker went public about his experience in Michigan's Lake Winds Energy Park, an energy company executive singled him out at a meeting several states away.

Mike Blazer of Chicago-based Invenergy claimed to know Shineldecker's medical history. He told a crowd in Clear Lake, South Dakota, that Shineldecker's health woes stemmed from alcohol use, obstructive sleep apnea and an irregular heartbeat – not wind turbines.

Blazer shared the information at a December 2016 city meeting about his company's proposed wind farm. He did it to quell fears about wind turbines and to provide "an example of the impact of the type of misinformation that is spread by wind opponents," Blazer said in an email.

Shineldecker said he was stunned to learn about the incident from an attorney who attended the meeting. He said he has neither sleep apnea nor alcohol problems and never received a diagnosis for those problems.

"All I ever had to go on was my integrity and honesty and work ethic," Shineldecker said, "and then to be belittled and treated like some whack-job psycho liar is kind of unbelievable."

Iowa wind farm resident Terry McGovern said he faced disparagement by Apex Clean Energy.

The Virginia-based company accused McGovern of holding "a personal anti-wind agenda" and claimed he would spread misinformation and generate unfounded fear of wind energy ahead of a public presentation he gave.

Apex made the claims in a July 2017 letter it sent to landowners discouraging them from attending the presentation, held near the site of its proposed Upland Prairie Wind farm in northwest Iowa.

McGovern denies holding an anti-wind agenda but is publicly critical of the industry and its business practices. His Iowa Wind Action Group calls for greater setbacks for industrial turbines to protect human health.

"Instead of focusing on the issues, they try to discredit the person," McGovern said. "That way, they can avoid talking about the facts."

Apex sent the letter to clear up confusion about the presentation, not to disparage McGovern, company spokeswoman Dahvi Wilson said.


"It was not our intent to attack the speaker, as it appears he has suggested," Wilson said, "but to explain that the presenter was unaffiliated with Apex and provide project participants with some information about his credentials, which we believe to be accurate."

A Minnesota lawmaker recently criticized the industry for dismissing wind farm residents' concerns, saying it hurts its own credibility.

"What's frustrating to me is when we take the taxpayer money and use it for these projects and then turn around to the taxpayer and completely blow off their concerns," said Republican state Sen. Andrew Mathews at an October legislative hearing on wind turbine siting.

To hear the industry say "it's all bias and not based on facts or science and it's fear and annoyance and rumors, I have tough time then trying to decide how much to consider is credible" from these companies.

Mathews wants the industry to work on solutions to these problems instead of denying they exist. He said it's time the state and its regulatory agencies do more to protect residents from harm.



[9]

Gary Steinich of Columbia County, Wisconsin, walks near one of the turbines in the Glacier Hills Wind Park. | Arturo Fernandez | GateHouse Media

Misleading tactics

Some landowners solicited by wind farm developers claim the companies used misleading statements in their bids to secure land rights for the projects.

Among the statements these landowners cited: That they should sign agreements because their neighbors already did; that the wind turbines would be quiet and unobtrusive; that they could exit the agreement at any time. Several of those who signed said they now regret doing so.

Large-scale wind farms need thousands of acres per project. Because it's not feasible to purchase the property, companies must seek leases with landowners.

Gary Steinich signed a lease agreement with FPL Energy in 2004 to host two turbines in exchange for annual payments of \$10,400.

Representatives "wined and dined" Steinich and told him he could end the contract at any time, he said. They also promised not to disturb his 160 acres of corn, soybeans and wheat. The turbines would go on the edge of his property, they told him, not in the fields.

But before it built the wind farm, FPL sold the project and its land agreements to WE Energies. The Wisconsin-based utility altered the original plan. It now called for larger turbines in different locations on the existing properties, all of which the agreements allowed.

WE Energies spokeswoman Cathy Schulze said the company did alter the wind project plans after purchasing the development. But she said it worked closely with the community and the Wisconsin Public Service Commission to meet their standards.

Steinich tried to terminate his contract after learning the turbines would stand in the middle of his crops, but he said WE Energies refused to release him. He formed a group and hired a lawyer to fight the project, but he couldn't stop it.

"You lose complete control of your land," Steinich said. "They decide everything."

He ultimately sold his acreage and stopped farming.

Steinich's contract contains a common clause rendering moot any verbal promises. It doesn't matter what developers told him if it's not in the agreement.

"This Agreement and the attached Exhibits shall constitute the entire agreement between the Parties and supersedes all other prior writings and understandings," Steinich's contract states.

Other agreements contain similar language, as Wisconsin farmer Allen Hass learned after contracting to host two turbines in the Blue Sky Green Field Wind Energy Project – a decision he now regrets.

"Everything they tell you is a lie unless it's documented in writing," Hass said.

Both men also said wind company representatives falsely claimed their neighbors had signed lease agreements and that the wind projects were coming no matter what. They might as well profit, too.

They said they later learned their neighbors hadn't signed up – at least not at that point. Steinich said he discovered he was the first to sign.

FPL Energy is a subsidiary of NextEra, whose spokesman Bryan Garner declined to comment on Steinich's contract negotiations because he has no direct knowledge of what happened. In general, though, he said the company is truthful to landowners.

Add to story queue:

How some politicians have personal interests in wind energy





[10]

Like a 'securities offer'

At least two Wyoming landowners said they also experienced "aggressive" tactics from wind farm developers.

One of those landowners, former state legislator Diemer True, said representatives of Utah-based Wasatch Wind approached him in 2009 to lease his land for the Pioneer Wind Park.

After True refused, he said, the group continued to pressure him.

"They assured me that because they had, or would have, our neighbors' land leased that I would experience the associated impacts. As a result, I might as well enjoy the income which would come with leasing to them," True wrote as part of a complaint about Wasatch's practices sent to the U.S. Securities and Exchange Commission.

True checked with several of his neighbors, and none had signed a lease with the company, he said in the complaint.

The 2009 SEC complaint came from a citizens' group to which True belonged called the Northern Laramie Range Alliance. It alleged Wasatch used "aggressive sales practices" to solicit development rights worth more than its payment to landowners – akin to a speculative investment and no different from a securities offer.

The alliance also claimed Wasatch, now called Enyo Renewable Energy, failed to disclose the risks associated with the project's development.

"In effect, you're making an in-kind investment in their business," said Kenneth Lay, alliance member and a former SEC enforcement lawyer. "But you don't make anything unless their development is successful."

It's unknown if the SEC took action on the complaint.

Enyo Principal Christine Mikell declined to comment on the alliance's claims, because she wasn't involved in the land negotiations nor was she heading the company at the time. She said Pioneer Wind Park's participating landowners are happy with their contracts.

Lay said he still believes the contracts require serious scrutiny.

Who the contracts favor

The agreements work in the favor of companies in almost every sense, according to several attorneys who have reviewed these types of documents.

Contracts with wind developers can last decades, sometimes with no exit clause for the landowner but language allowing the company to terminate at any time.

Most of the agreements obtained by GateHouse Media allow the company broad access to the property while restricting the landowner's use of the terrain. Some limit the landowner's ability to landscape or erect new structures.

Many contracts also demand the landowner's support of the project in both word and deed.

A lease with Consumer's Energy in Michigan, for example, bans landowners from taking "any action to in any manner attempt to wholly or partially prevent, or otherwise to in any manner oppose," the project even if years later the landowner comes to despise living among the turbines.

Some contracts ban landowners from filing lawsuits against the company, making formal complaints against it before a regulatory agency or lobbying against its future plans to expand the wind farm.

Many agreements also require landowners accept the very effects wind companies claim pose no risk: noises, air-pressure changes, shadow flicker and television and radio interference.

Several agreements contain clauses that let developers renew the terms, sometimes with the landowner's further consent and sometimes without. An Atlantic Wind lease obtained by GateHouse Media shows the company can extend its contract by 26 years without further approval from the landowner.

"These are the most atrocious contracts I've ever read in my life," said Roger McEowen, a professor of agricultural law and taxation at Washburn.

Contracts for land rights vary but all typically contain three components – an exploration phase allowing developers property access to determine project feasibility; a construction and operational phase allowing them to install and operate equipment on the property; and a decommissioning phase covering equipment disassembly and land restoration.

Together these phases' terms can last decades.

Landowners receive different payments depending on the contract phase and the type of equipment – if any – they host. They can range from a one-time sum of less than \$100 to annual installments of tens of thousands of dollars.



[11]

Sandy Kok of Columbia County, Wisconsin, stands near some of the turbines in the Glacier Hills Wind Park. | Arturo Fernandez | GateHouse Media

'Shut-up clause'

Some agreements obtained by GateHouse Media prohibit landowners from making any public statement against the company or the project.

Such was the case with an agreement NextEra offered Jim and Mary Ann Miller after the North Dakota couple complained about relentless shadow flicker from the company's Ashtabula Wind Energy Center.

The flicker was so bad, Jim Miller said, it forced the couple to build a windowless addition to their house.

NextEra agreed to pay them a lump sum of \$15,000 if they signed the waiver.

One of its provisions: "The Parties acknowledge and agree that this prohibition extends to statements, written or verbal, made to anyone, including but not limited to, the news media, investors, potential investors, any board of directors or advisory board or directors, industry analysts, competitors, strategic partners, vendors, employees (past and present) and clients," according to an agreement by Ashtabula Wind II.

The Millers refused to sign.

"I call it a shut-up clause," Jim Miller said.

Such clauses can appear not just in land contracts, but in waivers and so-called “good neighbor agreements.” Companies make agreements with property owners who didn’t sign land deals but live close enough to the project to experience its effects.

In exchange for money, the landowners release the company from liability for these issues and sometimes forfeit their right to complain about it.

Jericho Rise Wind Farm offered Nate Rogers of Chateaugay, New York, \$1,000 upfront and an additional \$1,000 annually to accept noise, shadow flicker, air turbulence, weather hazards and radio and television interference from the turbines near his land, according to a document Rogers shared with GateHouse Media.

The contract does not forbid landowners from complaining about the effects, but it removes their right to seek any legal claim against the company.


Rogers refused to sign, but he said he still lives with the effects of the nearby structures.

His brother’s family lives up the road, and Rogers said it’s even worse for them. Three giant turbines sit just beyond their property line – obstructing the view, interfering with their television reception, and keeping them up at night with loud noises and blinking lights.

“It makes a metal-on-metal grinding noise,” said Denise Rogers. “I’ve thought about moving. This is not the house we intended it to be.”

Denise and her husband, George, bought the same decibel meter the company uses to measure sound. They said they routinely catch the turbines exceeding the county’s 50-decibel limit and file complaints, but the problems continue.

It’s a never-ending battle, they said.



Left: Denise and George Rogers and their sons, Callahan, 15, and Witt, 12, live near several turbines in the Jericho Rise Wind Farm in Franklin County, New York. | Lucille Sherman | GateHouse Media | Right: Highlighted satellite imagery of a section of the Ashtabula II Wind Energy Center. | Bing.Com/Maps | Used with permission from Microsoft | www.bing.com/maps

'Property value decline'

"Many landowners feel compelled to sign a gag agreement to avoid paying attorney fees to battle the wind farm companies," McEowen said. "One part of what you're getting compensation for is the loss in value for your property."

Wind industry officials deny projects reduce property values. The American Wind Energy Association lists one dozen studies on its website showing no effect on home sales or values.

But other studies have found the opposite, including several conducted by Chicago-based certified residential appraiser Michael McCann.

McCann appraised Cary and Karen Shindelcker's property for \$260,000 when they put it on the market in 2011, shortly before Consumers Energy erected several large turbines near their home. The couple wanted to sell before the wind farm became operational.

The Shindelckers got no offers for nearly four years.

In early 2015, the family accepted an offer on the house for \$139,000 and sold the surrounding acreage separately for \$40,000 – a total 30 percent loss on the original asking price.

"We were devastated," Karen said.

The Shindelckers weren't alone. Several neighbors also complained about property devaluation and health problems from the Lake Winds Energy Park. Together, they sued Consumers Energy in March 2013.

The company denied the claims but ultimately settled with the residents in October 2014 for an undisclosed sum.

Dan Williams of Ione, Oregon, also lost value on his property after construction of the Willow Creek Wind Farm, according to real-estate appraiser Richard Barnett.

In court documents related to Williams' lawsuit against the wind farm, Barnett estimated the property's value at \$59,000 without the turbines and \$12,400 with the turbines – a nearly fivefold reduction.

Invenergy, which owns Willow Creek, denied Williams' allegations. The lawsuit settled in January 2016 for an undisclosed sum.

"If you were looking at two identical houses and one had wind turbine and one didn't, which would you pick?" said Bradley Tupi, a Pittsburg attorney who has litigated several wind-related suits.

"There is an obvious impact on property value," he said.

Splitting families, communities

Wind farms bring not only the promise of jobs and money to rural communities across America, but sometimes deep divisions that can rip apart families, friendships and the fabric of once tight-knit towns.

Proposed wind projects have fractured rural communities across the country, pitting neighbor against neighbor in fights over property rights, money and the future of their homes.



Residents erupted in a shouting match at a town meeting in Ellington Township, Michigan, in December in 2016. One of them had signed a lease with the wind company; the other didn't want the project.

In nearby Almer Township, resident Norman Stephens said somebody destroyed his lawn with Roundup after he spoke out against a proposed wind farm.

Jim and Mary Ann Miller lost friends by opposing the project near their home in Luverne, North Dakota. They said they were taunted at town meetings and shunned by neighbors.

Industry company representatives disputed these projects create community divisions, although they acknowledged some developments spur a period of debate as residents seek information and grapple with impending change.

"These wind farms obviously are creating a big change in these communities," said Evan Vaughn of the American Wind Energy Association, the trade and lobbying arm of the industry. "But it's a change for the better."



[13]

Competing yard signs line the streets in St. Lawrence County, New York, where the community is debating a proposed wind farm that would erect as many as 40 industrial turbines. | Lucille Sherman | GateHouse Media

Split in New York

The neighboring towns of Hopkinton and Parishville in northern New York currently face widespread division over a proposed wind farm that would erect as many as 40 industrial turbines throughout its rural pastures.

A group of residents called Concerned Citizens for Rural Preservation formed to oppose the project. Its members show up at town meetings and pass out yard signs saying "No industrial wind turbines" that now dot lawns across the county.

Other lawns belong to families supporting the development and feature "Yes wind power" signs along the sides of the roads. A pro-wind group called North County for a Brighter Future also formed. It paid for an ad in the local newspaper blaming opponents for using scare tactics.

The controversy flares up at town meetings and in letters to the editor in the local newspaper. It has ended friendships and split families. Project opponent Janice Pease said she no longer speaks to her grandfather, a World War II veteran and major landowner who signed a lease to place two turbines on his land.

"It has divided the community, even families," said Hopkinton Supervisor Sue Wood. "The majority doesn't want the wind turbines, but the people who signed leases really want it."

The project, called North Ridge Wind Farm, would pump \$750,000 annually into local coffers – divided among the county, two towns and the school district. It also would pay participating property owners a combined \$500,000 annually for use of their land.

Avangrid Renewables, a U.S. subsidiary of the Spanish utility giant Iberdrola, is developing the wind farm.

“These investments are, of course, going to represent some amount of change in the community, and we want to do the best that we can to make sure the community is a partner in bringing that change along responsibly and appropriately,” Copleman said. “I think from there people will wrestle with various questions about what it means to develop a wind farm in a community. It’s our job to do the best we can to answer those questions.”



[14]

Janice Pease (left) speaks to Luke Martin inside a cabin that acts as the headquarters of the Concerned Citizens for Rural Preservation group. The group, to which Pease and Martin belong, opposes plans for a wind farm in St. Lawrence County, New York. | Emily Le Coz | GateHouse Media

Accusations of secrecy

Many blame the wind companies for fostering the division, claiming developers enter communities in secret to sign up landowners years before publicly announcing the project.

By the time the general public learns about it, developers already have the easements they need from landowners and the assurances they seek from elected officials to develop their wind farms, several residents said.

Many said they felt blindsided and angry.

“To this date, in all of these projects, there are many people still unaware that these giants are coming to their communities,” said Tina Graziano of Villenova, New York, where two companies want to build wind farms.

Graziano made the comments at a Chautauqua County Legislature meeting in January, along with several other people upset about the community division, which many blamed on the wind companies’ tactics.

“These wind companies slide, snowball the uneducated board members, keep the notifications at a minimum to deter community opposition,” said Graziano said at the meeting. “The community is now split.”

Developers aren’t being secretive; they’re being cautious, said AWEA’s Mike Speerschneider. It can take years to determine a project’s feasibility due to easements, permitting, environmental studies and other factors. They don’t want to announce anything until they’re sure they can proceed.

“A very small percentage of projects become anything,” Speerschneider said, “so it doesn’t make sense to announce it publicly every time you look at a particular piece of property.”

But that secrecy, whatever the reason, can drive communities apart. When Cary Shineldecker went door to door informing residents of the proposed wind farm in Mason County, Michigan, he said people were shocked to learn neighbors had signed agreements.

“We had people break down and cry when they found out that people who had been their lifelong friends, who had babysat each other’s kids for 50 years, and they never even told their neighbors,” Shineldecker said. “They felt so betrayed their friend who lived right next to them had never told them they leased to the company.”

The same thing happened when Portuguese energy giant EDP was developing its 77-megawatt Jericho Rise Wind Farm in Chateaugay, New York, residents there said.

Glenda King knows the heartache firsthand. Although she and her family publicly opposed the project, adjacent neighbors quietly signed a lease agreement with EDP to erect three large turbines on their property.

King was devastated when she found out. One of the 496-foot turbines looms just inches from her property line. It screeches whenever the giant motor house rotates in search of optimum wind conditions, and its red lights blink incessantly, keeping the family up at night, she said.

“There is a huge emotional, psychological and physical effect from these things,” King said. “It’s disgraceful how these companies come into economically deprived area and rip apart families, friends and neighbors.”

See also:

Shadow flicker simulation: »» GO »» ^[15]

With data from the Federal Aviation Administration, the U.S. Geological Survey and Google Maps, we’ve mapped wind turbines across the country. See the growth over time and more details with a look inside the numbers: »» GO »» ^[16]

This investigation found more than 450 families who have publicly complained about the impacts of living near wind farms. **Have a similar experience? Tell your story in your own words:** »» GO »»^[17]

Inside the investigation: »» GO »»^[18]

Michigan wind farm cost a family its health, home^[19]

Communities fight wind farms, face pushback^[20]

Conflicts of interest abound in wind farm proposals^[21]

New York community divided over wind farm^[22]

URL to article: <https://www.wind-watch.org/news/2017/12/14/in-the-shadow-of-wind-farms/>

URLs in this post:

[1] Image: <https://www.wind-watch.org/news/wp-content/uploads/2017/12/InTheShadowOfWindFarms.jpg>

[2] Image: <https://www.wind-watch.org/news/wp-content/uploads/2017/12/shineldeckers5.jpg>

[3] Image: <https://www.wind-watch.org/news/wp-content/uploads/2017/12/GlacierHills.jpg>

[4] Image: <https://www.wind-watch.org/news/wp-content/uploads/2017/12/ABoomingIndustry.png>

[5] Image: <https://www.wind-watch.org/news/wp-content/uploads/2017/12/Rally.jpg>

[6] Image: <https://www.wind-watch.org/news/wp-content/uploads/2017/12/Vibrations-1.jpg>

[7] Image: <https://www.wind-watch.org/news/wp-content/uploads/2017/12/HealthImpactDebate.png>

[8] Image: <https://www.wind-watch.org/news/wp-content/uploads/2017/12/FranklinCountyNY.jpg>

[9] Image: <https://www.wind-watch.org/news/wp-content/uploads/2017/12/Gary.jpg>

[10] Image: <https://www.wind-watch.org/news/wp-content/uploads/2017/12/MisleadingTactics2.jpg>

[11] Image: <https://www.wind-watch.org/news/wp-content/uploads/2017/12/SandyKok.jpg>

[12] Image: <https://www.wind-watch.org/news/wp-content/uploads/2017/12/Rogers.jpg>

[13] Image: <https://www.wind-watch.org/news/wp-content/uploads/2017/12/SplittingFamiliesCommunities.png>

[14] Image: <https://www.wind-watch.org/news/wp-content/uploads/2017/12/SplitInNY-1.jpg>

[15] »» GO »»: <http://gatehousenews.com/windfarms/worst-of-it/>

[16] »» GO »»: <http://gatehousenews.com/windfarms/inside-the-numbers/>

[17] »» GO »»: <http://gatehousenews.com/windfarms/in-your-own-words/>

[18] »» GO »»: <http://gatehousenews.com/windfarms/inside-the-investigation/>

[19] Michigan wind farm cost a family its health, home: <https://www.wind-watch.org/news/2017/12/14/michigan-wind-farm-cost-a-family-its-health-home/>

[20] Communities fight wind farms, face pushback: <https://www.wind-watch.org/news/2017/12/14/communities-fight-wind-farms-face-pushback/>

[21] Conflicts of interest abound in wind farm proposals: <https://www.wind-watch.org/news/2017/12/14/conflicts-of-interest-abound-in-wind-farm-proposals/>

[22] New York community divided over wind farm: <https://www.wind-watch.org/news/2017/12/14/new-york-community-divided-over-wind-farm/>

#2 of 3

RECEIVED

MAY 03 2018

**SOUTH DAKOTA PUBLIC
UTILITIES COMMISSION**

To: Amanda Reiss

Brian <brian.taylor.aud@gmail.com>
To: rubyholborn@gmail.com

Mon, Feb 26, 2018 at 10:37 PM

By HHTM to use those wind turbine articles

Hearing, & Health that Matters

**MICHIGAN STATE
UNIVERSITY**

February 26, 2018

Dear Mr. & Ms. Holborn:

In response to your request for permission to distribute the Punch and James (2016) article to the Public Utilities Commission, the article is available online at the following website:

<http://hearinghealthmatters.org/journalresearchposters/files/2016/09/16-10-21-Wind-Turbine-Noise-Post-Publication-Manuscript-HHTM-Punch-James.pdf>

My understanding is that the article is accessible to anyone who has access to the Internet. For distribution in a public forum such as the PUC meeting, I assure you that I have no personal objection whatsoever to your distributing it, but because the article is copyrighted by the Hearing Health and Technology Matters website (hhtm.org), I suggest you contact the staff there for permission to use the article for that purpose. I believe the best and quickest way to obtain permission is to contact the staff by email at Info@Hearinghealthmatters.org.



**College of
Communication
Arts & Sciences**

Department of
Communicative
Sciences and
Disorders

1026 Red Cedar Road
Room 109, Oyer Speech &
Hearing Building
East Lansing, MI 48824

517-353-8780
Fax: 517-353-3176
comdis.msu.edu

Copyright permission is normally granted without reservations unless an article is being distributed for commercial purposes for which the distributor is compensated. Given the legal context in which you wish to distribute the article, I think the correct thing to do is to ask the Journal staff directly for permission. I am not aware if the staff makes a distinction between distribution in printed vs. electronic form. If you are unable to secure permission in time for the PUC meeting, my personal opinion is that there would be nothing inappropriate with providing the above URL to anyone who might wish to access the article.

Sincerely,

Jerry Punch, Ph.D.
Professor Emeritus

Gmail

COMPOSE

Consent to use Punch and James HHTM article

Inbox x

Inbox (15)

Starred

Important

Chats

Sent Mail

Drafts (32)

All Mail

Spam (127)

Trash

Categories

Social

Promotions (1)

Updates (2)

Forums

3129 Hwy 14 By...

AAA

Richard James <rickjames@e-coustic.com>
to me, Jerry

9:41 AM (6)

Mr. and Mrs. Holburn,
Dr. Punch was the lead author on the paper so his Letter of Consent should be sufficient to establish permission for you
This peer-reviewed paper is available through a public access Open Journal. It has been re-posted on web sites and blog
as you provide the URL to the document on the HHTM website there should be no reason for the Department to be con
sent to submit it.

However, you also have my consent to use it. I have attached a pdf version of it to make it easier for you to provide for
Rick James

"A subset of society should not be forced to bear the cost of a benefit for the larger society."

From: One Page Takings Summary: U.S Constitution and Local Land Use, by: George S. Hawkins, Esq., Stony Brook-Mi
Association

E-Coustic Solutions, LLC
Okemos, MI 48805
Tel: [\(517\) 507-5067](tel:5175075067)
Email: rickjames@e-coustic.com

The contents of this e-mail are intended for the named addressee only. It contains information that may be confidential. Unless you are the named addressee or an authorized designee, you may not c
else. If you received it in error please notify us immediately and then destroy it.





Ruby Holborn <rubyholborn@gmail.com>

Written Consent to Redistribute your Copyrighted Material

1 message

Ruby Holborn <rubyholborn@gmail.com>

Mon, Feb 26, 2018 at
9:39 PM

To: Info@hearinghealthmatters.org

Bcc: rubyholborn@gmail.com

For my Public Comment Presentations before the Minnesota Public Utilities Commission, South Dakota PUC, and our S.D. County Commissioners, I need your permission to redistribute your copyrighted material.

May I receive your permission to redistribute your research article titled "Wind Turbine Noise and Human Health: A Four-Decade History of Evidence that Wind Turbines Pose Risks" by Wayne Staab?

I have contacted Jerry Punch and have received his permission on this also.

The South Dakota Public Utilities Commission website below gives instructions on page 2 beneath the heading Submit Comments pertaining to copyrighted material.

<https://puc.sd.gov/commission/Publication/sitinghandout.pdf>

Thank You.
George L. Holborn

Gary, SD

Sent from my iPhone

2 attachments



image1.jpeg
85K





Ruby Holborn <rubyholborn@gmail.com>

Consent to use Punch and James HHTML article

1 message

Richard James <rickjames@e-coustic.com>Tue, Feb 27, 2018 at
9:41 AM

To: rubyholborn@gmail.com

Cc: "Punch, Jerry" <jpunch@msu.edu>

Mr. and Mrs. Holburn,

Dr. Punch was the lead author on the paper so his Letter of Consent should be sufficient to establish permission for you to use our paper.

This peer-reviewed paper is available through a public access Open Journal. It has been re-posted on web sites and blogs many times. As long as you provide the URL to the document on the HHTML website there should be no reason for the Department to be concerned that you need consent to submit it.

However, you also have my consent to use it. I have attached a pdf version of it to make it easier for you to provide formatted copies.

Rick James

"A subset of society should not be forced to bear the cost of a benefit for the larger society."

From: One Page Takings Summary: U.S Constitution and Local Land Use, by: George S. Hawkins, Esq., Stony Brook-Millstone Watershed Association

E-Coustic Solutions, LLC

Okemos, MI 48805

Tel: (517) 507-5067

Email: rickjames@e-coustic.com

The contents of this e-mail are intended for the named addressee only. It contains information that may be confidential. Unless you are the named addressee or an authorized designee, you may not copy or use it, or disclose it to anyone else. If you received it in error please notify us immediately and then destroy it.



16-10-22 Revision of Wind Turbine Noise Post-Publication Manuscript (HHTM Punch & James).pdf

1301K



Ruby Holborn <rubyholborn@gmail.com>

Consent to use Punch and James HHTML article1 message

Richard James <rickjames@e-coustic.com>Tue, Feb 27, 2018 at
9:41 AM

To: rubyholborn@gmail.com

Cc: "Punch, Jerry" <jpunch@msu.edu>

Mr. and Mrs. Holburn,

Dr. Punch was the lead author on the paper so his Letter of Consent should be sufficient to establish permission for you to use our paper.

This peer-reviewed paper is available through a public access Open Journal. It has been re-posted on web sites and blogs many times. As long as you provide the URL to the document on the HHTML website there should be no reason for the Department to be concerned that you need consent to submit it.

However, you also have my consent to use it. I have attached a pdf version of it to make it easier for you to provide formatted copies.

Rick James

"A subset of society should not be forced to bear the cost of a benefit for the larger society."

From: One Page Takings Summary: U.S Constitution and Local Land Use, by: George S. Hawkins, Esq., Stony Brook-Millstone Watershed Association

E-Coustic Solutions, LLC

Okemos, MI 48805

Tel: (517) 507-5067

Email: rickjames@e-coustic.com

The contents of this e-mail are intended for the named addressee only. It contains information that may be confidential. Unless you are the named addressee or an authorized designee, you may not copy or use it, or disclose it to anyone else. If you received it in error please notify us immediately and then destroy it.



16-10-22 Revision of Wind Turbine Noise Post-Publication Manuscript (HHTML Punch & James).pdf
1301K

**MICHIGAN STATE
UNIVERSITY**

February 26, 2018

Dear Mr. & Ms. Holborn:

In response to your request for permission to distribute the Punch and James (2016) article to the Public Utilities Commission, the article is available online at the following website:

<http://hearinghealthmatters.org/journalresearchposters/files/2016/09/16-10-21-Wind-Turbine-Noise-Post-Publication-Manuscript-HHTM-Punch-James.pdf>.

My understanding is that the article is accessible to anyone who has access to the Internet. For distribution in a public forum such as the PUC meeting, I assure you that I have no personal objection whatsoever to your distributing it, but because the article is copyrighted by the Hearing Health and Technology Matters website (hhtm.org), I suggest you contact the staff there for permission to use the article for that purpose. I believe the best and quickest way to obtain permission is to contact the staff by email at Info@Hearinghealthmatters.org.



**College of
Communication
Arts & Sciences**

Department of
Communicative
Sciences and
Disorders


1026 Red Cedar Road
Room 109, Oyer Speech &
Hearing Building
East Lansing, MI 48824

517-353-8780
Fax: 517-353-3176
comdis.msu.edu

Copyright permission is normally granted without reservations unless an article is being distributed for commercial purposes for which the distributor is compensated. Given the legal context in which you wish to distribute the article, I think the correct thing to do is to ask the Journal staff directly for permission. I am not aware if the staff makes a distinction between distribution in printed vs. electronic form. If you are unable to secure permission in time for the PUC meeting, my personal opinion is that there would be nothing inappropriate with providing the above URL to anyone who might wish to access the article.

Sincerely,

Jerry Punch, Ph.D.
Professor Emeritus



WIND TURBINE NOISE AND HUMAN HEALTH

A Four-Decade History of Evidence that Wind Turbines Pose Risks

Abstract

Many expert-review panels and some individual authors, in the U.S. and internationally, have taken the position that there is little literature to support concerns about adverse health effects (AHEs) from noise emitted by industrial wind turbines (IWTs). In this review, we systematically examine the literature that bears on some of the particular claims that are commonly made in support of the view that a causal link is non-existent. Investigation of the veracity of those claims requires that multiple topics be addressed, and the following specific topics were targeted for this review: (1) emissions of infrasound and low-frequency noise (ILFN) by IWTs, (2) the perception of ILFN by humans, (3) the evidentiary bases for establishing a causative link between IWTs and AHEs, as well as the physiological bases for such a link, (4) recommended setback distances and permissible noise levels, (5) the relationship between annoyance and health, (6) alternative causes of the reported health problems, (7) recommended methods for measuring infrasound, (8) foundations for establishing a medical diagnosis of AHEs due to IWTs, (9) research designs useful in establishing causation, (10) the role of psychological expectations as an explanation for the reported adverse effects, (11) the prevalence of AHEs in individuals exposed to IWTs, and (12) the scope and quality of literature addressing the link between IWT noise and AHEs. The reviewed evidence overwhelmingly supports the notion that acoustic emissions from IWTs is a leading cause of AHEs in a substantial segment of the population.

Original: October 4, 2016

Revised: October 21, 2016

Jerry L. Punch: Professor Emeritus, Department of Communicative Sciences and Disorders, Michigan State University, East Lansing, MI, USA

Richard R. James: E-Coustic Solutions, LLC, and Adjunct Professor, Department of Communication Disorders, Central Michigan University, Mt. Pleasant, Michigan, USA

©HearingHealthMatters.org

<http://hearinghealthmatters.org/journalresearchposters/files/2016/09/16-10-21-Wind-Turbine-Noise-Post-Publication-Manuscript-HHTM-Punch-James.pdf>

Wind Turbine Noise and Human Health: A Four-Decade History of Evidence that Wind Turbines Pose Risks*

Jerry L. Punch,ⁱ Richard R. Jamesⁱⁱ

Abstract

Many expert-review panels and some individual authors, in the U.S. and internationally, have taken the position that there is little literature to support concerns about adverse health effects (AHEs) from noise emitted by industrial wind turbines (IWTs). In this review, we systematically examine the literature that bears on some of the particular claims that are commonly made in support of the view that a causal link is non-existent. Investigation of the veracity of those claims requires that multiple topics be addressed, and the following specific topics were targeted for this review: (1) emissions of infrasound and low-frequency noise (ILFN) by IWTs, (2) the perception of ILFN by humans, (3) the evidentiary bases for establishing a causative link between IWTs and AHEs, as well as the physiological bases for such a link, (4) recommended setback distances and permissible noise levels, (5) the relationship between annoyance and health, (6) alternative causes of the reported health problems, (7) recommended methods for measuring infrasound, (8) foundations for establishing a medical diagnosis of AHEs due to IWTs, (9) research designs useful in establishing causation, (10) the role of psychological expectations as an explanation for the reported adverse effects, (11) the prevalence of AHEs in individuals exposed to IWTs, and (12) the scope and quality of literature addressing the link between IWT noise and AHEs. The reviewed evidence overwhelmingly supports the notion that acoustic emissions from IWTs is a leading cause of AHEs in a substantial segment of the population.

Key Words: Adverse health effects, human health, industrial wind turbines, infrasound, inner ear, low-frequency noise, wind turbine noise

Introduction

Whether infrasound and low-frequency noise (ILFN) from industrial wind turbines (IWTs) is detrimental to human health is currently a highly controversial topic. Advocates of industrial-scale wind energy assert that there is no credible scientific evidence of a causal relationship, while many reputable professionals believe that there is sufficient scientific evidence to establish a causal link between IWTs and detrimental health effects *for a non-trivial percentage of individuals who reside in communities hosting IWTs*. The veracity of claims regarding the effects on human health is being debated on a global scale by the wind industry; individuals living near

*Revised October 21, 2016

ⁱProfessor Emeritus, Department of Communicative Sciences and Disorders, Michigan State University, East Lansing, MI, USA

ⁱⁱE-Cooustic Solutions LLC, and Adjunct Professor, Department of Communication Disorders, Central Michigan University, Mt. Pleasant, Michigan, USA

IWTs; attorneys and expert witnesses in courts of law; print and web-based media; documentary films (which currently include *Windfall*, *Wind Rush*, and *Down Wind*); and scientists and other professionals in government reports, on the Internet, and in scientific and professional papers presented at society meetings and published in peer-reviewed journals.

The debate surrounding IWTs extends to many controversial issues, including physical safety, visibility, shadow flicker, and threats to property values and wildlife. Many problems involving wind turbines, including mechanical failures, accidents, and other mishaps, have been discussed on the Internet. At least one website has extensively catalogued these incidents,^[1] and the large number of incidents reported by that site is described by its webmaster as grossly underestimating the actual number of documented incidents. The most vigorous debate, however, centers on ILFN and its effects on human health.

The overall purpose of this article is to provide a systematic review of legitimate sources that bear directly and indirectly on the question of the extent to which IWT noise leads to the many health complaints that are being attributed to it. The authors accessed most articles and reports referenced in this review by employing Google, Google Scholar, and PubMed as the primary search engines. Our basic aim was to provide a comprehensive and representative—though not exhaustive—review of the literature that is relevant to many of the claims made by wind industry advocates. An exhaustive review is an elusive and impractical goal, given the large volume of directly and indirectly related work done in this area over the past several decades and the current pace of such work.

The role of evidentiary facts

Adverse impacts on people and property are among the most contentious issues that are typically the focus of legal proceedings involving IWT noise. Based on the forensic and research experiences of the authors, we believe that a resolution of the controversial aspects of this debate will require not just relevant scientific research, but rather a series of legal judgments based on the effective evaluation and interpretation of the existing research. In fact, much research and some already-rendered legal decisions show convincingly that some segments of the population suffer damaging effects from exposure to wind turbine noise (WTN). What is needed among the scientific community, local and national governmental agencies, and political leaders, is honest discourse about methods for reducing carbon emissions in ways that do not turn some rural communities into *sacrifice zones*.^[2, 3]

Many symptoms and complaints of adverse health effects (AHEs) related to IWTs have been self-reported by individuals living near wind turbines and described in published case reports.

There is a group of core symptoms and complaints, however—including sleep disturbance, headache, dizziness, vertigo, and ear pressure or pain—that are remarkably common worldwide. Dr. Nina Pierpont was the first to report these core symptoms in a case series,^[4] and she termed these core symptoms *Wind Turbine Syndrome*. For the sake of brevity, we will on occasion refer to Wind Turbine Syndrome as a substitute for this group of common symptoms and complaints, even though the phrase itself is currently not utilized as a medical diagnostic entity.

Numerous reviews of the literature have already been published that allege that there is no credible link between WTN emissions and AHEs. Those reviews have typically been sanctioned by state or provincial government agencies that have missions to support the development of wind energy, and which in turn appoint *expert panels* whose members hold views that regularly favor the wind industry and, therefore, may have conflicting interests. Too often, in the opinion of the authors, such reviews are biased in support of political policy decisions that promote the financial interests of wind developers, and perceived financial benefits to local communities, over the common good. None of those reviews has been specifically targeted toward describing or explaining the relationship between exposure to complex, dynamically modulated infra- and low-frequency sound from wind turbines or other industrial sources (e.g., noise-induced Sick Building Syndrome) and AHEs. Our primary objective in this article is to review the existing scientific and professional literature that is frequently overlooked in such reviews conducted by wind energy proponents. Such literature can be useful in legal proceedings in questioning and articulating the available evidence of risks to people who live in the footprint of utility-scale wind energy projects.

Some of the published reviews have been criticized for their failure to meet the standards noted by Horner,^[5] who reminds us that readers should regard literature reviews with caution, and employ an audit strategy in evaluating their completeness, accuracy, and objectivity. Authors, including ourselves, have an inherent obligation to ensure that such reviews cite all known legitimate sources that serve as the basis for their views of the issues and reflect accurately the contents of all references cited.

Some courts of law in the U.S. and other countries now tend to rely heavily on testimony that adheres to the principle that proof of evidence of causation of AHEs from IWTs be based on the peer-reviewed literature. Presumably, that practice in the U.S. stems at least partially from advocacy by the Office of Management and Budget^[6] that internal and external government science documents be peer-reviewed government-wide for the purpose of increasing the quality and credibility of scientific information generated by the federal government. Peer-review standards are considered paramount in that effort.

While the peer-review process has many virtues, it also has its shortcomings, which are well known. For example, not all journals or individual reviews of submitted manuscripts are of equal quality, as specific journals and specific reviewers may have ideological or philosophical biases, which may or may not be surmised from the journals' mission statements. Nonetheless, the peer-review process is one of the most widely acknowledged ways to control the quality of published works. We contend, however, that there are other credible sources of information, even though those sources may not have been subjected to as rigorous a peer-review process as that employed by many scientific journals. Such sources include papers presented at meetings of scientific and professional societies; reports and other documents commissioned by state and local governmental agencies, especially if such documents are authored by independent researchers; legal testimony given under oath by qualified scientists and professionals; and some information available on the Internet, especially if written by professionals who have reputable track records in their disciplines. Although we will emphasize the peer-reviewed literature in this article, we will also cite some of these additional sources as authoritative. Our citing of selected non-peer-reviewed reports, with a few exceptions, is based on our familiarity with the professional reputations of the authors of those reports, normally earned through publication of a solid body of work in the peer-reviewed literature and by acceptance of their work by other professionals and peers. Typically, individuals so referenced enjoy positive national or international recognition in their respective fields of expertise.

We begin this review by calling attention to a quote from geophysicist Marcia McNutt, who once headed the U.S. Geological Survey and is now editor of the prestigious journal *Science*. McNutt has been quoted as stating: "Science is not a body of facts. Science is a method for deciding whether what we choose to believe has a basis in the laws of nature or not."^[7] In fact, science consists of a variety of overlapping methodological approaches, which must be interwoven to discover answers to complex problems. That conviction has guided our attempt to re-examine the controversial topic at hand.

Review of wind industry claims and positions

Our review is organized by summarizing the past and present literature that addresses each of 12 selected statements, listed below, that encapsulate specific claims, or positions, commonly taken by advocates for the wind industry:

1. Infrasound is not an issue, as infrasound generated by wind turbines is not perceptible to humans.
2. There is nothing unique about wind turbine noise, as infrasound and low-frequency noise are commonly produced by the body and by many environmental sources.

3. There is no evidence that wind turbine noise, audible or inaudible, is the cause of adverse health effects in people, and there are no physiological mechanisms to explain how inaudible acoustic energy can be harmful.
4. Setback distances of 1,000-1,500 ft. (approximately 0.3-0.5 km) are sufficiently safe to protect humans from harm, regardless of height or other physical characteristics of the IWTs.
5. Annoyance is a nuisance, but it is not a health issue.
6. Noise cannot account for all of the complaints of people living in the vicinity of wind turbines; there must be another, unknown reason for the complaints.
7. Infrasound from wind turbines is sufficiently correlated to the A-weighted sound emissions to allow an A-weighted model to be used to predict how much infrasound is present in homes.
8. Wind Turbine Syndrome has not been accepted as a diagnostic entity by the medical profession, so medical professionals cannot diagnose or treat it.
9. Peer-reviewed epidemiological literature is the only acceptable basis for proving a causative relationship between wind turbine noise and adverse health effects.
10. The nocebo effect, a manifestation of psychological expectations, explains why people complain of adverse health effects when living near wind turbines.
11. Only relatively few people, if any, are adversely impacted by wind turbine noise, and the majority have no complaints.
12. There is no evidence in the literature to support a causative link between wind turbine noise and adverse effects.

Statement 1: Infrasound is not an issue, as infrasound generated by wind turbines is not perceptible to humans.

The argument that infrasound as a cause of AHEs is not an issue has been advanced in the published literature primarily by Dr. Geoff Leventhall,^[8, 9] with support from several other researchers. Those researchers have dismissed the influence of infrasound on human health by describing it as not exceeding the thresholds of audibility, and therefore ineffectual, without noting that those thresholds were established using steady pure tones instead of the complex, dynamically modulated tones emitted by wind turbines. Leventhall claims that infrasound from wind turbines is not a problem and that it is misunderstood largely because of mischaracterization by the media and by “those with limited knowledge” (p. 29). He states that there may be noise problems associated with wind turbines, but that such problems are due to

audible swishing sounds due to interactions of the blades with the tower. Supporters of wind energy have generally followed Leventhall's lead, although his own research has shown conclusively that exposure to modulated ILFN produced by large industrial equipment, including heating, ventilating and air-conditioning (HVAC) systems, leads to mental fatigue, lack of concentration, headaches, reduced performance, and work dissatisfaction. Indeed, there is a long history of noise-induced *Sick Building Syndrome*, stemming from investigations in the 1970s-1990s of the effects of low-frequency noise on knowledge workers (see James^[10] and Schwartz^[11] for reviews of that research). Leventhall^[12] stated:

“Low frequency noise causes extreme distress to a number of people who are sensitive to its effects. Such sensitivity may be a result of heightened sensory response within the whole or part of the auditory range or may be acquired. The noise levels are often low, occurring in the region of the hearing threshold, where there are considerable individual differences” (p. 4).

Later in the same document, he states:

“There is no doubt that some humans exposed to infrasound experience abnormal ear, CNS (central nervous system), and resonance induced symptoms that are real and stressful. If this is not recognised by investigators or their treating physicians, and properly addressed with understanding and sympathy, a psychological reaction will follow and the patient's problems will be compounded. Most subjects may be reassured that there will be no serious consequences to their health from infrasound exposure and *if further exposure is avoided* (emphasis added) they may expect to become symptom free” (p. 60).

Leventhall has also stated that the ear is designed to protect us from infrasound and that, in essence, *If you can't hear it, you can't feel it.*^[13, 14] The idea that ILFN from wind turbines does not affect health was further reinforced in a 2009 white paper co-authored by Leventhall and sanctioned by the wind industry,^[15] to be reviewed later.

The position that infrasound from wind turbines is not harmful to humans because it is not perceptible to the human ear also has support from Møller & Pedersen,^[16] who investigated noise emissions from 48 wind turbines with electrical output capacities of between 2.3 and 3.6 MW.

They stated:

“The turbines do emit infrasound (sound below 20 Hz), but levels are low when human sensitivity to these frequencies is accounted for. Even close to the turbines, the infrasonic sound pressure level is much below the normal hearing threshold, and infrasound is thus not considered as a problem with turbines of the investigated size and construction” (pp. 3742-3743).

Evans et al^[17] found that levels of infrasound measured at two residential locations near wind projects in South Australia were within the range of infrasound levels experienced in other urban and rural environments. Although Colby et al^[15] and Bolin et al^[18] dismiss wind turbines as a cause of AHEs, they acknowledge that turbines emit ILFN. A number of authors indicate that large turbines emit more such noise than smaller turbines (see, for example, Bolin et al^[18] and Møller & Pedersen.^[16]) George Kamperman (personal communication, 2009) has concluded that the amount of low-frequency noise generated by IWTs increases by 3–5 dB for every megawatt of electrical power generated.

Evidence that IWTs produce perceptible levels of infrasound, in addition to audible low-frequency noise above 20 Hz, has been available since the 1980s. In their seminal research on large-scale wind turbines, which was funded by the U.S. Department of Energy, Kelley et al^[19] measured noise levels emitted by a DOE/NASA MOD-1 wind turbine operating near Boone, North Carolina, in response to noise complaints. They concluded that:

“...one of the major causal agents responsible for the annoyance of nearby residents by wind turbine noise is the excitation of highly resonant structural and air volume modes by the coherent, low frequency sound radiated by large wind turbines. Further, there is evidence that the strong resonances found in the acoustic pressure field within rooms actually measured indicates a coupling of subaudible energy to human body resonances at 5, 12, and 17-25 Hz, resulting in a sensation of whole-body vibration” (p. 120).

Those conclusions were further strengthened in a subsequent report.^[20] In a second follow-up report, also funded by the Department of Energy, Kelley^[21] electronically simulated three interior environments resulting from low-frequency acoustical loads radiated from both single and grouped upwind and downwind turbines. (These terms refer to the placement of the rotor and blades with respect to the tower. With upwind designs, the more contemporary design, the airflow strikes the blades before striking the tower, and with downwind designs, the airflow strikes the tower before striking the blades.) Relatively low levels of low-frequency acoustic noise from a single, 2-MW MOD-1 wind turbine led to annoyance of residents of the surrounding community, largely through interaction with residential structures. Most importantly, Kelley found that the turbines radiated their peak sound power in the infrasonic range, typically between 1 and 10 Hz. An extensive investigation revealed that the reported annoyance was the result of a coupling of the turbine’s impulsive low-frequency acoustic energy into the structures of some of the surrounding homes, and that annoyance was “frequently confined to *within the home itself*” (p. 1). Despite these early findings that IWTs generate infrasonic levels that produce acoustic energy, vibrations, and resonances that affect people in

their homes, the wind industry has chosen to regard them as insignificant or only applicable to obsolete, downwind wind turbine designs.

The basis for discounting the research by Kelley and associates is predicated on the assumption that pressure changes of equal levels to wind turbines occur in natural environments and do not cause any similar complaints. The authors find that their own experiences with rapidly changing pressures have caused similar experiences. If these rather short-duration sensations were to continue over days, weeks, and months, as they do for people living near wind projects, they would likely find them to be unacceptable.

The primary argument of people who deny any effects is encapsulated by Leventhall^[9] in his *Child on a Swing* example:

“A child on a swing experiences infrasound at a level of around 110dB and frequency 0.5Hz, depending on the suspended length and the change in height during the swing” (p. 30).

The inference is that because children often swing on swings, there are no adverse sensations. That fails to acknowledge that the experience of swinging is one that elicits many visceral sensations that are pleasant to the child as long as the sensations stop when the swing stops. The example, however, misses one major point. The duration and motion of the swing provide a smooth, sinusoidal pressure change that has two high pressure points (at the top of each swing) that occur over a period of several seconds or so. This is a completely different experience to that of pressure pulses lasting 100 msec or less. If one considers a swing with a period of 3.5 sec, there is a pressure change at 1.75 sec, resulting in a frequency of 0.57 Hz. The pressure changes are approximately 120 dB peak-to-peak, or 110 dB rms. The overall G-weighted value in this example is -60 dB, with a smooth pressure change, resulting in a net 50 dBG for the child, versus the 75 dBG experienced as a pulse for a person living near a wind turbine (calculations provided by Malcolm Swinbanks, personal communication, 2010).

The assertion that wind turbine infrasound immissions, especially when received in the bedroom of a quiet home, must be at or above the threshold of hearing to cause adverse effects has been disproved, as noted above in the works of Kelley and colleagues in the 1980s.^[19, 20, 21] The significant finding of the Kelley studies is that when the intruding infrasound is dynamically modulated short-duration pulses (generally under 100 msec and as short as 4 msec), the thresholds of sound pressure levels (SPLs) for non-auditory perception are in the range of 60 to 70 dB. In the work by one of the authors of this paper (James, with Mr. Wade Bray, INCE, of Head Acoustics, GMBH), infrasound pulsations were measured from a GE 1.5-MW wind turbine

with a blade-pass frequency of 1 Hz that reached a level as high as 100 dB.^[22] The people living in the home 'felt' the pulsations when the crests of the pressure waves were as low as 60 dB at 1 Hz. During similar measurements, Swinbanks, who has reported that he is sensitive to infrasound pulsations, was present at the test site. His experience was that he could feel the pulsations outside the home at similar SPLs.

Subsequent to the papers by Kelley and colleagues, several other studies have also reported the thresholds for significant experiences at similar thresholds, all substantially below the threshold for audibility of steady pure tones. In many of those tests, the rms SPL of the dynamically modulated blade-pass tone and its harmonics has been as low as 40 dB when using narrow-band analysis with windows of 40 to 80 sec, providing the crest of the pressure waves are 10 to 15 dB higher than the rms levels. These studies include the works of Robert Rand, INCE, and Stephen Ambrose, Bd. Cert., INCE, in their study of homes of complainants in Falmouth, Massachusetts;^[23] Walker, Hessler, Hessler, and Schomer, in their work at the Shirley Wind project in Brown County, Wisconsin, for the Wisconsin Public Health Service;^[24] and most recently, Steven Cooper's study of the Cape Bridgewater project in Victoria, Australia.^[25] All of these studies report similar findings, namely that perception, generally non-auditory in character, begins when the rms SPLs of the modulating tones are as low as 40 dB rms, with increasing impacts as the rms levels rise to 50, 60, and to 70 dB and higher levels. In all these studies, the dynamic modulation of the blade-pass tones produce pressure peaks that are often 10 dB or more, sometimes much more, than the rms values.

In the opinion of the authors, a paper prepared by Swinbanks for the 2015 conference on wind energy in Glasgow, Scotland, shows the impact of dynamically modulated infrasound on a sensitive individual—himself—along with high-quality measurements of the environments in which he experienced the sensations.^[26] That paper shows that a highly respected acoustician and scientist with expertise in infra- and low-frequency sound also responds to this acoustic energy in a way that is similar to the many complaints from others, both in the location of his tests and at other wind energy projects around the world. In the paper, Swinbanks reports that he was able to differentiate the pulsations in the test data from at least six separate wind turbines in a project consisting of 46 1.5-MW GE models. He also reports that he was able to perceive the effects of the pulsations in his home's basement, approximately 3 km from the nearest operating wind turbine, with the SPLs of the blade-pass frequency and harmonics summing to about 55 dB rms. At closer locations, he measured positive-going pressure peaks of 87 dB with corresponding negative-going peaks of equal level. It is worth noting that at the Glasgow conference,

Swinbanks presented the paper as a poster session,^[27] as he was informed by the conference moderator that time restraints prevented him from presenting his paper to conference attendees.

In the 2012 investigation of infrasound at the Shirley Wind project, where local regulations require that the Nordex 2.5-MW turbines be sited at least 1,250 ft., or 381 m, from residences, Walker et al reported infrasound levels at one of the three test homes.^[24] WTN was not audible outside the residence where infrasound was greatest, supporting the position that infrasound is at the root of at least some of the complaints. The blade-pass frequency and harmonics were clearly evident from the measurements inside that one home, and the family had moved far away for a solution.

Following the Shirley Wind team study, several members of the community conducted a series of micro barometer measurements inside homes ranging from 1,280 ft. to approximately 6 mi. from the wind turbine towers. Infrasonic tones at blade-pass frequencies and harmonics were found at all test sites, including test sites at distances of several miles or more from towers under downwind conditions. Testimony to Wisconsin's Brown County Board of Health by people with homes more than 4 mi. from the nearest wind turbines reported AHEs during the times the turbines operated. In mid-October 2014, the Brown County Board of Health went on record declaring that wind turbines at the Shirley Wind site "...are a human health hazard."^[28] That action, which appears to be a precedent in the U.S., meant that Duke Energy's Shirley Wind utility were forced to prove to the Board that the utility was not the cause of the health complaints documented in the study and voiced by community residents. The outcome could result in a shut-down order, but no final decision had been made in that case at the time of this writing. Other examples of legally ordered turbine shutdowns include those in Massachusetts^{29, 30} and Portugal.³¹

We will return to the issue of perceptibility of infrasound later in this paper, as we describe the physiological bases for perceptibility.

Statement 2: There is nothing unique about wind turbine noise, as infrasound and low-frequency noise are commonly produced by the body and by many environmental sources.

To begin, when the spectral characteristics of IWT noise, as depicted in several papers,^[24, 32, 33] are compared to the spectra of subsonic jet transport planes,^[34] five different types of aircraft,^[35] and road traffic noise,^[36] it is clear that noise generated by wind turbines has a number of unique acoustical characteristics. These comparisons reveal dissimilarities in spectral and peak levels in both the higher and lower frequency regions, including the low-frequency and infrasonic range.

Leventhall^[37] was one of the first to describe how low-frequency noise is a special noise problem, particularly to sensitive people in their homes. He indicated that annoyance to low-frequency noise increases rapidly with level, often starting just above the threshold of audibility, and that about 2.5% of the population may be 12 dB more sensitive than the average person to low-frequency noise. He also noted that the World Health Organization (WHO) places a special emphasis on low-frequency noise as an environmental problem and source of sleep disturbance, even at low levels. The WHO^[38] acknowledges that a noise consisting of a large proportion of low-frequency components may considerably increase AHEs and should be limited to below 40 dBA. Cummings^[39] notes that sound levels of 40 dBA trigger high levels of community pushback.

Jung et al^[40] experimentally identified the characteristics of acoustic emissions from large upwind wind turbines, with emphasis on ILFN. The sound spectral density showed that the blade-passage frequency component is clearly dominant, revealing up to 6-7 harmonics that generally occupy the infrasonic frequency region of 1 to 10 Hz. They voiced a concern that the low-frequency noise of the 1.5-MW and 600-kW wind turbines in the frequency range over 30 Hz would very likely lead to psychological complaints from ordinary adults.

In responding to a bylaw to restrict wind turbine infrasound in the town of Plympton-Wyoming, Ontario, Leventhall^[41] declared that “Infrasound has become the Godzilla of acoustics” (p. 2). He concluded that science does not support the conditions in the bylaw, which was largely aimed at restricting blade-passing tones, because “There is no evidence that the very low level of blade passing tones affects humans, whilst there is evidence that it does not” (p. 7). Based on the kinds of evidence just discussed, we strongly disagree.

WTN has been described as having a character that makes it far more annoying and stressful than other sources of noise at the same A-weighted level, including traffic and industrial noise.^[42, 43, 44, 45] Harrison^[42] concluded that IWTs cause annoyance in about 20% of residents living within a distance considered acceptable by most regulatory authorities, and that for many of the 20%, the annoyance and sleep disturbance lead to AHEs. Thorne^[46] has pointed out that human perception of noise is based primarily on sound character rather than sound level, and that wind turbines are unique sound sources that exhibit special audible and inaudible modulated and tonal characteristics. He states that sound levels of 32 dBA Leq outside a residence and/or above an individual’s threshold of hearing inside the home are markers for serious AHEs, especially among susceptible individuals.

Structural and human responses to low-frequency noise, including noise from wind turbines, have been described by Hubbard.^[47] Hubbard and Shephard^[48] illustrated the special characteristics of WTN by explaining its sources, pathways, and receptors. Thorne^[46, 49] described wind turbines and *wind farms* as a unique source of sound and noise, like no other noise source or set of noise sources. The sounds are often of low amplitude and shifting in character, making it difficult for people who have never been exposed to such sounds to understand the problems of those who complain about the sounds. Shepherd et al^[50] have described WTN as having characteristics sufficiently different from other, more extensively studied, noise sources to justify the application of standards different from pre-existing noise standards.

The preponderance of evidence on this point leads to the conclusion that WTN has special acoustic characteristics that distinguish it from other industrial sounds. A primary feature is that it consists of measureable energy down to below 1 Hz.^[24, 51, 52] Its sound pressure level decreases rapidly with increasing frequency from about 0.5-5 Hz. It varies in amplitude over time,^[9, 49, 51, 53, 54, 55, 56, 57, 58] it tends to have an intermittent tonal quality,^[49, 52, 59] and its characteristics vary with distance and direction.^[52, 53] It can result in an impulsive sound,^[21, 40, 49, 60] even at long distances.^[52] According to Lee et al,^[53] the swishing sounds of turbines can be perceived from all directions, but at long distances from a turbine, low-frequency amplitude-modulated sounds can be heard only in particular directions and when the SPL is sufficiently high. This effect may make the WTN seem more impulsive at long distances despite an overall SPL that is relatively low.

Furthermore, ILFN from any source, including IWTs, is well known to penetrate walls and other barriers (e.g., Minnesota Department of Health^[55]); is typically more disruptive indoors than outdoors;^[46, 47, 61, 62, 63] and is not easily masked by atmospheric sounds, including road traffic and other sources of infrasound.^[63, 64, 65, 66] The perception of low-frequency noise depends on density level, modulations, bandwidth, purity of blade-pass tones and harmonics, discrete beating tones, or other time-varying properties, and can occur even at near-infrasonic frequencies if any of these factors is present; otherwise, it might pass unnoticed.^[57, 67, 68] James^[69] describes the infrasound occurring when wind turbine blades rotate past the tower as a short pressure pulse that consists of a well-defined array of tonal harmonics below 10 Hz. If the pressure peaks are received at the same time, they sum in a linear manner that significantly raises the overall SPL. Often, however, there are many wind turbines rotating at similar speeds, but not synchronized in time. This can lead to another form of modulation as the wind turbine infrasound is perceived as rising and falling, intermittent, or pulsating with variable intensity.

A common argument of wind industry proponents—one that is sometimes raised in legal proceedings—is that humans themselves generate infrasound by virtue of their own heartbeat and breathing, at levels that can be substantially higher than an external noise source such as wind turbines. In a rebuttal to a formal statement to this effect by the Association of Australian Acoustical Consultants (AAAC), Salt has provided a definitive explanation of why the two sources of infrasound (internal vs. external) cannot be equated. In a letter addressed to the AAAC,^[70] Salt stated:

“Stimulation of the ear occurs not directly by pressure (which is why deep sea divers can still hear) but by induced motions of the inner ear fluids, which in turn move sensory tissues and motion-sensitive cells....when low frequency and infrasound enters the ear via the stapes, it causes fluid movements throughout the entire ear between the stapes in the vestibule, through scala vestibuli and scala tympani to the compliant round window membrane at the base of scala tympani. It is these fluid movements that drive sensory tissue movements and cause stimulation. In contrast, pressure fluctuations generated by the body, such as by heartbeat and respiration, enter the ear via the cochlear aqueduct, not through the stapes. The cochlear aqueduct enters the ear adjacent to the round window membrane in the very basal part of scala tympani, so the fluid flows are localized in this tiny region of the ear. As the rest of the ear is bounded by a bony shell which is not compliant, fluid flows in the rest of the ear are substantially lower so that displacements of sensory tissues are negligible. Infrasound generated by the body, because it enters through the aqueduct, therefore does not cause stimulation of the ear.”

Statement 3: There is no evidence that wind turbine noise, audible or inaudible, is the cause of adverse health effects in people, and there are no physiological mechanisms to explain how inaudible acoustic energy can be harmful.

In fact, there is ample evidence that noise in general, and especially low-frequency noise, has long-term consequences for human health.^[71, 72] For example, long-term exposure to ordinary traffic noise has been associated in a dose-dependent manner with higher risk of myocardial infarction.^[73]

Two landmark reports embodying diametrically opposing perspectives with regard to the impact of WTN on health appeared almost concurrently in 2009. One was published as a book by Dr. Nina Pierpont,^[4] a Fellow of the American Academy of Pediatrics who holds an MD degree from Johns Hopkins University School of Medicine and a PhD degree in Population Biology from Princeton University. The other report was written by a panel of seven experts (three physicians, two acousticians, an audiologist, and an audiologist/hearing scientist) commissioned by the American Wind Energy Association and the Canadian Wind Energy Association. The latter report^[15] is commonly referred to as the AWEA/CanWEA report, or white paper. These

respective reports, more than any others, quickly became the rallying cry for so-called anti-wind and pro-wind advocacy groups in the media, in the public discourse, and in court proceedings.

In her book, Pierpont^[4] coined the term *Wind Turbine Syndrome* to describe a range of symptoms reported for 38 family members (adults and children) of 10 families who lived near wind turbines. Based on telephone interviews, she treated her observations and analyses as a case-series research design. She described the syndrome as consisting of 10 classes of symptoms (enumerated below), many of which she attributed to overstimulation of the vestibular system of the inner ear by ILFN. The wind industry, in its AWEA/CanWEA report and elsewhere, has vigorously criticized her study for being non-scientific and non-peer-reviewed. In fact, Pierpont's book was critically reviewed by far more than the usual number of reviewers for a peer-reviewed journal article. While it is true that case series are prone to selection bias, and can at best suggest hypotheses, many discoveries of new phenomena begin with a case study or case series. Furthermore, an increasing body of scientific evidence supports Pierpont's observations of a relationship between WTN and AHEs. More recent laboratory research, described later in this review, suggests that a variety of health symptoms may be due to ILFN stimulation of both vestibular and cochlear components of the inner ear.

Prior to Pierpont's book,^[4] Dr. Amanda Harry^[74] and Dr. Robyn Phipps and colleagues^[75, 76] had documented the occurrence of ill effects from IWTs by use of questionnaire-based surveys of the health complaints of people living near wind projects in Cornwall, England, and Palmerston North, New Zealand, respectively. These authors concluded that a substantial number of people living near wind turbines suffer from health problems and that the cause of the disturbances was the complexity of the noise and vibration. Harry^[74] observed that the symptoms were evident for people living within a mile from the wind development and recommended that no wind turbine should be sited closer than 1.5 mi. from the nearest residents. She noted that the guidelines used at the time to site wind turbines were developed when the turbines were 20% the size of the current ones. She concluded that annoyance from noise adversely affects human well-being, and that developers are wrong when they state that WTN is not a problem. Phipps et al^[75] noted that 45% of households living within 2 km of the wind farm and 20% of households living up to 8 km away reported hearing noise from the turbines. Phipps^[76] reported on the negative consequences of noise that were evident in her own survey and in the works of others, warning that residents do not readily habituate to the presence of WTN.

The AWEA/CanWEA report^[15] has been widely used by the wind industry as a basis for its denial of AHEs from IWTs. However, the report is the product of a hand-picked group of experts, at least some of whom were known to hold positions favorable to the report's sponsors.

it was never peer-reviewed, and it shows signs of bias, such as conclusions not supported by the research referenced in the report. That white paper concluded that sound from wind turbines, including sub-audible low-frequency sound, does not pose a risk of hearing loss or any other AHE in humans, whether those health effects are described as Wind Turbine Syndrome or otherwise. It also concluded that some people may be annoyed at the presence of sound from wind turbines, including its fluctuating nature, but described annoyance as unrelated to health. Although there is indeed no evidence that IWTs causes hearing loss, the report's conclusion that ILFN does not cause AHEs, and its dismissal of annoyance as a serious entity, have been heavily criticized as erroneous. Horner et al^[77] cite many specific examples of the AWEA/CanWEA report's failure to use proper documentation, concluding that it lacks scientific merit and that it is neither authoritative nor convincing. They criticized the report's conclusion that the issue of AHEs stemming from IWTs is settled and that no more research is required, a conclusion that is rarely voiced by scientists. Horner^[78] has characterized the report as offering nothing new in its treatment of annoyance, as annoyance has long been known to result from the stress effects of exposure to noise, and he criticized the report for downplaying the relationship between annoyance and health. Phillips^[79] has indicated that the report mischaracterized the research designs used by epidemiologists. Despite widespread denial by wind industry advocates of a causal relationship between IWTs and AHEs, the vast majority of peer-reviewed papers have shown that IWTs significantly disturb sleep in at least some residents at distances and noise levels that are typical where IWTs are installed. Furthermore, not a single well-designed scientific study has found WTN to be harmless.^[80, 81]

A panel of seven independent experts was commissioned by the Massachusetts Departments of Environmental Protection and Public Health to identify any documented or potential health impacts of risks that may be associated with exposure to IWTs and to facilitate a discussion of IWTs and public health based on scientific findings. The panel generated a report^[82] concluding that scientific evidence is lacking to show that WTN leads to AHEs and that a more comprehensive assessment of WTN in populated areas is needed for establishing and refining siting guidelines and for developing best practices. Closer investigation was recommended near homes where outdoor A- and C-weighted levels differ by more than 15 dB, a strategy for detecting the presence of ILFN (e.g., Kamperman & James^[83]). The Massachusetts report has been criticized as misrepresenting the evidence it cites, as well as underestimating evidence indicative of AHEs from IWTs.^[84, 85] Schomer and Pamidighantam^[86] have described the report as a critique of the literature relating to wind turbine acoustic emissions and health effects, and one with problems similar to those it criticizes.

Some laypersons have remarked disparagingly in the media on the factual evidence—including observations and scientific reports—that shows a relationship between IWTs and AHEs. Shahan,^[87] for example, confidently states: “To date, there is no scientific evidence that anything such as ‘Wind Turbine Syndrome’ actually exists.” A common argument of wind energy advocates is that studies show that wind turbines do not lead to AHEs, or that studies that draw such a conclusion are not sufficiently scientific to establish causation. Efforts to discredit those who take a skeptical view toward the wind industry commonly use terms such as *opponents*, *detractors*, *anti-wind activists*, or in the case of Shahan,^[87] “paid anti-wind ‘experts’ who have a long history of directly testifying against wind energy in various court cases.” Such critics casually ignore the fact that many of the industry experts, including consulting acousticians and physicians, routinely testify on behalf of the industry in such cases, sometimes for substantial fees, and those individuals are rarely described as paid pro-wind experts or activists.

Numerous researchers have reported the existence of a constellation of health symptoms, either directly mirroring or closely related to those described as Wind Turbine Syndrome by Pierpont,^[4] in persons living near IWTs. Significantly, the WHO^[38] states that there is sufficient evidence that nighttime noise, irrespective of its source, is related to self-reported sleep disturbance and other health problems, and that these effects can lead to a considerable burden of disease in the population.

Sleep disturbance has been identified as a major adverse impact of IWTs.^[4, 18, 45, 47, 54, 57, 58, 72, 74, 76, 77, 79, 80, 81, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100, 101, 102, 103, 104, 105, 106, 107] Nighttime exposure to 40-dBA low-frequency noise has been shown to affect cortisol levels, a physiological indicator of stress. Those levels, following awakening, have been found to be associated with subjective reports of lower sleep quality and mood changes.^[108] Sleep is a biological necessity, and disturbed sleep is associated with a number of adverse health conditions. The WHO^[71] has concluded that there is available, good-quality evidence supporting a causal association between noise and sleep disruption. Sleep disturbance has important implications for public health and may be a particular problem in children.^[84, 94, 109]

Even if no other adverse effects were associated with WTN, sleep disturbance alone is a sufficient reason to site turbines at distances that do not disrupt sleep. Many rural communities have background, nighttime sound levels that do not exceed 25 dBA, and observable effects of nighttime, outdoor noise do not occur at levels of 30 dBA or lower.^[71] As outdoor sound levels increase, the risk of AHIEs increases, the most vulnerable populations being the first to show their effects. Vulnerable populations include elderly persons; children, especially those younger than age six; and people with pre-existing medical conditions, especially if sleep is affected.^[38, 71]

According to the WHO, there is ample evidence to link AHEs with prolonged exposure to outdoor sound levels of 40 dBA or higher. It is important to note that the WHO guidelines are based largely on industrial and transportation noise research, and not on wind turbine research. Because multiple studies (covered in this review) have indicated that WTN is significantly more annoying, has higher infra- and low-frequency sound energy, and is modulating, pulsatile, and sometimes tonal, it may impact health to a greater degree than other noises. This means that noise limits in the WHO guidelines may need to be adjusted downward when applied to WTN.

Additional factors increase the probability of sleep disruption due to WTN. The noise can be heard especially well in areas with low background noise levels, which usually occur at night. Also, lower nighttime wind speeds at ground level increase the nighttime contrast between WTN and background sound levels. Using test data taken during daytime wind conditions will result in a large underestimate of nighttime WTN levels, and thus underestimate the potential for sleep disruption.^[38, 58]

Researchers who have studied the impacts of ILFN in general and WTN specifically on health, including some who have reviewed and assessed the findings of other researchers, have attributed a variety of symptoms to ILFN exposure. Those symptoms have been variously described by different researchers, with varying degrees of overlap and detail. They are shown, in no particular order, in Table 1.

Clearly, in addition to annoyance, the most commonly experienced and least-contested health symptom suffered by people living near IWTs is sleep disturbance.^[110] Both the United Nations Committee against Torture (CAT) and the Physicians for Human Rights^[111] describe sleep deprivation as critical to human functioning. According to Physicians for Human Rights:

“Sleep deprivation ... causes significant cognitive impairments including deficits in memory, learning, logical reasoning, complex verbal processing, and decision-making; sleep appears to play an important role in processes such as memory and insight formation” (p. 22).

Table 1. Health symptoms described by different researchers as linked to exposure to infrasound and low-frequency noise, including exposure to industrial wind turbines.

Author (Year)	Reference	Symptomatology
Pierpont (2009)	4	Sleep disturbance; headache; Visceral Vibratory Vestibular Disturbance (VVVD); dizziness, vertigo, unsteadiness; tinnitus; ear pressure or pain; external auditory canal sensation; memory and concentration deficits; irritability and anger; and fatigue and loss of motivation
Leventhall (2003) Kasprzak (2014)	12 112	Vibration of bodily structures (chest vibration), annoyance (especially in homes), perceptions of unpleasantness (pressure on the eardrum, unpleasant perception within the chest area, and a general feeling of vibration), sleep disturbance (reduced wakefulness), stress, reduced performance on demanding verbal tasks, and negative biological effects that include quantitative measurements of EEG activity, blood pressure, respiration, hormone production, and heart rate
Havas & Colling (2011)	91	Difficulty sleeping, fatigue, depression, irritability, aggressiveness, cognitive dysfunction, chest pain/pressure, headaches, joint pain, skin irritations, nausea, dizziness, tinnitus, and stress
Horner (2013) Paller et al (2013)	78 113	Headaches, nausea, tinnitus, vertigo, and worsened sleep
Jeffery et al (2013)	92	Sleep disturbance; subjective complaints such as headaches, fatigue, temporary feelings of dizziness, and nausea; objective complaints such as vomiting, insomnia, and palpitations; annoyance; and reduced quality of life (QoL)
Jeffery et al (2014)	93	Negative impacts on the physical, mental and social well-being of people
Krogh et al (2012)	96	Annoyance (regarded as an adverse health effect associated with stress), sleep disturbance, headaches, difficulty concentrating, irritability, fatigue, and a variety of more-serious ailments
Minnesota Department of Health (2009)	55	Annoyance, reduced quality of life, sleeplessness, and headache
Howe Gastmeier Chapnik Limited (2010)	114	High levels of annoyance in a non-trivial percentage of persons, with annoyance associated with sound from wind turbines expected to contribute to stress-related health impacts in some persons

Author (Year)	Reference	Symptomatology
Nissenbaum (2013)	81	Sleep disturbances/sleep deprivation and the multiple illnesses that cascade from chronic sleep disturbance, which include cardiovascular diseases mediated by chronically increased levels of stress hormones, weight changes, and metabolic disturbances (including the continuum of impaired glucose tolerance through diabetes); psychological stresses that can result in cardiovascular disease, chronic depression, anger, and other psychiatric symptomatology; headaches, auditory and vestibular system disturbances; an increased requirement for and use of prescription medication; tinnitus; and vertigo
Nissenbaum et al (2012)	97	Increased sleep disruption, reduced mental health
Thorne (2013)	49	Sleep disturbance, headache, tinnitus, ear pressure, dizziness, vertigo, nausea, visual blurring, tachycardia, irritability, problems with concentration and memory, and panic attack episodes
Pawlaczyk-Luszczyńska et al (2005)	115	Problems with vision, concentration, and continuous and selective attention (especially in persons who are highly sensitive to low-frequency noise)
Pedersen (2011)	99	Annoyance (both outdoors and indoors), statistically related to SPLs; sleep interruption, diabetes, and tinnitus (at one of three test sites); annoyance outdoors, significantly related to sleep interruption, tension, stress, irritability (at all three sites), headache (at two sites), and undue fatigue (at one site); annoyance indoors, significantly related to sleep interruption (at all three sites), and to diabetes, headache, undue fatigue, tension, stress, and irritability (at one of three sites)
Roberts & Roberts (2013)	102	Vibration or fatigue, annoyance or unpleasantness
Shepherd & Billington (2011)	103	Annoyance, which has been linked to increased levels of psychological distress, stress, difficulty falling asleep, and sleep interruption
Taylor (2013)	58	Annoyance, stress, sleep disturbance, interference with daily living, headache, irritability, difficulty concentrating, fatigue, dizziness, anxiety, and reduced QoL
Ambrose et al (2012)	61	Dizziness, irritability, headache, loss of appetite, fatigue, inability to concentrate, a need to leave the home, and a preference for being outdoors (during investigations of WTN by seasoned researchers, including acousticians)
Rand et al (2011)	116	
Thorne (2011)	46	Sleep disturbance, anxiety, stress, and headaches

Author (Year)	Reference	Symptomatology
Palmer (2013)	117	Negative impacts on sleep, job stability, social relationships, care giving, pursuit of hobbies, leisure, learning, and overall health (based on interviews of residents four years after living near operational wind turbines)
Castelo Branco & Alves-Pereira (2004)	118	Vibroacoustic disease, described as occurring only after extensive exposure to high levels of infrasound
Castelo Branco (1999)	119	

Other sources quoted by the Physicians for Human Rights^[111] note that:

“A review of the medical literature reveals numerous adverse cognitive effects of sleep deprivation including impaired language skills-communication, lack of innovation, inflexibility of thought processes, inappropriate attention to peripheral concerns or distractions, over-reliance on previous strategies, unwillingness to try out novel strategies, unreliable memory for when events occurred, change in mood including loss of empathy for colleagues, and inability to deal with surprise and the unexpected” (pp. 22-23).

Another line of reasoning is that there is a cause-effect relationship between AHEs and ILFN from wind turbines that mirrors that in motion sickness. Kennedy et al^[120] made acceleration recordings during 193 standard training mission scenarios for two moving-base flight trainers. The pilots, who were of comparable age and experience in both groups, were interviewed for motion sickness symptomatology and tested for ataxia after leaving the simulators. Motion sickness incidence was high for one of the simulators, but not for the second. Ataxia scores departed slightly from expected improvements following exposure in both simulators. Spectral analyses of the motion recordings showed significant amounts of energy in the *nauseogenic range* of 0.2 Hz. The authors concluded that simulator sickness in moving-base simulations may be, at least in part, a function of exposure to infrasonic frequencies that make people seasick. Later, von Gierke and Parker^[121] advanced the notion that motion sickness may involve an intermodal sensory conflict between visceral graviceptor signals and vestibular stimulation. Schomer and colleagues^[52, 86] have argued that similarities with motion sickness may explain some of the health symptoms suffered by individuals living near IWTs, given that the inner ear is capable of responding to accelerations of the kind that lead to seasickness. These accelerations correspond to frequencies in the infrasonic range, around and under 1 Hz. Schomer^[66] states that

some persons affected by WTN may be responding directly to acoustic factors, rather than to non-acoustic factors, as argued by Leventhall.^[14]

In a rare show of cooperation between the wind industry and independent acousticians, Pacific Hydro agreed to allow acoustician Steven Cooper, a consultant for The Acoustic Group,^[25] unlimited access to its Cape Bridgewater wind project in SW Victoria, which had been in operation for about six years. The company allowed Cooper to make noise measurements and independently investigate the noise complaints of six affected residents at three residences located 650-1,600 m from the nearest turbines while the company controlled the on-off cycling of turbine operation. Given Cooper's credentials as an acoustician, the study was described as an acoustical study, as opposed to a medical study. Noise levels were based on A-, G-, and Z-weighted measurements, as well as 1/3-octave band and narrow-band measurements. Participants vacated their homes at night when necessary for Cooper to perform his acoustic studies, and they provided detailed diary accounts of their observations during on-off cycles. Those accounts included severity ratings of perceptions of noise impacts, vibration impacts, and other disturbances, which were collectively labelled as *sensations*. The sensations included headache; pressure in the head, ears, or chest; ringing in the ears; heart racing; or a sensation of heaviness. Synchronization of the timing of the residents' experiences with turbine operational data revealed heightened sensations inside their dwellings during turbine operation. Sensations were not dependent on the ability to hear or see the turbines, as residents were not aware of any of the turbines' operational characteristics. Cooper found that *sensation*, and not *noise disturbance*, was the major disturbance identified. Furthermore, sensations were most related to several different operating conditions of the turbines: at start-up, when there was an increase or decrease in power output of about 20%, and when the turbines were operating at maximum power and the wind speed increased above 12 m/sec.

Based on narrow-band data, Cooper identified a unique *wind turbine signature* (WTS) in which there was an energy peak at the blade-pass frequency and first five harmonics. Shutdown testing confirmed that the WTS, which included an amplitude-modulated signal, was present when the turbines were operating, but not in a natural environment during a turbine shutdown. Participants rated sensations as proportionally more severe as increases occurred in the magnitude of the low-frequency amplitude-modulated signature. The identification of infrasound components was consistent with earlier observations of Kelley et al.^[19] Based on his findings, Cooper recommended that further studies be conducted to determine a threshold level of the WTS that protects against adverse impacts, and that the signature concept be used in medical studies by

identifying energy from the operation of wind turbines, as the A-weighted scale inside homes is of no assistance in such studies.

In consideration of the above findings and observations, it is reasonable to conclude that IWTs cause AHEs and other unwanted disturbances. We next examine the physiological mechanisms that may explain how inaudible infrasound can be harmful.

In a recent paper, Berger et al^[122] concluded that ILFN levels are insufficient to induce AHEs, given the levels of ILFN typically produced by wind turbines, and that guidelines for audible noise are sufficient to protect human health. Their conclusions were based on measurements of indoor infrasound levels and low-frequency noise levels at distances >500 m that were similar to background levels. While we believe the design and major conclusions of their study to be faulty, their conclusions are consistent with the position taken by Leventhall and other wind energy advocates over the past decade.

In her original description of Wind Turbine Syndrome, Pierpont^[4] described a distinctive constellation of symptoms that she believed to be due to stimulation, or overstimulation, of the vestibular organs of balance as a consequence of ILFN from wind turbines. She termed these symptoms Visceral Vibratory Vestibular Disturbance (VVVD). In a follow-up report, Pierpont^[100] suggested that the observed symptoms of Wind Turbine Syndrome are due to air-borne or body-borne low-frequency sounds that directly stimulate the inner ear, both the cochlea, or hearing organ, and the vestibular organs of balance and motion detection. As discussed below, research by Salt and associates shows that responses in the cochlea suppress the perception of low-frequency sound but still send signals to the brain, signals whose function is, at present, mostly unknown. The physiologic response of the cochlea to WTN is also a trigger for tinnitus and the brain-cell-level reorganization that tinnitus represents. Although cochlear and vestibular organs are housed within the same bony (otic) capsule, evolutionary adaptations have led to selective activation of auditory or vestibular hair cells. In the presence of certain disorders of the inner ear, however, anatomical defects in the otic capsule can alter the functional separation of auditory and vestibular stimuli, resulting in pathological activation of vestibular reflexes in response to sound.^[123] The possibility that high-level ILFN can stimulate the vestibular organs lends credibility to Pierpont's suggestion and may explain the basis for symptoms that mimic other vestibular disorders. Physiologic responses from the otolith organs generate a wide range of brain responses, including dizziness and nausea, seasickness (even without bodily movement), fear and alerting responses such as startle and wakefulness, and difficulties with visually based problem-solving.^[100] One candidate for the other destination of cochlear input from the outer hair cells may be the interface between the insula and the medial surface of the transverse (Heschl's)

gyrus, where primary hearing is experienced but not recognized as sound; the latter involves adjacent secondary areas.^[124]

WTN can increase alerting responses that disturb sleep, even when people do not recall being awakened. This effect is one that clearly disturbs sleep and mental well-being out to 1,400 m (4,600 ft.) from turbines, with diminishing effects out to 3 km (3 mi.), as shown in a cross-sectional study by Nissenbaum et al.^[97]

Laboratory studies conducted by Salt and colleagues have provided evidence that clearly establishes the biological plausibility that infrasound can adversely affect health. That work shows that there are mechanisms in the inner ear that are capable of transducing infrasonic energy into a neural signal that can be transmitted to the brain, where the signals can lead to such symptoms as tinnitus, dizziness, pulsations, and sleep disturbance. Those studies by Salt and associates have involved laboratory experiments funded primarily by the National Institutes of Health and conducted mostly on guinea pigs, whose ears are very similar to human ears. Basically, electrodes were inserted into the inner ears to determine which structures respond to specific types of electroacoustic stimulation. Their findings help to explain why sound that is normally inaudible can result in the kinds of negative reactions reported by people who are exposed to wind turbine ILFN. Findings from their research indicate the following:

- (1) The inner hair cells (IHCs) of the inner ear, which are primarily responsible for transmitting signals to the brain that are interpreted as sound, are velocity-sensitive, and thus unresponsive to infrasound. The outer hair cells (OHCs), on the other hand, are displacement-sensitive and respond to infrasonic frequencies at levels well below those that are heard (i.e., interpreted as sound). This suggests that most IWTs produce an unheard stimulation of OHCs;^[56, 125, 126] specifically, at 5 Hz the OHCs can be stimulated at sound pressures 40 dB below those that stimulate the inner hair cells associated with conscious hearing.^[126]
- (2) Low frequencies, which are coded in the cochlear apex, require less low-frequency SPL to be amplitude modulated, when compared to higher frequencies, which are coded in the cochlear base. This means that amplitude modulation of audible sounds by wind turbine infrasound may be the basis for complaints of those living near wind turbines, including complaints such as annoyance or feelings of throbbing and rumbling sensations. It also means that infrasound from wind turbines need not be audible to annoy people, since infrasound can amplitude modulate sounds that are within the range of audibility.^[54]

- (3) There are several ways that infrasound could affect people, even though they cannot hear it:
 - (a) causing amplitude modulation (pulsation) of heard sounds, (b) stimulating subconscious pathways, (c) causing endolymphatic hydrops, and (d) possibly potentiating, or exacerbating, noise-induced hearing loss.^[127]
- (4) Responses to infrasound reach the brain through pathways that do not involve conscious hearing but instead may produce sensations of fullness, pressure or tinnitus, or absence of sensation. Activation of subconscious pathways by infrasound could disturb sleep.^[128]
- (5) The presence of other, higher-pitched sounds (between 150-1,500 Hz) can suppress infrasound.^[129, 130, 131] Because the ear is maximally sensitive to infrasound when higher frequency sounds are absent, this means that WTN is most disturbing to persons inside their homes at night, when background sound levels are low and higher-pitched sounds are attenuated by walls and other physical structures.
- (6) A pathway exists, through the OHCs, for infrasound to reach the brain. There, parts of the brain other than auditory centers become active and the signals are perceived as something other than sound. This pathway to the brain, which also includes the vestibular mechanism of the inner ear, means that it is biologically plausible for infrasound to produce a variety of sensations, including pulsation, annoyance, stress, panic, ear pressure or fullness, unsteadiness, vertigo, nausea, tinnitus, general discomfort, memory loss, and disturbed sleep (with chronic sleep deprivation leading to blood pressure elevation and possibly changes in heart rate).

On the above grounds, Salt dismisses the common perception that *What we can't hear can't hurt us*, and has stated unequivocally that "Wind turbines can be hazardous to human health."^[132]

Interestingly, Oohashi et al,^[133] using non-invasive physiological measurements of brain responses, found evidence that sounds containing *high-frequency* components *above* the audible range, or ultrasound, significantly affect the brain activity of healthy human listeners. It should not be considered implausible, therefore, that infrasonic stimulation can also activate the brain.

Recent research supports the plausibility of such effects. Bauer et al,^[134] using functional magnetic resonance imaging (fMRI), found a significant response down to the 8 Hz, the lowest frequency presented, to be localized within the auditory cortex. Using magnetoencephalography (MEG), significant brain responses could be detected down to a frequency of 20 Hz. The authors hypothesized that a somatosensory excitation of the auditory cortex possibly contributes at these frequencies. In a somewhat related study, He and Krahe^[135] demonstrated a significant relationship between EEG reactions under different low-frequency noise exposures and

subjective annoyance. Noise sensitivity was also found to be an important factor in most of the observations. The authors of these two studies suggested that EEG, fMRI, and MEG may serve as effective physiological measures to explain negative reactions to low-frequency noise.

Kugler et al^[136] measured spontaneous otoacoustic emissions (SOAEs) before and after stimulation with perceptually unobtrusive low-frequency sound (30 Hz) and found significant changes to occur; these changes were positively correlated in frequency and level to pre-exposure status and lasted for about 2 min after stimulation. SOAEs are narrow-band acoustic signals that are spontaneously emitted by the inner ear in the absence of acoustic stimulation, and they can be recorded simply and non-invasively in the ear canal with a sensitive microphone. Otoacoustic emissions, first reported by physicist David Kemp,^[137] are a by-product of active biophysical amplification by OHCs in the cochlea, persisting in relatively stable form for years under normal physiological conditions. The main task of the OHCs is to detect and mechanically amplify sound waves. In acting as a cochlear amplifier, OHCs actively generate mechanical energy, which is fed back into the cochlear travelling wave to maximize the sensitivity and dynamic range of the mammalian ear. In humans, non-invasive recordings of different classes of sound-evoked otoacoustic emissions (EOAEs) allow indirect access to OHC function, but only SOAE measurements can probe the cochlea in its natural state. The presence of OAEs signals a healthy ear, and their absence or changes in their response patterns can signal pathological function. The significance of the work by Kugler et al is that it reveals OHC function to be affected by a brief exposure to very low-frequency sound that is largely imperceptible. It also reveals that measures of perception severely underestimate OHC sensitivity. The authors concluded that direct quantifications of inner ear active amplification, as measured in their study, are well suited for assessing the risk potential of low-frequency sounds. In the present context, the study provides further support for the notion that what we can't hear can potentially affect us.

Motion sickness has been mentioned in this article as being among the variety of symptoms suffered by individuals living near IWTs. Recalling the work of Kennedy et al,^[120] who found evidence of motion sickness in Navy pilots subjected to acceleration during flight simulation, Schomer et al^[138] stated that it is plausible that the ear responds similarly to accelerations of a moving vehicle and acoustic pressures at infrasonic frequencies under 1 Hz, in the nauseogenic range. They suggested that the AHEs experienced as a consequence of exposure to IWTs not only bear a striking resemblance to motion sickness, but that the condition may be induced by stimulation of the otolithic organs in the vestibular system of the inner ear. That type of stimulation is purportedly worse when a person is subjected to pressure changes in a closed

cavity, including inside one's home. Further, they describe the type of research needed to verify their hypothesis.

Michaud and colleagues have recently authored a series of papers^[139, 140, 141, 142, 143, 144, 145] describing a cross-sectional epidemiological study conducted under the sponsorship of Health Canada, in which they investigated the prevalence of health effects or health indicators among a sample of Canadians exposed to WTN. The studies employed both self-reported and objectively measured health outcomes. The final sample, drawn from communities in Ontario and Prince Edward Island where a sufficient number of dwellings were located near wind turbine installations, included 1,238 participants (606 males, 632 females) living between 0.25 and 11.2 km from operational turbines. One participant between the ages of 18-79 years was randomly selected from each household. The reported response rate was 78.9% and did not significantly vary across sampling strata or provinces. Modelled A- and C-weighted WTN levels reached 46 dBA and 63 dBC, respectively, and the two levels were found to be highly correlated, which suggested that C-weighted values offered no additional information beyond that offered by A-weighted values. Only minor differences across strata were reported for age, employment, and type and ownership of dwelling. WTN exposure was not found to be related to hair cortisol concentrations, blood pressure, resting heart rate, or any of several measured sleep parameters (i.e., sleep latency, sleep time, rate of awakenings, sleep efficiency). Self-reported results obtained through an in-person questionnaire did not provide support for an association between increasing WTN levels and self-reported sleep disturbance, use of sleep medication, or diagnosed sleep disorders. Similarly, no significant association was found between WTN levels and self-reported migraines, tinnitus, dizziness, diabetes, hypertension, perceived stress or any measure of QoL. However, they observed statistically significant exposure-response relationships between increasing WTN levels and the prevalence of long-term high levels of annoyance toward noise, shadow-flicker, visual impacts, blinking lights, and vibrations.

The authors of the present report, along with a number of professional colleagues with acoustical or medical expertise, have carefully analyzed the reports by Michaud and colleagues and have concluded that the research protocol of the Health Canada study reflects shortcomings that severely undercut the conclusions that were drawn in the various reports. To enumerate the major flaws in the Michaud et al reports:

- (1) They incorrectly concluded that AHEs were not found when sound levels were below 46 dBA by failing to benchmark their "surrogate control group" against the general population. Proper analysis, using a proper control group, would have resulted in high correlations of these symptoms with decreasing distances to, and increasing noise levels from, wind

turbines. In reports of the sound-exposure data, sound levels of 30-35 dBA were significantly associated with increases in the prevalence rates of symptoms. This indicates that the 40 dBA currently used as the permissible threshold in Ontario and other Canadian provinces is not protective of the public's health and welfare.

- (2) Key health symptoms were reported primarily for non-vulnerable populations, in that younger individuals and individuals who had left their homes were excluded from participation. Those exclusions invalidate the study as a reflection of health conditions in the general population.
- (3) Evidence provided by the World Health Organization^[38] showing that exposure to noise from vehicles, railways, and aircraft is linked to serious physiological and psychological health effects at sound levels of 40 dBA and higher, and that lower levels are needed to protect the more vulnerable members of the population, was ignored in the Health Canada study. The finding that AHEs did not occur below 46 dBA should have been a warning sign to the researchers that their study design, their analyses, or both, were flawed.

Statement 4: Setback distances of 1,000-1,500 ft. (approximately 0.3-0.5 km) are sufficiently safe to protect humans from harm, regardless of height or other physical characteristics of the IWTs.

Many zoning ordinances that regulate IWTs specify the height of the turbine tower from its base to blade tip, plus 10% to 100%, as a setback distance that sufficiently protects residents against a catastrophic event such as a tower failure, a falling blade, or ice throw. Some ordinances specify a distance of twice the base-to-blade tip height, roughly 900 ft., while others arbitrarily specify slightly longer distances such as 1,500 ft. or 0.5 km. Most of the reported health symptoms have been observed at distances much greater than these setback distances. One can deduce, therefore, that *setbacks intended to protect physical health from mechanical or other traumatic failure of a wind turbine component are not adequate to protect general health and well-being.*

While terrain, weather patterns, number and size of turbines, and the turbine array itself can influence the ILFN emitted from IWTs, the two major factors are turbine size and distance from the receiver. Distance is the only practical means of achieving acceptable sound levels, as controlling the noise through the erection of barriers or enclosures near the source or receiver are not feasible or effective. Because infrasound is involved, closing windows, insulating buildings (including residences), and sleeping in basements are not normally helpful in attenuating the noise, and there is less likelihood that the emissions will be masked by wind at ground level.^[60]
^[46] Noise levels must be measured by qualified personnel, and the sound level at the residence—or arguably at the property line—is the key element in protecting the health of residents.

To protect human health, a number of researchers have recommended specific distances, while others have recommended limitations on sound levels, irrespective of the distances needed to achieve those levels. Such recommendations are based on observed or reported complaints of AHEs. Though quite specific, the recommendations vary somewhat widely, as shown in Table 2.

The recommendations in Table 2 include boundaries of distance and noise levels of 0.5-2.5 mi. and 30-40 dB, respectively, that are believed by various professionals to protect human health. Although the use of maximum permissible noise levels appears to be the optimal approach for protecting the greatest number of people, the existence of multiple acoustic and environmental factors complicates our ability to recommend a single distance or noise level that protects most residents. Those factors are covered elsewhere in this review.

Table 2. Recommended minimum siting distances and maximum noise levels of industrial wind turbines, based on the protection of human health.

Author (Year)	Reference	Distance/Level
Pierpont (2009)	4	Distance of 1.25 mi, or 2 km
Kamperman & James (2008)	83	
Nissenbaum et al (2012)	97	Minimum distance of 0.87 mi, or 1.4 km, based on experimental conditions studied
Harry (2007)	74	Minimum distance of 1.5 km from nearest turbine
Frey & Hadden (2007)	90	2 km between family dwellings and IWTs of up to 2-MW installed capacity, with greater separation for a wind turbine greater than 2-MW installed capacity
Shepherd & Billington (2011)	103	4 km, to protect against amplitude-modulated turbine noise
Position of the National Institute of Public Health-National Institute of Hygiene on wind farms (2016)	147	A minimum distance of 2 km of wind farms from buildings
Cummings (2011)	39	Distance of ½ mi or greater; noise levels within 5-10 dB of existing background conditions; sound levels below 40 dBA, or even 30-35 dBA, as levels of 40 dBA or higher trigger large numbers of noise complaints
World Health Organization (2009)	38	Outdoor sound levels <40 dBA, with vulnerable populations expected to be most affected

Author (Year)	Reference	Distance/Level
Knopper et al (2014)	148	Sound levels <40 dBA, for non-participating receptors
Horner (2013)	78	Sound levels <30 dB
Harrison (2011)	42	Sound levels limited to 35 dBA at nighttime and 40 dBA during daytime hours; 5-dBA and 4-dBA penalties, respectively, imposed for the periodic or impulsive character of turbine noise and for uncertainty in noise prediction
Thorne (2013)	49	Sound levels <32 dB LAeq outside a residence

Statement 5: Annoyance is a nuisance, but it is not a health issue.

In the past few years, the position of the wind industry has changed from a blanket denial of any impact from noise to admitting that IWT noise is annoying to a substantial portion of exposed populations, and that annoyance from ILFN is a well-accepted phenomenon. While Bolin et al^[18] and Ellenbogen et al^[82] downplay the relationship between annoyance and WTN, the larger research community has documented that ILFN from wind turbines and other sources leads to annoyance.^[12, 14, 15, 19, 21, 37, 38, 40, 42, 46, 49, 55, 58, 59, 63, 64, 74, 78, 80, 81, 90, 92, 94, 98, 99, 102, 118, 146, 149, 150]

Several investigators have concluded that annoyance increases in a dose-response relationship as distance from turbines is reduced.^[44, 89, 146] A number of studies have concluded that noise annoyance appears to be worse when nearby residents have negative attitudes and when visual annoyance or intrusive sound characteristics are also involved.^[e.g., 44, 65, 112, 146, 151] However, the annoyance from visual stimulation and the annoyance from noise may be entirely independent. The two irritants do not have to be linked. The common factor is that as one moves closer to a wind turbine, it is perceived as both larger *and* louder. One recent study,^[152] which compared visual, audible noise, and combined visual-auditory representations of wind turbines, found noise sensitivity to correlate with both noise and visual annoyance. That study also demonstrated a reciprocal influence between auditory and visual stimuli, but in essentially a direction opposite that predicted by earlier studies of wind turbine visibility and noise. Interestingly, the study showed that a visual stimulus had a mitigating effect on noise annoyance, while an auditory stimulus had a disturbing effect on visual annoyance. This finding supports the idea that humans perceive the environment holistically and in context of all perceptual information. In suggesting that auditory and visual features are processed in close interaction, it forces us to question the idea that annoyance from WTN arises largely because the turbines are visible. Given our current

state of knowledge, it seems reasonable to accept that people can be annoyed by auditory and visual irritants independently, even though there may be interactions between them.

Annoyance occurs in residents living near wind turbines at lower sound levels than for transportation noise, industrial noise, or other sources.^[38, 42, 43, 58, 64, 93] Perception and annoyance have been found to be associated with both urbanized and rural terrains.^[149] Pedersen et al.^[146] in summarizing survey data on annoyance from wind turbines in the Netherlands and Sweden, found that 25% or more of all respondents were annoyed by levels of 40-45 dBA, while about 18-20% were very annoyed by those levels. A total of 18% found outdoor levels of 35-40 dBA to be rather annoying or very annoying outdoors and 8% found those levels to be rather or very annoying indoors. For outdoor levels of 40-45 dBA, 18% and 16% were rather or very annoyed outdoors and indoors, respectively. Because such surveys tend to emphasize *noise* from wind turbines, results often reflect levels of annoyance that relate more directly to audible sounds, as opposed to infrasound.

While few would argue that noise from wind turbines annoys a substantial percentage of nearby residents, there is disagreement over whether it leads to AHEs. Colby et al.^[15] stated that:

“...there is no evidence for direct physiological effects from either infrasound or low frequency sound at the levels generated from wind turbines, indoors or outside” (p. 3-8).

They reasoned, therefore, that annoyance is not a pathological entity. Their basic contention was that although wind turbines produce infrasound, it is not harmful because people can't hear it. They contended that while some people may be annoyed by the sound from wind turbines — presumably audible sound—annoyance is primarily due to the fluctuating nature of the noise and personal attitudes. In their view, it is a psychological reaction, as opposed to a direct physiological reaction to sound. As noted above, however, several investigations^[44, 89, 146] have found a dose-response relationship to exist between measured or estimated sound levels and annoyance. IWT noise emissions have been found to be a mediator between exposure and sleep disturbance and psychological distress,^[89] and to be directly associated with stress.^[e.g., 104]

The documented health symptoms from exposure to wind turbines are often stress-related and exacerbated by sleep disorders; they appear to be mediated through both direct and indirect pathways, and the result can be serious harm to human health.^[92] There is an association between WTN, stress, and well-being, and this association is a potential hindrance to psycho-physiological restitution.^[58, 98] The WHO has described annoyance as a critical health effect, in that in some people it is associated with stress, sleep disturbance, and interference with daily living.^[38] A range of symptoms, often described as stress responses, have been associated with

WTN in people living in the vicinity of wind projects. As Pierpont^[4] and others have noted, these symptoms include headache, irritability, difficulty concentrating, fatigue, dizziness, anxiety, and sleep disturbance. Regardless of whether the perceived impacts of noise from wind projects are physiological or psychological in nature, they are considered to cause AHEs through sleep disturbance, reducing the quality of life and serving as a source of annoyance that sometimes leads to stress-related symptoms.^[71] The potential of environmental noises to induce stress reactions is well known. These reactions are dependent on how the noises are interpreted in the central nervous system; medical effects such as increased blood pressure, for example, are known to result from prolonged noise exposure.^[153]

Generally, models that explain the relationship between noise and health fall into two broad




Figure 1. Three models representing the relationship between noise and health: the biomedical model (a) stipulating a direct causal relationship and indirect models (b and c) containing moderators and mediators (Adapted from original source and used with permission of first author, Daniel Shepherd).^[50]

categories, based on pathways that are *direct* or *indirect*. Figure 1, which is a modification of a figure from Shepherd et al,^[50] depicts three models, one direct and two indirect, that have been described in the contemporary literature. The first (Fig. 1a) represents a direct pathological relationship between

an environmental parameter (e.g., noise level) and a target organ that affects health. For example, in this model, noise can affect both cognition and sleep, and thus directly impact health. An alternative approach (Fig. 1b) distinguishes between direct health effects and psychosomatic illness. This approach suggests that any physiological illness coinciding with the onset of WTN may be caused by a negative psychological response to the noise, and not the noise *per se*. Any anxiety or anger resulting from the presence of WTN induces stress and strain that, if maintained, can eventually lead to AHEs. Another explanation that involves an indirect pathway from sound to health effects is one that is consistent with the WHO's definition of health.^[38] That model (Fig. 1c) recognizes the role of environmental moderators, or mediators, in the determination of whether a sound is (unwanted) noise, and, if so, whether or not the noise

negatively impacts health. Mediators include factors such as degree of urbanization, house type, and sound level, and psychological and demographic moderators such as age, gender, education, employment status, attitudes to wind energy, noise sensitivity, and whether the individual receives a monetary return from the turbines. In this model, sleep disruption plays a major role in producing AHEs, with annoyance and sleep disruption being intervening factors between noise and AHEs for some people.

Authors of a recent study,^[154] which focused on the province of Ontario, acknowledge both the link between annoyance and health and the possibility that wind projects can exacerbate psychosocial health problems through social processes such as intra-community conflict. They list socially mediated health concerns, distribution of financial benefits, lack of meaningful engagement, and failure to treat landscape concerns seriously, as the core stumbling blocks to a community's acceptance of wind energy development.

Statement 6: Noise cannot account for all of the complaints of people living in the vicinity of wind turbines; there must be another, unknown reason for the complaints.

Havas & Colling^[91] have observed that wind turbines generate electromagnetic waves in the form of poor power quality (*dirty electricity*) and ground current, and speculate that these waves can adversely affect those who are electrically hypersensitive. McCallum et al^[155] performed magnetic field (EMF) measurements in the proximity of 15 Vestas 1.8-MW wind turbines, two substations, various buried and overhead collector and transmission lines, and nearby homes in the vicinity of Goderich, Ontario, during high-wind, low-wind, and shut-off operational stages. They concluded that there is nothing unique to wind farms with respect to EMF emissions, finding that magnetic field levels in the vicinity of wind turbines were lower than those produced by many common household electrical devices and that levels were well within any existing regulatory guidelines with respect to human health.

Although at least a few of the health symptoms mentioned above have been self-reported by individuals who are exposed to electromagnetism, clinical trials to date suggest the link between health complaints and exposure to electromagnetism to be a purely psychological one, or a nocebo effect, in that self-described sufferers of electromagnetic hypersensitivity are unable to distinguish between exposure and non-exposure to electromagnetic fields.^[156] Another review paper^[157] found no convincing scientific evidence that symptoms are caused by electromagnetic fields. However, one cannot rule out that the design of the experiments upon which the review papers drew their conclusion may have missed some unique characteristic that could account for the anecdotal evidence. (See our earlier statements describing how failure to identify infrasound

pulsations as a causal factor for perception at pressure levels below those needed for audibility have led some to conclude that IWT infrasound causes no harm.) When faced with health complaints from families who live near IWTs, especially when there are repeated instances of symptoms that wax and wane with alternating sequences of exposure and non-exposure, and especially when those families have taken the drastic step of abandoning their homes, it is unreasonable to argue that noise is not the cause of the complaints. Even if other factors such as electromagnetic waves are the root cause of a given complaint, it is still the placement of turbines too close to those residents that is the most likely cause of the problem.

Unfortunately, not as much is known about the effects of electromagnetism as is known about ILFN. At this point in time, therefore, it is reasonable to conclude that more people who live near wind turbines are negatively affected by ILFN than by hypersensitivity to dirty electricity or ground current, as measurable levels of ILFN from wind turbines are highly associated with individual complaints. When Stigwood et al^[57] studied and analyzed complaints at over 75 wind developments in the U.K., they found that identifying the problems was straightforward, occurrence was common (i.e., some residents reported problems in all developments), all developments generated excess amplitude modulation (AM), and AM was the cause of the vast majority of the complaints. These findings have recently been reinforced by Cooper's work^[25] in Australia.

Statement 7: Infrasound from wind turbines is sufficiently correlated to the A-weighted sound emissions to allow an A-weighted model to be used to predict how much infrasound is present in homes.

This statement is not typically stated explicitly, but it is one that is inherent in the positions commonly taken by wind energy advocates and regulatory bodies through their interpretations and acceptance of research on WTN, which is based largely on A-weighted levels. As noted in many previous papers, including one of our own,^[101] the continued use of the A-weighting scale in sound level meters is a major basis for misunderstandings that have led to acrimony between advocates and opponents of locating wind turbines in residential areas. The dBA scale was devised as a means to incorporate into measurements of environmental and industrial SPLs the inverse of the minimum audibility curve^[158] at the 40-phon level. It is typically used, though, to specify the levels of noises that are more intense, where the audibility curve becomes considerably flattened, obviating somewhat the need for A-weighting. Use of the A-weighted scale is mandated or recommended in various national and international standards for measurements that are compared to damage-risk criteria for hearing loss and other health effects resulting from occupational or environmental noise exposure. It drastically reduces sound-level

readings in the lower frequencies, beginning at 1,000 Hz, and reduces sounds at 20 Hz by 50 dB. For WTN, the A-weighting scale is especially inappropriate because of its devaluation of the effects of ILFN. Many authors have commented on its inadequacy. For example, Pederson and Persson Waye^[159] state:

“There is... support both from experimental and field studies that intrusive sound characteristics not fully described by the equivalent A-weighted sound pressure level contribute to annoyance with wind turbine noise” (p. 4).

A number of researchers have recommended comparing C-weighted measurements to A-weighted measurements when considering the impact of sound from wind turbines.^[10, 12, 37, 61, 67, 75, 76, 83, 101] According to these sources, the presence of infra- and low-frequency sound is generally indicated when the difference between levels on the two scales differs by 10-20 dB. When such differences are observed, the use of third-octave or linear-scale measurements is typically recommended (for example, see Shepherd et al^[50]). Other weighting scales have been suggested for wind turbine applications, but at present, linear-scale or narrow-band measurements, used in conjunction with a conventional sound level meter (with low-frequency microphone) and micro barometer, offer the best potential for accurately and completely describing the soundscape in the vicinity of IWTs.

As noted above, Cooper^[25] has suggested that A-weighted levels, measured inside homes, are not likely to be useful indicators of AHEs. That report concluded that A-weighted levels are not a valid index of protection from AHEs and recommended the further exploration of a newly developed *wind turbine signature* scale, based on the discovery of its capability to quantify the amplitude-modulated peak energy in the infrasonic frequency region. That scale was shown to be directly linked to a variety of adverse bodily sensations when nearby turbines were operating or undergoing transitions in operation.

Although A-weighted sound level measurements have been the *sine qua non* for specifying environmental and occupational noise levels for many decades, we must recognize the inherent inadequacies of applying the A-weighting scale to quantifying noise emitted by IWTs. Bray^[160] goes even further by noting that people, and not electronic devices, are the ultimate analysts of data that affect their responses to sound, making the point that people's responses should be given the credence they deserve, and not be devalued when physical measurements fail to confirm them.

Statement 8: Wind Turbine Syndrome has not been accepted as a diagnostic entity by the medical profession, so medical professionals cannot diagnose or treat it.

Currently, Wind Turbine Syndrome is not included in the International Classification of Diseases (ICD) coding system, which is used globally for purposes of establishing categories for diagnosing diseases and other health conditions, and as a basis for reimbursing medical providers for diagnostic and treatment services. Yet, of the 10 symptom sets comprising Pierpont's Wind Turbine Syndrome,^[4] at least seven are included as a category or subcategory in the newly revised (ICD-10) coding system. The fact that the syndrome itself is not included may be due to its relatively recent discovery, but is more likely due to the fact that the syndrome consists of symptoms that are highly variable from person to person and affect a minority of the exposed population.

Especially in legal proceedings, it is important to distinguish between the terms *differential diagnosis* and *causation assessment*. It is the latter that is most often the subject of such proceedings. Attorneys and expert witnesses often get the terms confused. Differential diagnosis refers to the identification of disorder(s) that may account for a particular complaint or symptom complex. It rarely deals with the external cause of the disorder. Causation assessment, on the other hand, typically requires an evaluation of whether potential causative agents have irritating properties; a determination of the approximate amount of exposure, or dose, of that agent, and the timing between exposure (and non-exposure) and the occurrence of symptoms; and an assessment of whether alternative potential causes of the disorder can be ruled out. These latter steps are not necessarily considered part of the diagnosis.

Notwithstanding the fact that Pierpont herself is a practicing pediatrician, a couple of recent developments would appear to increase the prospect that medical personnel will soon be able to establish Wind Turbine Syndrome, by that or a similar label, as a clinical entity caused by exposure to WTN. Dr. Robert McMurtry, a physician who is a special advisor to the Canadian Royal Commission on the Future of Health Care, and a long-time advocate for more effective public involvement in healthcare policy, recently published a set of highly specific criteria for establishing such a link. McMurtry^[161] originally proposed a case definition that identifies first-, second-, and third-order criteria, as well as specified circumstances and symptoms that must be established before AHEs can be attributed to wind turbine exposure. According to those criteria, probable AHEs are present when:

- (1) All four of the following first-order criteria are met: (a) The individual resides within 5 km of IWTs, (b) Health status is altered following the start-up of or initial exposure to, and during

the operation of, IWTs (a latent period of up to 6 months may be allowed), (c) Amelioration of symptoms occurs when more than 5 km from the environs of IWTs, and (d) Recurrence of symptoms occurs upon return to the environs of IWTs within 5 km.

- (2) At least three of the following second-order criteria are met (occurring or worsening after the initiation of operation of IWTs): (a) Compromised quality of life, (b) Continuing sleep disruption, difficulty initiating sleep, and/or difficulty with sleep disruption, (c) Annoyance producing increased levels of stress and/or psychological distress, and (d) A preference to leave the residence temporarily or permanently for sleep restoration or well-being.
- (3) At least three specified symptoms occur or worsen following the initiation of IWTs, those symptoms referred to as third-order criteria that fall within the following categories: (a) Otological and vestibular disorders, (b) Cognitive disorders, (c) Cardiovascular disorders, (d) Psychological disorders, (e) Regulatory disorders, or (f) Systemic disorders.

To be confirmed as AHEs from WTN exposure, McMurtry indicated that consideration should be given to other stressors present in the community, that sleep studies be carried out if at all possible, and that a licensed physician be able to rule out alternate explanations for AHEs. These alternate explanations include substantial barometric changes from prevailing winds, a stressful home environment, and psychological and/or mood disorders, all of which can normally be ruled out when symptoms subside or disappear when the individual leaves the vicinity of the wind turbines. Apart from these three factors, he indicates that there are very few, if any, other health conditions that can mimic those caused by exposure to wind turbines and at the same time meet the three orders of criteria outlined in his case definition. More recently, McMurtry and Krogh^[162] published a revised case definition, in which the third-order criteria—which are commonly present—are not considered essential elements. In both papers, the authors acknowledged that the identification of IWTs as the cause of adverse health symptoms is a complex emerging issue that requires further study to validate the criteria. They proposed key elements that ought to be included in any model used to assess the validity of the case-definition criteria.

McCunney and colleagues^[163] have challenged those case definitions as having poor specificity, leading to a substantial potential for false-positive assessments and missed diagnoses. A potential fallacy in this challenge is that the authors unnecessarily conflate the concept of case definition for medical practitioners with that of an epidemiologic research plan. The case definitions presented by McMurtry^[161] and McMurtry and Krogh^[162] represent guidelines for medical doctors whose individual patients are experiencing new or unusual symptoms. It is erroneous to purport that a physician's mental process can be encapsulated into a set of equations, especially

during the earliest stages of developing a case definition. The criticisms of these early case definitions should not deter physicians from attempting to evaluate and treat patients who report AHEs after living in the vicinity of IWTs. This area may indeed benefit from further study. Our view, however, is that such criteria provide an adequate starting point for guiding medical practitioners.

Dr. Steven Rauch, an otolaryngologist at the Massachusetts Eye and Ear Infirmary and a professor at Harvard Medical School, recently declared that he believes Wind Turbine Syndrome to be a real phenomenon.^[164] As reported by numerous websites and newspapers, multiple patients have sought treatment from him for AHEs stemming from consistent exposure to IWTs. Rauch compares the syndrome to migraine headaches and believes that people who suffer from migraines are among the most sensitive to the effects of WTN, and he has stated that the wind industry aims to suppress the notion of Wind Turbine Syndrome by blaming the victim.

Given these developments, it is possible that the medical profession may someday embrace Wind Turbine Syndrome—by that or another name—as a clinical entity. This prospect is encouraging, as such acceptance by the profession will facilitate efforts to protect individuals from the harmful health effects of exposure to IWTs. Even though it may be some time before such a diagnostic label is formally acknowledged as an ICD code, it is currently possible for physicians to identify many of the specific symptoms associated with wind turbine exposure and to bill for diagnosing and treating those symptoms, with or without regard for their underlying cause. Paradoxically, it is apparently the case that the most effective treatment for AHEs associated with WTN exposure is non-medical in nature; it is to recommend that patients physically remove themselves from the vicinity of IWTs.

Statement 9: Peer-reviewed epidemiological literature is the only acceptable basis for proving a causative relationship between wind turbine noise and adverse health effects.

This issue runs as a thread through virtually all the other issues addressed in this paper, as it relates to the kind of scientific evidence frequently called for, especially in legal settings, to prove that IWTs are the cause of AHEs. While personal physicians of complainants in legal cases are often considered the only expert witnesses qualified to establish *specific causation*, others can testify to *general causation*, which is the methodology by which scientists determine whether or not an agent is responsible for producing a particular disorder. In general, this requires evaluation of the scientific and medical literature to identify documented instances of health-related conditions arising from exposure to specific agents and, when available, the dose-response relationships between agents and their effects. This process is highly similar to that of

causation assessment, as explained above, and it does not necessarily require the input of a complainant's personal physician, although such input may be helpful. In legal cases involving WTN, it is critical that expert witnesses in acoustics and health be able to reconcile their positions with the reports and standards of the WHO,^[165] the International Organization of Standards (ISO),^[166] and the American National Standards Institute/Acoustical Society of America (ANSI/ASA)^[167] that have linked low-frequency noise to symptoms of the type involved in complaints. These acoustical documents and research reports are seldom, if ever, included in literature reviews used by the industry to deny potential health risks. If challenged on the validity of the available evidence, acousticians need to be knowledgeable of the relevant acoustical standards and make sure that they are understood by all parties. In reality, the wind industry's almost universal refusal to cooperate with researchers has made it virtually impossible to conduct proper acoustical or epidemiological studies. The industry has been largely unwilling, or claims it is unable, to shut down or modify operations of its turbines for experimental purposes. To date, such a situation has rarely occurred, most notably in the case of the Cape Bridgewater study.^[25]

The veracity of Statement 9 is strongly challenged by the classic address by Sir Austin Bradford Hill,^[168] Professor Emeritus of Medical Statistics, University of London, to the newly founded Section of Occupational Medicine of the Royal Society of Medicine. In his essay, Hill shared his thinking about association and causal evidence surrounding environmental disease. He posited nine elements that are critical in establishing causation:

- (1) *strength* (strength of observed relationships),
- (2) *consistency* (consistency, or repeatability, of relationships, based on observations by different persons, in different places, under different circumstances, and at different times),
- (3) *specificity* (causation is indicated if the association is limited to specific individuals and to particular sites and types of disease and there are no associations with other factors),
- (4) *temporality* (there is a clear temporal relationship between outcomes and periods of exposure and non-exposure),
- (5) *biological gradient* (a dose-response relationship exists),
- (6) *plausibility* (causation is more likely when certain outcomes are biologically plausible, or possible, a caveat being that plausibility depends on the biologic knowledge of the day; this element is best expressed in the statement: "When you have eliminated the impossible, whatever remains, however improbable, must be the truth" (p. 10),

- (7) *coherence* (the cause-and-effect interpretation of data should not seriously conflict with generally known facts of the natural history and biology of the disease),
- (8) *experiment* (experimentation or semi-experimental evidence, even if only occasional, can reveal the strongest kind of evidence for causation), and
- (9) *analogy* (the recognition that similar cause-effect relationships have occurred under similar conditions).

Hill states:

“What I do not believe (is) ...that we can usefully lay down some hard-and-fast rules of evidence that must be obeyed before we can accept cause and effect. None of my nine viewpoints can bring indisputable evidence for or against the cause-and-effect hypothesis and none can be required as a *sine qua non*. What they can do, with greater or less strength, is to help us to make up our minds on the fundamental question – is there any other way of explaining the set of facts before us, is there any other answer equally, or more, likely than cause and effect?... No formal tests of significance can answer those questions. Such tests can, and should, remind us of the effects that the play of chance can create, and they will instruct us in the likely magnitude of those effects. Beyond that they contribute nothing to the ‘proof’ of our hypothesis” (p. 299).

Hill makes this final observation in his essay:

“All scientific work is incomplete – whether it be observational or experimental. All scientific work is liable to be upset or modified by advancing knowledge. That does not confer upon us a freedom to ignore the knowledge we already have, or to postpone the action that it appears to demand at a given time” (p. 300).

Extrapolating from Hill’s essay, the totality of our knowledge gained from the available evidence must be considered when examining the link between WTN and AHEs. Fortunately, in addition to experimentation, this evidence includes simple tools that are useful, particularly if we are willing to recognize their collective value. Those tools begin, but do not end, with adverse health reporting.

Dr. Carl Phillips, a specialist in epidemiology and science-based policy making, and a former professor of public health, has stated:^[169]

“In cases of emerging and unpredictable disease risk, adverse event reports are the cornerstone of public health research. Since it is obviously not possible to study every possible exposure-disease combination using more formalized study methods, just in case an association is stumbled on, collecting reports of disease cases apparently attributable to a particular exposure is the critical first step” (p. 304).

He gives familiar examples of hazards revealed by adverse event reporting, including infectious disease outbreaks and side effects from pharmaceuticals. He points out that:

“Pharmaceutical regulators rely heavily on clearinghouses they create for adverse event reporting about drug side effects (and often become actively concerned and even implement policy interventions based on tens of reports)” (p. 304).

Phillips indicates that the case of wind turbines and health fits the same pattern. He describes adverse event reporting as a special type of case study—sometimes denigrated as anecdotes—that generally reports on the rapid onset of a disease that appears to be related to a particular exposure. He advocates self-reporting of adverse events as a highly useful approach in studying the health effects of wind turbines. In addition, he advocates the use of case-crossover experiments as useful and well-accepted sources of epidemiologic information, stating that they are intuitively recognized by both experts and laypersons seeking to assess whether an exposure is causing specifiable outcomes.

Other forms of evidence, all considered scientific, have been or can be used to determine the impacts of WTN on health. These include case studies, case-series studies, and other pre-experimental, quasi-experimental, true experimental, correlational analysis, and single-subject designs. Single-subject designs, like the case-crossover design used by epidemiologists, can also be applied across multiple individuals to reveal relationships between specific interventions and changes in outcomes in individuals or groups. In both designs, subjects serve as their own controls while crossing over from one treatment to another (A vs. B) during the course of the experimental trial. Both are flexible designs and useful in studying events that are infrequent or sporadic. Numerous individuals living near IWTs have experienced health symptoms that have waxed and waned during repeated cycles of exposure (A) and non-exposure (B), which indicates that the wind industry has unwittingly engaged individuals and families worldwide in a series of quasi-empirical studies for many years, without obtaining informed consent from un-enrolled subjects, typically by downplaying any concerns about potential health impacts. The outcomes from these experiments offer some of the strongest evidence available that there is a causative link between WTN and AHEs in some individuals.

According to the WHO,^[170] epidemiology is “the study of the distribution and determinants of health-related states or events (including disease), and the application of this study to the control of diseases and other health problems. Although the randomized clinical trial (RCT) is generally considered the *gold standard* of designs for establishing causation, various methods can be used to carry out epidemiological investigations: surveillance and descriptive studies can be used to study distribution; analytical studies are used to study determinants.” Epidemiology uses a

systematic approach to study the differences in disease distribution in subgroups and allows for the study of causal and preventive factors.^[171] Descriptive epidemiological studies describe the occurrence of outcomes, and analytical studies reveal associative linkages between exposure and outcomes. Descriptive studies include primarily case reports and case-series studies. Analytic designs include experimental studies such as community trials and randomized controlled clinical trials, and observational studies, in which observations can be made retrospectively, concurrently, or prospectively. Observational studies include those in which either grouped (i.e., ecologic) or individual data are collected, the latter normally favored by the scientific community. Those designs involving individual data include cross-sectional, cohort, case-control, and case-crossover studies. Although epidemiological studies rely on statistical analyses of relationships between exposure to specific agents and AHEs in relatively large samples of the population, they are not aimed at revealing the cause of a disease or disorder in specific individuals. A cogent summary of research designs used in *evidence-based medicine* can be found online.^[172]

Cross-sectional studies survey exposures and disease status at a single point in time in a cross-section of the population. They measure prevalence, not incidence, of a disease process, and have the disadvantage of difficulty in establishing the temporal sequence of exposure and effect. Also, rare and quickly emerging events may be difficult to detect. Their major advantage is that data can be collected at the same time on all participants, which means the study can be completed in a relatively short time. Notably, several cross-sectional investigations of the effects of WTN exposure have been reported.^[44, 97, 98, 99, 104, 149] These studies serve as major contributions to the scientific literature on the subject.

Cohort studies involve an observational design in which a sample of the population is followed to discover new events.^[75] They compare individuals with a known risk factor or exposure with others without the risk factor or exposure and aim to determine whether there is a difference in the risk, or incidence, of a disease over time. They tend to be the strongest observational design, especially when the data are collected prospectively, as opposed to retrospectively. Compared to the cross-sectional design, cohort studies tend to require more time, which partially explains the paucity of such studies involving wind turbine exposure.

Case-control designs compare exposures in diseased cases vs. healthy controls from the same general population. Specific disease states must be known prior to initiation, and exposure data must be collected retrospectively. This design can be applied to cases of IWT exposure, despite the fact that it requires the cooperation of affected and unaffected segments of the same population, a circumstance made difficult by attempts on the part of energy companies to

maintain confidentiality and privacy as a means to facilitate wind turbine development in areas involving both participants and non-participants.

In case-crossover studies, which are a special type of case-control design, the *case* and *control* components reside in the same individual. This design is especially useful in investigating triggers of a disease process within an individual. In the behavioral sciences, it is commonly referred to as a *single-subject design*, as already described. The case component signifies the hazard period, which is the time period before the disease or event onset (e.g., exposure to IWTs), and the control component signifies a specified time interval other than the hazard period, namely the non-exposure interval. As already mentioned, wind companies themselves have unwittingly subjected residents to the basic conditions of this design, and results clearly suggest that exposure to WTN leads to a variety of health complaints in some individuals and families. Phillips^[79] argues that:

“A case-crossover study is one of the most compelling sources of epidemiologic data. It consists of observing whether someone’s outcomes change as their exposure status changes. This is often not possible because the outcomes only happen a single time as a result of long-term exposure (e.g., cancer) or the exposure cannot be changed. But the observed effects of turbine exposure lend themselves perfectly to such studies because the exposure is transient and the effects, while not instantaneous in their manifestation or dissipation, are generally transient over a period of days or weeks at most. Thus, unlike a case of a lifelong exposure or non-transient disease, where we can only make one observation about disease and outcome per person, the effects of turbines allow multiple observations by the same person, including experimental interventions” (p. 305-306).

Turning to experimental designs, the clinical trial is considered the ideal design to test hypotheses of causation. In a clinical trial, the investigator has control of the exposure to an extent similar to a laboratory experiment. The subjects generally are randomly assigned to one of at least two groups, an experimental and a control group. The experimental group receives the treatment (i.e., exposure in the case of wind turbines) and the control group does not; instead, it usually is subjected to a condition that simulates a generic treatment of some type, and the purpose and procedures of the control condition are explained only after the experiment ends.

A fully developed clinical trial of residents who live near wind turbines has never been conducted, and the reasons are fairly clear if we consider the circumstances surrounding such a trial. In a rigorous trial done to establish the link between AHEs and WTN, the investigator would randomly assign hundreds of people selected from the general population—including adults and children, elderly adults, and chronically ill adults—to either an experimental or a control group. Randomization would control for pre-experimental biases toward or against wind

energy, as well as for other factors that could confound the outcome. The experimental group would be required to spend a significant period (day and night for weeks or months) in homes located between approximately 1,000 ft. and several miles from the nearest wind turbine. The control group would be required to take up residence several miles or more away from the nearest wind turbine, where they would presumably be free from any effects due to extraneous noise or infrasound. Homeowners who leave their homes, as well as research participants occupying those homes, would have to adjust to new residences and modify their work and school activities, eating patterns, and overall lifestyles. Participants in both groups and at least some of the homeowners who vacate their homes for the experiment would have to be reimbursed for their participation, as well as for the costs incurred as a result of their participation, and the research staff would also have to be paid. To maintain some control across sites, the average age and health status within each group should be equivalent, and data would have to be gathered regarding such factors as turbine size, wind speed and other weather conditions, length of time the turbines were operating, terrain, the exact distance of each participating family from the nearest turbines, and actual noise levels present outside and inside the homes. Scientifically rigorous methods for measuring low-frequency noise and infrasound would have to be agreed upon and used. Although self-report via a survey technique could be part of the experimental design, medical examinations and physiological measurements, including sleep studies, should also be incorporated into the research protocol.

While possible, it is not practical to expect such a study design, in its ideal form, to be implemented. Aside from the difficulty of recruiting and enrolling enough families in enough geographic areas to form statistically strong samples, legitimate ethical questions should be raised regarding the exposure of individuals, especially children and other vulnerable individuals, to potentially hazardous conditions. One might conjecture, however, that consent to participate in such a study could be gained from fully informed adults because the effects of WTN are widely believed to be reversible when a period of non-exposure follows a period of exposure.

Statement 10: The nocebo effect, a manifestation of psychological expectations, explains why people complain of adverse health effects when living near wind turbines.

This statement is the core position of some of the most outspoken critics of the view that IWTs cause AHEs. Any discussion of this statement should begin with an acknowledgment that human behavior and beliefs are highly variable and are often driven by psychological and emotional influences, and not just by observations, logic, intellectual knowledge, or cognitive thought processes. It is not surprising, therefore, that some have adopted the view that negative reactions

to wind turbines are based primarily or solely on psychological expectations. Our analysis of the limited literature on the topic leads us to state unequivocally that it is lacking in scientific rigor. Even if the results were as described, the existing studies and observations do not support a conclusion that psychological forces are the only or even primary explanation for most of the negative reactions toward IWTs. Here, we will critically review four papers, all supporting a psychological explanation for the negative reactions.

Chapman et al^[173] tested four hypotheses relevant to psychogenic explanations of the variable timing and distribution of health and noise complaints about wind farms in Australia. They obtained records from the wind companies of complaints about noise or degraded health from residents living near 51 wind projects operating between 1993 and 2013 and corroborated those records with complaints documented by three government public agencies, news media records, and court affidavits. Complaints were expressed as proportions of estimated populations residing within 5 km of a wind project. The authors concluded that historical and geographical variations in complaints were consistent with psychogenic hypotheses expressing health problems as “communicated diseases,” with nocebo effects likely to play an important role in the etiology of complaints.

Nocebo effects are commonly described as being the opposite of placebo effects. While the *placebo effect* usually refers to a positive reaction to an inert substance—the placebo—the *nocebo effect* refers to a negative reaction to an inert substance—the nocebo. Both effects are psychogenic, but known to exert powerful influences on human physiology, behavior, and attitudes. Essentially, Chapman and his supporters believe that psychogenic reasons are the basis for health complaints about wind turbines, which they believe to be harmless.

Our major criticism of the work of Chapman et al is that wind companies typically engage in practices that discourage local residents to complain. These companies require participating residents to sign contracts before turbines are constructed and before the residents can receive compensation for leasing their land, and they often request non-participating residents to sign contracts prior to initiating a project. Those contracts, which are binding, often include gag clauses that effectively limit resident complaints. The contracts have often stipulated not only that residents refrain from voicing negative views of the wind project, but also that they support the development of future projects. Such conditions create an atmosphere in which it is highly unlikely that the records of wind companies, governments, courts, or the media will sufficiently reflect all of the complaints that residents have and would voice under less-restrictive circumstances. We argue that the only way to gather accurate data on such complaints is through a survey of either an adequate sample of residents living near multiple wind projects or all such

residents, where residents are free of restrictions by the wind companies. Such data would allow a valid determination of the proportion of residents who experience adverse effects. Whether that proportion is large or small, we could all act on the basis of factual evidence, as opposed to incomplete observations.

Another shortcoming of the study by Chapman et al,^[173] which is less well documented but a factor observed in legal cases in which the present authors have been involved, is that residents near IWT projects tend to be delayed in their responses to AHEs. Many of them believe their health problems to be linked to other causes before suspecting that the turbines are the cause. Some or most of these individuals were supporters of wind projects prior to experiencing such problems, as Phipps et al^[75] noted in New Zealand. The delay factor would mean that the types of records used by Chapman et al would not likely reflect the reactions of many affected residents.

Crichton and colleagues conducted two laboratory investigations, each of which has bolstered the argument that negative reactions to audible and inaudible WTN can be explained by psychological expectations. Crichton et al^[174] conducted what they described as a sham-controlled double-blind provocation study, in which participants were exposed to 10 min of infrasound and 10 min of sham infrasound. Fifty-four participants were randomized to high- or low-expectancy groups and presented with audio-visual information, using material from the Internet that was designed to invoke either high or low expectations that exposure to infrasound causes specified symptoms. High-expectancy participants reported significant increases, from pre-exposure baseline assessment, in the number and intensity of symptoms experienced during exposure to both infrasound and sham infrasound. There were no symptomatic changes in the low-expectancy group. Healthy volunteers, when given information about the expected physiological effect of infrasound, reported symptoms that aligned with that information, during exposure to both infrasound and sham infrasound. According to the authors, results suggest that psychological expectations are sufficient to explain the link between wind turbine exposure and health complaints.

Punch^[175] has criticized that study as methodologically weak, on the following grounds:

- (1) Subjects were never exposed to infrasound that adequately represented that to which residents near wind turbine projects are subjected. It is extremely unlikely that the employed studio woofer was capable of producing a 5-Hz stimulus; the authors did not describe or show a graph of the output spectrum. Even if a true infrasound stimulus was produced by their equipment, 40 dB (presumably SPL) was not sufficient to represent the level of

infrasound commonly produced by IWTs. Even if a sufficient stimulus had been produced to represent wind turbine infrasound, a 10-min exposure would have been meaningless in representing the duration of exposure that is likely necessary to produce any substantial health symptoms.

- (2) In effect, subjects were exposed to two sham conditions. If they had been exposed to infrasound that adequately mimicked infrasound from IWTs (preferably actual IWT infrasound), subjects in both the high- and low-expectancy groups would have had a physical stimulus (in the infrasound condition) that could have overridden, or at least moderated, their psychological reactions.
- (3) The design limited the study's external validity, the ability to generalize the results to other populations and situations. Most of the individuals who have reported AHEs from WTN, some of whom have abandoned their homes, are not people who were adequately warned of potential health effects prior to their exposures. In fact, most of them were likely told by the wind company to expect no harmful effects. Again, many individuals who report AHEs were advocates of wind energy prior to being exposed. Because the major premise underlying the study is that people complain of WTN based primarily on expectancies that align with prior information, the study is based on a false premise. Also, the recruitment of university students does not represent the type of subjects who are apt to complain about WTN. This population is probably the least vulnerable to the effects of WTN in that few, if any, were very young, very old, likely to have chronic health conditions, or disabled. Also, they are more likely to exhibit a response bias because they are less likely than prospective residents of a wind project to believe that they might be harmed by participating in an experiment. Furthermore, the extensive use of pretesting introduced reactive or interactive effects that could have affected post-test behaviors and ratings. Finally, the use of a laboratory setting and short exposure times, as opposed to a real-life setting in which wind turbine blades are turning at night and the subjects are inside a home, introduced situational effects that limit the ability to generalize the data. The authors admit this shortcoming in their statement:
 "... exposure to infrasound in a listening room purpose (sic) built for sound experiments may not be directly comparable to exposure to infrasound from a wind farm" (p. 4).

- (4) This was an experiment whose outcomes could have been predicted, given the conditions employed. Aside from the fact that the outcome had virtually nothing to do with the real-world conditions of exposure to infrasound from wind turbines, none of the factors that influence how expectations can affect perceptions through top-down, or cognitive- based, processing, as opposed to bottom-up, or stimulus-based, processing, were controlled or even

discussed. (Interested readers should refer to Williams^[176] for examples of the effects of top-down processing and for a discussion of how such experiments might be improved.)

In a second laboratory study by Crichton and colleagues,^[177] similar in design to the first, the authors investigated whether positive expectations can produce a reduction in symptoms and improvements in reported health. Sixty participants were randomized to either positive or negative expectations and subsequently exposed to audible wind turbine sound and infrasound. According to the authors,

“Participants were ... exposed to infrasound (9Hz, 50.4dB) and audible wind farm sound (43dB), which had been recorded 1 km from a wind farm, during two 7-minute listening sessions. Both groups were made aware they were listening to the sound of a wind farm, and were being exposed to sound containing both audible and sub audible components and that the sound was at the same level during both sessions” (p. 2).

Prior to exposure, negative-expectation participants watched a DVD incorporating TV footage about health effects said to be caused by infrasound produced by wind turbines. In contrast, positive-expectation participants viewed a DVD that:

“...framed wind turbine sound as containing infrasound, sub audible sound created by natural phenomena such as ocean waves and the wind, which had been reported to have positive effects and therapeutic benefits on health” (p. 2).

The authors described the results as indicating that during exposure to audible wind turbine sound and infrasound, symptoms and mood were strongly influenced by subject expectations. Negative-expectation participants experienced a significant increase in symptoms and a significant deterioration in mood, while positive-expectation participants reported a significant decrease in symptoms and a significant improvement in mood. The authors concluded that if expectations about infrasound are framed in more neutral or benign ways, then it is likely that reports of symptoms or negative effects could be nullified.

That second investigation by Crichton and colleagues has some of the same methodological weaknesses as the first, particularly with respect to the use of what was described as experimental infrasound. Again, recordings of WTN were used, and no description of the recording instrumentation was provided, leading us to assume that the instrumentation may have been incapable of accurately reproducing infrasound, and thus its true effects. All participants were informed of the purpose of the study, which was:

“...to investigate the effect of sound below the threshold of human hearing (infrasound) on the experience of physical sensations and mood” (p. 2).

Preferably, the purpose should have been divulged only after the data were gathered because the description of sounds as those that humans cannot hear would presumably have established a mind-set, or bias, in both groups that the sound would have little impact. That preconception could have confounded any reactions to the different DVD messages. Another criticism of the study is that wind companies frame their turbines in the best possible light, so positive expectations have already been established in the minds of most wind-project participants and non-participants. Despite neutral or positive framing that has sometimes included assurance that the turbine sounds would be no louder than that of a refrigerator (see, for example, Chen & Narins^[178]), the consequences of living near IWTs are catastrophic for some residents.

Tonin et al^[179] repeated the experimental work of Crichton and her colleagues by using specially modified headphones to produce infrasound, as opposed to the loudspeaker system used in the previous studies, and exposed participants to 23 min of infrasound, as opposed to the 10-min exposures in the Crichton studies. Similar results were reported, suggesting that the simulated infrasound had no statistically significant effect on the symptoms reported by volunteers, while the prior expectations the volunteers had about the effect of infrasound had a statistically significant influence on the symptoms reported, thereby supporting the nocebo effect hypothesis. Some of the same criticisms of the Crichton et al study^[174] levelled by Punch^[175] also apply to the Tonin et al study, as participants were not being stimulated by sufficient durations or peak levels of infrasound exposure to which residents living near IWTs are exposed, and participants were effectively exposed to two sham conditions, denying them any opportunity to experience realistic infrasonic stimuli that could have overridden or moderated their psychological reactions based on expectancy.

In a related study, Taylor et al^[180] assessed the effect of negatively oriented personality (NOP) traits (Neuroticism, Negative Affectivity and Frustration Intolerance) on the relationship between both actual and perceived noise on “medically unexplained non-specific symptoms (NSS)” (p. 338), presumably their euphemism for Pierpont’s Wind Turbine Syndrome.^[4] Households within 500 m of 8 0.6-kW micro turbine installations and within 1 km of 4 5-kW small wind turbines in two U.K. cities were surveyed, and 138 questionnaires were completed and returned for analysis. Turbine noise level for each household was also calculated. There was no evidence for an effect of calculated noise on NSS. A statistically significant relationship was found between perceived noise and NSS for individuals high in NOP traits.

That study is similar in concept to those performed by Crichton and colleagues,^[174, 177] with virtually the same conclusion—that the link between wind turbines and AHEs has a psychological origin. The study can be criticized on several grounds:

(1) Only smaller wind turbines were investigated; there is virtually no literature demonstrating that such turbines produce noise levels of any consequence to humans. The fact that no relationship was found between “calculated actual noise” from the turbines and participants’ attitudes toward wind turbines was thus predictable because the noise levels were either too low to affect attitudes differentially or were completely inaudible.

(2) The authors state:

“Actual noise turbine level for each household was also calculated” (p. 338).

Calculated levels (from noise maps) are not necessarily actual levels, so this procedure was, at a minimum, mischaracterized.

(3) It should not be surprising to find that individuals with negatively oriented personalities respond negatively to WTN, as they would likely respond negatively to almost any stimulus. However, the findings, as acknowledged by the authors, resulted from reports of participants’ retrospective perceptions of noise from turbines and symptoms at the same point in time, possibly resulting in common-method variance and retrospective bias. Also, although the authors reported a statistically significant relationship between NSS and negatively oriented personality, the reported variance explained by those relationships was quite low. That finding suggests that a meaningful (i.e., clinical) significance was not established, in which case one might reasonably question whether symptom reporting in the study was actually linked to negative personality type.

(4) Among other possible confounders, individual differences are likely to have complicated the authors’ analyses (see Williams^[176] for an explanation).

To conclude this section, we believe that while psychological expectations conceivably can influence perceptions of the effects of WTN on health status, no scientific studies have yet convincingly shown that psychological forces are the major driver of such perceptions. Based on the bulk of literature covered in this review, those drivers are the physical stimuli themselves and the internal physiological reactions they induce.

Statement 11: Only relatively few people, if any, are adversely impacted by wind turbine noise, and the majority have no complaints.

As indicated earlier, most of the studies that have documented specified percentages of the population adversely affected by WTN have been those focusing on annoyance, as opposed to health. While the exact percentage of people whose health is affected by WTN has not been accurately determined, countless reports worldwide suggest that the acoustic energy emitted by

IWTs is harmful to the health of substantial numbers of people. As already noted, Phipps et al^[75] found that 45% of households living as far away as 4 km from a wind project and 20% of households living up to 8 km away reported hearing turbine noise. Those figures take into account only the audible noise, of course, and not the inaudible infrasound, and they do not account for any documented adverse impacts.

Estimates of the percentage of people adversely affected by WTN should not be based solely on questionnaire surveys of populations known to be experiencing health problems, due to selection bias. Such surveys can be helpful in arriving at rough estimates of AHEs, however, but only if those surveys also report estimates of the total population from which the affected sample is drawn. The main value of surveys that include only affected individuals (e.g., Harry^[74]; Pierpont^[41]; The Acoustic Group^[25]) is that they strongly suggest that substantial numbers of people living near wind turbines suffer health symptoms. For example, Harry^[74] reported that 81% of her 42 survey respondents had health complaints, 76% had visited a doctor regarding those complaints, and 73% reported a reduced quality of life. In a somewhat more representative survey of residents living within 15 km of a wind turbine project—most of whom lived within 3 km—Phipps^[76] found that 42 of 614 households who responded to a questionnaire (6.8%) reported occasional sleep disturbance, another 21 (3.4%) reported frequent sleep disturbance, and an additional 5 (0.8%) reported sleep disturbance most of the time due to WTN. Eleven percent of households, therefore, reported suffering at least occasional sleep disruption due to the wind turbines. Fifteen percent of respondents to that survey reported that they had suffered at least occasional reductions in their quality of life since the turbines became operational.

Despite the lack of definitive scientific evidence, we cannot ignore the numerous accounts of such effects reported worldwide on the Internet, in legal proceedings, and in news accounts. Krogh et al^[96] have reviewed studies that document such incidents, many of which have involved the abandonment of homes. In a 2010 report commissioned by the Ontario Ministry of the Environment, the engineering firm of Howe Gastmeier Chapnik Limited,^[112] despite its general conclusion that Ontario IWTs do not pose a risk to human health, stated:

“The audible sound from wind turbines, at the levels experienced at typical receptor distances in Ontario, is nonetheless expected to result in a non-trivial percentage of persons being highly annoyed research has shown that annoyance associated with sound from wind turbines can be expected to contribute to stress related health impacts in some persons” (p. 39).

In conclusion, we should recall that Phillips^[169] advocates self-reporting of adverse events as a critical element in the study of the health effects of wind turbines. As stated earlier, he has noted

the importance of case-crossover experiments as useful and well-accepted sources of epidemiologic information. Numerous households around the world have been subjected to this type of quasi-experiment by the wind industry. It is unfortunate that an accurate count of these incidents has never been tallied formally and scientifically. Although that task must be left to future research, we should regard complaints of AHEs from individuals living near wind turbine installations seriously, when they occur, and the wind industry must act responsibly by siting its turbines at distances from residents that protect health and quality of life.

It is widely accepted that the industry has warned that tighter siting restrictions will destroy its prospects for growth. Such growth, however, should not continue in areas where there are probable and potential risks to human health. There are regions of the U.S. and other countries where turbines can operate safely, presumably without such risks. Some examples of those sites are illustrated in Figure 2.

Statement 12: There is no evidence in the literature to support a causative link between wind turbine noise and adverse health effects.

The above review has been aimed specifically at addressing this point, which is often cited as factual by wind industry advocates in the literature and in legal proceedings. Namely, there is an abundant literature, much of it peer-reviewed and authored by highly reputable researchers, indicating that audible and inaudible noise emitted by IWTs adversely impacts the health and well-being of substantial numbers of people who are regularly exposed to wind turbines. It is clear that the literature reviews and papers claiming no AHEs fail to include important studies, international standards, guidance from the WHO, and research conducted on wind turbine noise and other sources of infra- and low-frequency sound. Whether this is through oversight or calculation, only reports that cite scientifically credible references should be considered legitimate sources of information. Our review has shown that it is unacceptable simply to state that the literature contains little or no evidence of a causal link between WTN and AHEs. At a minimum, those effects have been shown to be regularly correlated to living in proximity to IWTs, and there is sufficient evidence that those effects are highly associated with objective measurements of audible noise and infrasound.

Although sleep disturbance and its associated impacts on health and quality of life appear to be the most salient consequences of IWT noise, varying health effects that are unrelated to sleep have also been widely and consistently reported by different investigators. While not everyone who is exposed to IWTs suffers AHEs, it is incumbent on governmental officials and the wind industry to take seriously the health implications of their decisions to locate wind turbines near

residential and other populations, especially vulnerable populations, that are or likely to be negatively affected.




Figure 2. Photographic images of sites illustrating onshore landscapes where industrial wind turbines expose humans to minimal health risks due to large setback distances. Note that homes are not seen in the photos. (Source: https://images.search.yahoo.com/search/images?p=wind+turbine+images+california&fr=tightropetb&imgurl=http%3A%2F%2Fwww.freefoto.com%2Fimages%2F39%2F01%2F39_01_1---Wind-Turbine-Generators--Palm-Springs--California_web.jpg#id=36&iurl=http%3A%2F%2Fmedia-cdn.tripadvisor.com%2Fmedia%2Fphoto-%2F01%2F70%2F19%2Fbb%2Ftehachepi-area-california.jpg&action=close).

Conclusion

We have discussed in this paper various elements of acoustics, sound perception, sound measurement, and psychological reactions, and the role these factors play in support of the view that a general-causative link exists between human health and ILFN emitted by IWTs. The available evidence warrants the following conclusions:

- (1) Large wind turbines generate infrasound, which is not normally experienced as sound by most human listeners. Some people, however, experience it in the form of pathological

symptoms such as headache, dizziness, nausea, or motion sickness, which appear to be caused by the excitation of resonances inside closed structures and the human body itself.

- (2) WTN has unique acoustic characteristics when compared to other environmental noises. These characteristics include low-amplitude, amplitude-modulated, intermittent occurrences of tones that mirror the peak energy of the blade-pass frequency and the first several harmonics. The coupling mechanisms in the inner ear prevent internally generated sound, but not externally generated sound, from being perceived, which means that perception of wind turbine infrasound is far more disturbing than infrasound generated within the human body.
- (3) There is voluminous evidence, ranging from anecdotal accounts from around the world to peer-reviewed scientific research, that audible and inaudible low-frequency noise and infrasound from IWTs lead to complaints ranging from annoyance to AHEs in a substantial percentage of the population. Although sleep disturbance is the most common problem cited, a variety of other health problems has been reported by numerous reputable sources. Recent research is largely consistent with Pierpont's original description of Wind Turbine Syndrome. Research on humans and lower animals has shown that it is biologically plausible that inner ear mechanisms, in conjunction with the brain, can process acoustic energy in ways that result in pathological perceptions that are not interpreted as sound. Both balance and hearing mechanisms appear to be involved in evoking these perceptions. The findings that infrasonic stimuli can amplitude modulate higher frequencies in the audible region, and that infrasound may be more perceptible when higher frequencies are absent, are especially compelling in suggesting that what we can't hear can hurt us.
- (4) To prevent AHEs, scientists have recommended that distances separating turbines and residences be 0.5-2.5 mi., and 1.25 mi. (2 km) or more has been commonly recommended. Clearly, the short siting distances used by the industry for physical safety do not protect against AHEs. Alternatively, researchers have recommended sound levels typically ranging from 30-40 dBA for safeguarding health, which is consistent with the recommendation of nighttime noise levels by the WHO.
- (5) Annoyance is a health issue for many people living near IWTs, which is consistent with both the WHO's definition of health and contemporary models of the relationships among annoyance, stress, and health.
- (6) The scientific evidence regarding factors other than amplitude-modulated ILFN as an explanation for most of the health complaints near IWTs, including electromagnetic fields (dirty electricity), is weak; the preponderance of research suggests that ILFN is the most viable explanation for such complaints.

- (7) The A-weighted decibel scale, which effectively excludes infrasound and substantial amounts of low-frequency noise, is inadequate to predict the level of outdoor or indoor infrasound, to reveal correlations to infrasound, or to show a definitive relationship with AHEs. Achievement of these goals requires the development of new measurement methods.
- (8) Even though Wind Turbine Syndrome is not currently included in the ICD coding system, that system includes most of the acknowledged symptoms of the syndrome. Medical professionals, therefore, have the necessary tools to evaluate and treat it, and that process has already begun on a limited scale.
- (9) While some epidemiologically solid research has been done in the area of IWTs and AHEs, evidence from other sources cannot be ignored. Hill noted the nature of such sources in 1965, and Phillips, in 2011, described the importance of other kinds of evidence, including adverse event reports, in establishing a causative relationship. One of the strongest types of evidence is the case-crossover experimental design, which the wind industry has unwittingly imposed for years on multiple families, many of whom have abandoned their homes to escape IWT noise exposure.
- (10) While psychological expectations and the power of suggestion conceivably can influence perceptions of the effects of WTN on health status, no scientifically valid studies have yet convincingly shown that psychological forces are the major driver of such perceptions.
- (11) Accurate estimates of the percentage of people who are affected by IWTs exist only for annoyance, not AHEs. Multiple reports, however, emphasize the relationships that exist between annoyance, stress, health, and quality of life, and indicate that a non-trivial percentage of people who live near IWTs experience AHEs. Those reports are consistent with thousands of reports worldwide. Although it seems reasonable to conclude that noise from IWTs does not cause AHEs in the majority of exposed populations, and that accurate estimates of AHEs are yet to be established, it is also clear that considerable numbers of people are affected and that they deserve to be heard and protected from adverse health impacts.
- (12) The available literature, which includes research reported by scientists and other reputable professionals in peer-reviewed journals, government documents, print and web-based media, and in scientific and professional papers presented at society meetings, is sufficient to establish a general causal link between a variety of commonly observed AHEs and noise emitted by IWTs.

Based on all the evidence presented, our fundamental view is that the controversy surrounding AHEs should not be polarized into two groups consisting of either *pro-wind* or *anti-wind*

factions, but rather one in which there is room for a third, *pro-health*, perspective. Essentially, the pro-wind view is that IWTs should be installed wherever feasible, that definitive scientific research is lacking to indicate that turbines cause AHEs, and that if you can't hear it, you can't feel it. The anti-wind view is that IWTs should not be installed anywhere because wind is not an economically viable source of renewable energy, that all government subsidies and development efforts should end, and that what we can't hear can hurt us. A pro-health view is that there is enough anecdotal and scientific evidence to indicate that ILFN from IWTs causes annoyance, sleep disturbance, stress, and a variety of other AHEs to warrant siting the turbines at distances sufficient to avoid such harmful effects, which, without proper siting, occur in a substantial percentage of the population. That view holds that what we can't hear can hurt some of us, and that the precautionary principle must be followed in siting IWTs if such health risks are to be avoided. Industrial-scale wind turbines should not be located near people's homes, educational and recreational facilities, and workplaces. It is our belief that the bulk of the available evidence justifies a pro-health perspective. It is unacceptable to consider people living near wind turbines as collateral damage while this debate continues.

Further scientific investigations of the dose-response relationship between IWT noise and specific health effects in exposed individuals are sorely needed. However, people should be protected by conservative siting guidelines that recognize the concerns raised in this review. Hopefully, such research can and will be planned and executed by independent researchers with the full cooperation of the wind industry. The major objective of such research should be to reveal directions for the industry in balancing the energy needs of society with the need to protect public health.

Statement of conflict of interest: The authors declare no conflicts of interest. Mr. James is on the Board of Directors for the Society for Wind Vigilance, an international federation of physicians, acousticians, engineers, and other professionals who share scientific research on the topic of health and wind turbines.

Address for correspondence:

Jerry L. Punch

Department of Communicative Sciences and Disorders

1026 Red Cedar Road

Michigan State University, East Lansing, MI 48824, USA

E-mail: jpunch@msu.edu

References

- ¹ Caithness Windfarm Information Forum. Summary of wind turbine accident data to 30 June 2016. Available from: <http://www.caithnesswindfarms.co.uk/AccidentStatistics.htm>. [Last accessed on 2016 July 5].
- ² Hedges C, Sacco, J. *Days of Destruction, Days of Revolt*. New York: Nation Books; 2012.
- ³ Krogh C, Horner B, Morris J, May M, Papadopoulos G, Watts AC. Trading off human health: wind turbine noise and government policy. Presentation at 5th International Meeting on Wind Turbine Noise, August 2013. Available from: <http://waubrafoundation.org.au/wp-content/uploads/2014/02/Wind-Turbine-Noise-Conference-2013-Policy-paper.pdf>. [Last accessed on 2016 July 5].
- ⁴ Pierpont N. *Wind turbine syndrome: a report on a natural experiment*. Santa Fe (NM): K-Selected Books, 2009.
- ⁵ Horner B. Open Letter Audit: National Health and Medical Research Council Public Statement (2010) and Rapid Review (2010). Available from: http://docs.wind-watch.org/Horner_NHMRC-references-audit_July-31-2012.pdf. [Last accessed on 2016 July 5].
- ⁶ Office of Management and Budget: Final Information Quality Bulletin for Peer Review, December 16, 2004. Available from: http://www.google.com/url?sa=t&rct=j&q=&esrc=s&source=web&cd=1&ved=0CB4QFjAA&url=http%3A%2F%2Fwww.cio.noaa.gov%2Fservices_programs%2Fpdfs%2FOMB_Peer_Review_Bulletin_m05-03.pdf&ei=zxo8VI2PLevesASY64LQBA&usq=AFQjCNHRv2iLaSO_W6HyH05x9E90yQynDQ&sig2=jewV1g8YLE-Yrqz3IZ6rxg&bvm=bv.77161500,d.cGE&cad=rja. [Last accessed on 2016 July 20].
- ⁷ Achenbach J. Why do many reasonable people doubt science? *National Geographic*, 2015. Available from: <http://ngm.nationalgeographic.com/2015/03/science-doubters/achenbach-text>. [Last accessed on 2016 July 5].
- ⁸ Leventhall G. How the "mythology" of infrasound and low frequency noise related to wind turbines might have developed. Presentation at First International Meeting on Wind Turbine Noise: Perspectives for Control, October 2005. Available from: https://www.researchgate.net/publication/237542296_First_International_Meeting_on_Wind_Turbine_Noise_Perspectives_for_Control_Berlin_17th_and_18th_October_2005_How_the_mythology_of_infrasound_and_low_frequency_noise_related_to_wind_turbines_might_have_developed. [Last accessed on 2016 July 5].
- ⁹ Leventhall G. Infrasound from wind turbines—fact, fiction or deception. *Canadian Acoustics* 2006; 34:29-36.
- ¹⁰ James RR. Wind turbine infra and low-frequency sound: warning signs that were not heard. *Bulletin of Science, Technology & Society* 2012;32:108-127.

-
- ¹¹ Schwartz S. Linking noise and vibration to Sick Building Syndrome in office buildings. Air & Waste Management Association. March 2008:26-28. Available from: <http://pubs.awma.org/gsearch/em/2008/3/schwartz.pdf>. [Last accessed on 2016 July 5].
- ¹² Leventhall G. A review of published research on low frequency noise and its effects, May 2003. Available from: <http://docs.wind-watch.org/leventhall-defra-lowfreqnoise.pdf>. [Last accessed on 2016 July 20].
- ¹³ Broner N. The effects of low frequency noise on people—a review. *Journal of Sound and Vibration* 1978;58:483-500.
- ¹⁴ Leventhall G. Concerns about infrasound from wind turbines. *Acoustics Today* 2013;9:30-38.
- ¹⁵ Colby WD, Dobie R, Leventhall G, Lipscomb DM, McCunney RJ, Seilo MT, et al. Wind turbine sound and health effects: an expert panel review. Report prepared for Prepared for American Wind Energy Association and Canadian Wind Energy Association, December 2009. Available from: http://www.google.com/url?sa=t&rct=j&q=&esrc=s&source=web&cd=1&cad=rja&uact=8&ved=0CB4QFjAA&url=http%3A%2F%2Fcanwea.ca%2Fpdf%2Ftalkwind%2FWind_Turbine_Sound_and_Health_Effects.pdf&ei=Ja5TVIvDJ4WjyATUq4HQBA&usg=AFQjCNGYQ3-rkSZtsOVpuyhzeGsk2o4lQ&sig2=kZ_liEZ8jzUkFsT4bE7dbg&bvm=bv.78677474,d.aW. [Last accessed on 2016 July 5].
- ¹⁶ Møller H, Pedersen CS. Low-frequency noise from large wind turbines. *Journal of the Acoustical Society of America* 2011;129:3727-3744.
- ¹⁷ Evans T, Cooper J, Lenchine V. Infrasound levels near windfarms and in other environments. Environment Protection Authority, South Australia, January 2013. Available from: http://www.google.com/url?sa=t&rct=j&q=&esrc=s&source=web&cd=7&cad=rja&uact=8&ved=0CD8QFjAG&url=http%3A%2F%2Fwww.epa.sa.gov.au%2Fxstd_files%2FNoise%2FReport%2Finfrasound.pdf&ei=wIJeU_nAfOFyQG26YCoDQ&usg=AFQjCNG-V01kqE5hz7j0Jajwv8nFac0C4A&sig2=fj0z4hblVm_TOTTKxs-0nA&bvm=bv.65397613,d.aWc. [Last accessed on 2016 July 20].
- ¹⁸ Bolin K, Bluhm G, Eriksson G, Nilsson ME. Infrasound and low frequency noise from wind turbines: exposure and health effects. *Environmental Research Letters* 2011;6:1-12.
- ¹⁹ Kelley ND, Hemphill RR, McKenna ME. A methodology for assessment of wind turbine noise generation. *Journal of Solar Energy Engineering* 1982;104:112-120.
- ²⁰ Kelley ND, McKenna HE, Hemphill RR, Etter CL, Garrelts RL, Linn NC. Acoustic noise associated with the MOD-1 wind turbine: its source, impact, and control. Report prepared for the U. S. Department of Energy, Contract No. DE-AC02-83CH-10093, February 1985. Available from: <http://www.google.com/url?sa=t&rct=j&q=&esrc=s&source=web&cd=1&cad=rja&uact=8&ved=0CB4QFjAA&url=http%3A%2F%2Fwww.nrel.gov%2Fdocs%2Flegosti%2Fold%2F1166.pdf&ei=uK9TVIL3L82P7AajoIHQDQ&usg=AFQjCNGgDEPZV0hd1gkxw4hGcqWROWkufQ&si>

g2=abXK4ET8bDhYWbdG7UsKaA&bvm=bv.78677474,d.ZGU. [Last accessed on 2016 July 20].

- ²¹ Kelley ND. A proposed metric for assessing the potential of community annoyance from wind turbine low-frequency noise emissions. Presentation at Windpower'87 Conference and Exposition, November 1987. Available from: <http://www.nrel.gov/docs/legosti/old/3261.pdf>. [Last accessed on 2016 July 20].
- ²² Bray W, James R. Dynamic measurements of wind turbine acoustic signals, employing sound quality engineering methods considering the time and frequency sensitivities of human perception. Presentation at Noise-Con 2011 conference, July 2011. Available from: <http://waubrafoundation.org.au/wp-content/uploads/2013/07/Bray-James-11-07-25-Dynamic-measurement-of-wind-turbine-noise.pdf>. [Last accessed on 2016 July 20].
- ²³ Rand RW, Ambrose SE, Krogh CME. Occupational health and industrial wind turbines: a case study. *Bulletin of Science, Technology & Society* 2011;31:329-362.
- ²⁴ Walker B, Hessler GF, Hessler DM, Rand R, Schomer PD. A cooperative measurement survey and analysis of low frequency and infrasound at the Shirley Wind Farm in Brown County, Wisconsin. Report Number 122412-1, December 24, 2012. Available from: <https://docs.wind-watch.org/Shirley-LFN-infrasound.pdf>. [Last accessed on 2016 July 5].
- ²⁵ The Acoustic Group. The results of an acoustic program: Cape Bridgewater Wind Farm. Report prepared for Energy Pacific (Vic), Melbourne, Vic 3000, January 2015. Available from: <http://www.pacifichydro.com.au/english/our-communities/communities/cape-bridgewater-acoustic-study-report/?language=en>. [Last accessed on 2016 July 20].
- ²⁶ Swinbanks M. Direct experience of low-frequency noise and infrasound within a windfarm community. Paper prepared for presentation at 6th International Meeting on Wind Turbine Noise, April 2015. Available from: <https://docs.wind-watch.org/WTN2015-Swinbanks.pdf>. [Last accessed on 2016 July 5].
- ²⁷ Swinbanks M. Direct experience of low frequency noise and infrasound within a windfarm community. Presentation at 6th International Meeting on Wind Turbine Noise, April 2015. Available from: <http://docs.wind-watch.org/WTN2015-Swinbanks-poster.pdf>. [Last accessed on 2016, July 20].
- ²⁸ Artz K. Health threat from Wisconsin wind farm affirmed, October 29, 2014. Available from: <http://news.heartland.org/newspaper-article/2014/10/28/health-threat-wisconsin-wind-farm-affirmed>. [Last accessed on 2016 July 20].
- ²⁹ Abel D. State wants turbine shut over noise. *Boston Globe*, May 16, 2012. Available from: <https://www.bostonglobe.com/metro/2012/05/15/massachusetts-officials-recommend-falmouth-shut-down-turbines/mCPNKvUoq1IrdPCIRygmWN/story.html>. [Last accessed on 2016 September 10.]

-
- ³⁰ Anon, Kingston wind turbine shut down indefinitely; financial problems reported to the Town, June 19, 2016. Available from: http://www.windaction.org/posts/45258-kingston-wind-turbines-shut-down-indefinitely#.V8x_tDXIS-E. [Last accessed on 2016 September 4.]
- ³¹ Castelo Branco NAA, Alves-Pereira M, Pimenta AM, Ferreira JR. Low frequency noise-induced pathology: contributions provided by the Portuguese wind turbine case. Presentation at EuroNoise 2015 conference. Available from: <http://docs.wind-watch.org/Euronoise2015-000602.pdf>. [Last accessed on 2016 September 11.]
- ³² Leloudas G, Zhu WJ, Sørensen JN, Shen WZ, Hjort S. Prediction and reduction of noise from a 2.3 MW wind turbine. *Journal of Physics: Conference Series* 75, 2007. Available from: <http://iopscience.iop.org/article/10.1088/1742-6596/75/1/012083/pdf>. [Last accessed on 2016 July 20].
- ³³ Rogers AL. Wind turbine noise, infrasound and noise perception. January 18, 2006. Available from: http://www.google.com/url?sa=t&source=web&cd=1&ved=0CBoQFjAA&url=http%3A%2F%2Fwww.windpoweringamerica.gov%2Fpdfs%2Fworkshops%2Fmwwg_turbine_noise.pdf&rct=j&q=frequency%20spectrum%20wind%20turbine%20noise&ei=u_fLTdu9OunRiALiotmUCA&usg=AFQjCNFWWT5fFWS6aO3XYIpvqkevckXbmw&sig2=1C0uNL4d19vHkmbvE4V8Lg&ad=rja. [Last accessed on 2016 July 20].
- ³⁴ Powell CA, Preisser JS. NASA's subsonic jet transport noise reduction research. Available from: <http://hdl.handle.net/2060/20040086700>. [Last accessed on 2016 July 8].
- ³⁵ Hubbard HH, Maglieri DJ. A brief review of air transport noise. *Journal of Sound and Vibration* 1975;43:159-172.
- ³⁶ Cermak GW, Cornillon PC. Multidimensional analyses about judgments about traffic noise. *Journal of the Acoustical Society of America* 1976;59:1412-1420.
- ³⁷ Leventhall HG. Low frequency noise and annoyance. *Noise & Health* 2004;6:59-72.
- ³⁸ World Health Organization. Night Noise Guidelines for Europe. World Health Organization, 2009. Available from: http://www.euro.who.int/__data/assets/pdf_file/0017/43316/E92845.pdf. [Last accessed on 2016 July 20].
- ³⁹ Cummings, J. Looking for wind industry leadership in reducing noise impacts. February 23, 2011. Available from: <http://www.renewableenergyworld.com/rea/news/article/2011/02/looking-for-wind-industry-leadership-in-reducing-noise-impacts>. [Last accessed on 2016 July 20].
- ⁴⁰ Jung SS, Cheung W-S, Cheong C, Shin S-H. Experimental identification of the acoustic emission characteristics of large wind turbines, with emphasis on infrasound and low frequency noise. *Journal of the Korean Physical Society* 2008;53:1897-1905.
- ⁴¹ Leventhall G. On the overlap region between wind turbine infrasound and infrasound from other sources and its relation to criteria. Presentation at 6th International Conference on Wind

Turbine Noise, April 2015. Available (for purchase) from:

<http://www.proceedings.com/26771.html>. [Last accessed on 2016 July 15.]

- ⁴² Harrison JP. Wind turbine noise. *Bulletin of Science, Technology & Society* 2011;31:256-261.
- ⁴³ Janssen SA, Vos H, Eisses AR, Pedersen E. Predicting annoyance by wind turbine noise. Presentation at 2010 Internoise conference, June 2010. Available from: http://docs.wind-watch.org/Janssen_Predicting-annoyance.pdf. [Last accessed on 2016 July 20].
- ⁴⁴ Pedersen E, Persson Waye KP. Perception and annoyance due to wind turbine noise—a dose-response relationship. *Journal of the Acoustical Society of America* 2004;116:3460-3470.
- ⁴⁵ Van Renterghem T, Bockstael A, De Weirt V, Botteldooren D. Annoyance, detection and recognition of wind turbine noise. *Science of the Total Environment* 2013;456-7:333-345.
- ⁴⁶ Thorne B. The problems with “noise numbers” for wind farm noise assessment. *Bulletin of Science, Technology & Society* 2011;31:262-290.
- ⁴⁷ Hubbard HH. Noise induced house vibrations and human perception. *Noise Control Engineering Journal* 1982;19:49-55.
- ⁴⁸ Hubbard HH, Shepherd KP. Wind turbine acoustics. NASA Technical Paper 3057. December 1990. Available from: <http://hdl.handle.net/2060/19910007366>. [Last accessed on 2016 July 8].
- ⁴⁹ Thorne B. Wind farm noise and human perception: a review. April 2013. Available from: http://www.google.com/url?sa=t&ret=j&q=&esrc=s&source=web&cd=2&cad=rja&uact=8&ved=0CC8QFjAB&url=http%3A%2F%2Fdocs.wind-watch.org%2FNMS-Wind-Farm-Noise-Human-Perception-April-2013.pdf&ei=vcprU_3KOZCFyQG-p4HYBA&usq=AFQjCNGJSSylvcUMNXbqjy7IML7kMd_H7w&sig2=Ls0JpH4uFoSdfxYnlhz6Vg&bvm=bv.66330100,d.aWc. [Last accessed on 2016 July 8].
- ⁵⁰ Shepherd D, Hanning C, Thorne B. Noise: windfarms. In: Jorgensen SE, editor. *Encyclopedia of Environmental Management*. New York: Taylor & Francis Online; 2012. pp. 1-17.
- ⁵¹ Schomer P. Can wind turbine sound that is below the threshold of hearing be heard? Presentation at ICA 2013 Conference, June 2013. Available from: http://www.ica2013montreal.org/Proceedings/mss/040063_1.pdf. [Last accessed on 2016 July 20].
- ⁵² Schomer PD, Erdreich J, Boyle J, Pamidighantam P. A proposed theory to explain some adverse physiological effects of the infrasonic emissions at some wind farm sites. Presentation at 5th International Conference on Wind Turbine Noise, August 2013. Available from: <http://docs.wind-watch.org/Schomer-et-al-physiologic-effects-infrasound-wind.pdf>. [Last accessed on 2016 July 20].
- ⁵³ Lee S, Lee S, Lee, S. Numerical modeling of wind turbine aerodynamic noise in the time domain. *Journal of the Acoustical Society of America* 2013;133:94-100.

-
- ⁵⁴ Lichtenhan JT, Salt AN. Amplitude modulation of audible sounds by non-audible sounds: understanding the effects of wind turbine noise. Presentation at 2013 ICA conference, June 2013. *Journal of the Acoustical Society of America* 2013;133:3419. Available from: <http://oto2.wustl.edu/cochlea/LichtenhanAMASA.pdf>. [Last accessed on 2016 July 20].
- ⁵⁵ Minnesota Department of Health. Public health impacts of wind turbines. May 22, 2009. Available from: <http://www.health.state.mn.us/divs/eh/hazardous/topics/windturbines.pdf>. [Last accessed on 2016 July 20].
- ⁵⁶ Salt AN. Does the infrasound from wind turbines affect the inner ear? Presentation at Association for Research in Otolaryngology conference, February 2011. Available from: https://c.ymcdn.com/sites/aro.site-ym.com/resource/resmgr/Abstract_Archives/2011_Abstract_Book.pdf. Pp. 137-138. [Last accessed on 2016 July 20].
- ⁵⁷ Stigwood M, Large S, Stigwood D. Audible amplitude modulation: results of field measurements and investigations compared to psycho-acoustical assessment and theoretical research. Presentation in Denver, Colorado, August 2013. Available from: http://www.masenv.co.uk/uploads/WTN13_Stigwood_Presentation.pdf. [Last accessed on 2016 July 20].
- ⁵⁸ Taylor S. Report on the health impacts of wind farms: Shetland 2013 Summary. July 15, 2013. Available from: http://www.shb.scot.nhs.uk/board/publichealth/documents/Summary_Report_on_Health_Impacts_Wind_Farms.pdf. [Last accessed on 2016 July 20].
- ⁵⁹ Bray WR. Measurement and sound quality issues concerning low-frequency noise. Presentation at Noise-Con 2007 conference (Abstract). Available from: http://www.head-acoustics.de/downloads/messen/Noise-Con_2007_Measurement_and_SQ_WBray.pdf. [Last accessed on 2016 July 20].
- ⁶⁰ van den Berg GP. Effects on the wind profile at night on wind turbine sound. *Journal of Sound and Vibration* 2004;277:955-970.
- ⁶¹ Ambrose SE, Rand RW, Krogh ME. Wind turbine acoustic investigation: infrasound and low-frequency noise – a case study. *Bulletin of Science, Technology & Society* 2012;32:128-141.
- ⁶² Vasudevan RN, Gordon CG. Experimental study of annoyance due to low frequency environmental noise. *Applied Acoustics* 1977;10:57-69.
- ⁶³ Frey BJ, Hadden PJ. Wind turbines and proximity to homes: the impact of wind turbine noise on health. January 2012. Available from: http://www.google.com/url?sa=t&rct=j&q=&esrc=s&source=web&cd=2&cad=rja&uact=8&ved=0CC8QFjAB&url=http%3A%2F%2Fdocs.wind-watch.org%2FFrey_Hadden_WT_noise_health_01Jan2012.pdf&ei=op9eU4aJCsJK2wXeyIDQCA&usq=AFQjCNHGxv6iq3RAc_CXS0KtVqKxdedzNw&sig2=hMEop9T4B7eFyX97B_36Fw&bvm=bv.65397613,d.b2U. [Last accessed on 2016 July 20].

-
- ⁶⁴ Farboud A, Crunkhorn R, Trinidade A. Wind turbine syndrome: fact or fiction? *Journal of Laryngology & Otology* 2013;127:222-226.
- ⁶⁵ Pedersen E, van den Berg F. Why is wind turbine noise poorly masked by road traffic noise? Internoise 2010 conference, June 2010. Available from: <http://www.google.com/url?sa=t&rct=j&q=&esrc=s&source=web&cd=2&cad=rja&uact=8&ved=0CCQqFjAB&url=http%3A%2F%2Fwww.diva-portal.org%2Fsmash%2Fget%2Fdiva2%3A332207%2FFULLTEXT01.pdf&ei=sLJTVJeaNNCWyATQkIGoBA&usg=AFQjCNEyiBjgIjPcsq3ShXZAMUPdSP4rzQ&sig2=n3ZJBFNLUzT4dMjib-gghw&bvm=bv.78677474,d.aWw>. [Last accessed on 2016 July 20].
- ⁶⁶ Schomer PD. Comments on recently published article, "Concerns about infrasound from wind turbines." *Acoustics Today* 2013;9:7-9.
- ⁶⁷ Moorhouse A, Waddington D, Adams M. Proposed criteria for the assessment of low frequency noise disturbance. Report (NANR45) prepared for DEFRA, February 2005. Available from: <http://webarchive.nationalarchives.gov.uk/20130402151656/http://archive.defra.gov.uk/environment/quality/noise/research/lowfrequency/documents/nanr45-criteria.pdf>. [Last accessed on 2016 July 20].
- ⁶⁸ Swinbanks MA. Numerical simulation of infrasound perception, with reference to prior reported laboratory effects. Presentation at 2012 Internoise conference, August 2012. Available from: <http://docs.wind-watch.org/Internoise2012-Swinbanks.pdf>. [Last accessed on 2016 July 20].
- ⁶⁹ James RR. Untitled. ND. Available from: <http://www.windturbinesyndrome.com/wp-content/uploads/2014/07/How-Blade-pass-causes-infrasound-pulsations.pdf>. [Last accessed on 2016 July 8].
- ⁷⁰ Salt AN. Letter to Chairman of Association of Australian Acoustical Consultants. September 18, 2013. Available from: <https://s3.amazonaws.com/windaction/attachments/1998/Warpenius.pdf>. [Last accessed on 2016 September 5].
- ⁷¹ Berglund B, Lindvall T, Schwela DH (eds.), Guidelines for Community Noise. World Health Organization, April 1999. Available from: https://www.google.com/url?sa=t&rct=j&q=&esrc=s&source=web&cd=1&ved=0CB8QFjAAahUKEwjsqc_CnJPHAhXEi5IKHeJxANk&url=http%3A%2F%2Fwhqlibdoc.who.int%2Fhq%2F1999%2Fa68672.pdf&ei=RK3Cvez3A8SXygTi44HIDQ&usg=AFQjCNHq0SRjmXAXPKGPvQC88NtlGaJJBQ&bvm=bv.99261572,d.aWw&cad=rja. [Last accessed on 2016 July 20].
- ⁷² Ising H, Kruppa B. Health effects caused by noise: evidence in the literature from the past 25 years. *Noise & Health* 2004;6:5-13.
- ⁷³ Sørensen M, Andersen ZJ, Nordsborg RB, Jensen SS, Lillelund KG, Beelen R., et al. Road traffic noise and incident myocardial infarction: a prospective cohort study. *PLoS ONE* 2012;7(6):1-7.

-
- ⁷⁴ Harry A. Wind turbines, noise and health. February 2007. Available from: http://docs.wind-watch.org/wtnoise_health_2007_a_harry.pdf. [Last accessed on 2016 July 20].
- ⁷⁵ Phipps R, Amati M, McCoard S, Fisher R. Visual and noise effects reported by residents living close to Manawatu Wind Farms: preliminary survey results. ND. Available from: <http://docs.wind-watch.org/hiphps-visualnoiseeffects.pdf>. [Last accessed on 2016 July 8].
- ⁷⁶ Phipps R. Evidence of Dr. Robyn Phipps, in the matter of Moturimu Wind Farm application, Palmerston North. March 2007. Available from: <http://docs.wind-watch.org/hiphps-moturimutestimony.pdf>. [Last accessed on 2016 July 20].
- ⁷⁷ Horner B, James RR, Jeffery RD, McMurtry RY, Nissenbaum MA, White DL. Wind energy industry acknowledgement of adverse health effects: part 1 conclusion and executive summary. January 2010. Available from: http://co.wasco.or.us/planning/Energy/BOCC/New_Comments/after_2-15/swaim1_SWV_Critique_CANAWEA.pdf. [Last accessed on 2016 July 20].
- ⁷⁸ Horner B. Open letter to Prime Minister of Canada and others to request formally that representatives of CanWEA, the Government of Canada, Health Canada, and the Government of Ontario provide Canadians immediate and full disclosure of the health effects “conclusively demonstrated” from exposure to wind turbine noise. March 21, 2013. Available from: <https://mothersagainstturbines.files.wordpress.com/2013/09/request-stop-health-canada-experiment-on-canadians-march-21-2013.pdf>. [Last accessed on 2016 July 20].
- ⁷⁹ Phillips CV. An analysis of the epidemiology and related evidence on the health effects of wind turbines on local residents. Public Service Commission of Wisconsin, Docket no. 1-AC-231. July 3, 2010. Available from: <http://docs.wind-watch.org/Phillips-wind-turbines-and-health.pdf>. [Last accessed on 2016 July 8].
- ⁸⁰ Hanning C. Wind turbine noise, sleep and health. July 2010. Available from: http://www.acousticecology.org/wind/winddocs/health/Hanning%202010_Wind%20turbine%20noise%20sleep%20and%20health%20November%202010.pdf. [Last accessed on 2016 July 20].
- ⁸¹ Nissenbaum MA. Industrial wind turbines, human variability, and adverse health effects. NOCOEM Reporter, *New England College of Occupational and Environmental Medicine*. Fall 2013;2(38). Available from: http://www.necoem.org/documents/V2_38e.pdf. [Last accessed on 2016 July 20].
- ⁸² Ellenbogen JM, Grace S, Heiger-Bernays WJ, Manwell JF, Mills DA, Sullivan KA, et al. Wind Turbine Health Impact Study. Report prepared for Massachusetts Department of Environmental Protection. January 2012. Available from: http://www.google.com/url?sa=t&rct=j&q=&esrc=s&source=web&cd=1&cad=rja&uact=8&ved=0CCMQFjAA&url=http%3A%2F%2Fwww.mass.gov%2Feea%2Fdocs%2Fdep%2Fenergy%2Fwind%2Fturbine-impact-study.pdf&ei=wSw0VMjCDoz_yQTRpILoAQ&usq=AFQjCNEdk-4087qFICDXRnPB2mXjV5MU1Q&bvm=bv.76943099,d.aWw. [Last accessed on 2016 July 20].

-
- ⁸³ Kamperman GW, James RR. The “how to” guide to criteria for siting wind turbines to prevent health risks from sound. October 28, 2008. Available from: <http://www.windturbinesyndrome.com/wp-content/uploads/2008/11/kamperman-james-10-28-08.pdf>. [Last accessed on 2016 July 20].
- ⁸⁴ Hanning C. Comments on wind turbine health impact study: report of independent expert panel. ND. Available from: <http://docs.wind-watch.org/MassDEP-wind-health-I-Hanning.pdf>. [Last accessed on 2016 July 26].
- ⁸⁵ Hartman RS. Statement of Dr. Raymond S. Hartman presented to the zoning board of Charlestown, Rhode Island, Critique of the Massachusetts Department of Environmental Planning (DEP) “Wind Turbine Health Impact Study, Report of Independent Expert Panel.” January 2012. Available from: <https://www.wind-watch.org/docviewer.php?doc=Hartman-Mass-DEP-study-RI-130605.pdf>. [Last accessed on 2016 July 20].
- ⁸⁶ Schomer P, Pamidighantam P. A critical analysis of Wind Turbine Health Impact Study: report of independent expert panel. Presentation at 166th meeting of Acoustical Society of America, December 2013. Available from: <http://scitation.aip.org/deliver/fulltext/asa/journal/poma/20/1/1.4870639.pdf?itemId=/content/asa/journal/poma/20/1/10.1121/1.4870639&mimeType=pdf&containerItemid=content/asa/journal/poma>. [Last accessed on 2016 July 20].
- ⁸⁷ Shahan, Z. Wind Turbine Syndrome... not! Available from: <http://cleantechnica.com/2012/12/27/wind-turbine-syndrome-not/>. December 27, 2012. [Last accessed on 2016 July 20].
- ⁸⁸ Hanning CD, Evans A. Wind turbine noise. *British Medical Journal* 2012;344:1-2.
- ⁸⁹ Bakker RH, Pedersen E, van den Berg GP, Stewart RE, Lok W, Bouma J. Impact of wind turbine sound on annoyance, self-reported sleep disturbance and psychological distress. *Science of the Total Environment* 2012;425:42–51.
- ⁹⁰ Frey BJ, Hadden PJ. Noise radiation from wind turbines installed near homes: effects on health. February 2007. Available from: <http://wauubrafoundation.org.au/wp-content/uploads/2014/06/Frey-Hadden-Noise-Radiation-fro-Wind-Turbines-Installed-Near-Homes.pdf>. [Last accessed on 2016 July 20].
- ⁹¹ Havas M, Colling D. Wind turbines make waves: why some residents near wind turbines become ill. *Bulletin of Science, Technology & Society* 2011;31:414–426.
- ⁹² Jeffery RD, Krogh C, Horner B. Adverse health effects of industrial wind turbines. *Canadian Family Physician* 2013;59:473-475.
- ⁹³ Jeffery RD, Krogh CME, Horner B. Industrial wind turbines and adverse health effects. *Canadian Journal of Rural Medicine* 2014;19:21-26.
- ⁹⁴ Krogh C. Risk of harm to children and industrial wind turbines: health and social-economic impacts in Canada, Health Canada Wind Turbine Noise and Health Study. December 27, 2012.

Available from:

http://www.google.com/url?sa=t&rct=j&q=&esrc=s&source=web&cd=1&cad=rja&uact=8&ved=0CB0QFjAA&url=http%3A%2F%2Fwepat.files.wordpress.com%2F2013%2F05%2Fhealth-canada_risks-to-children-december-27-2012-final.pdf&ei=Lp2tU862N4W2yAT6kYDwDQ&usg=AFQjCNGeq2a21hWue4rFj3f4817L8nvQ5g&sig2=fTWiBMrlj6KwvfzeNnVtQQ&bvm=bv.69837884,d.aWw. [Last accessed on 2016 July 20].

- ⁹⁵ Krogh CME, Gillis L, Kouwen N, Aramini J. WindVOiCe, a self-reporting survey: adverse health effects, industrial wind turbines, and the need for vigilance monitoring. *Bulletin of Science, Technology & Society* 2011;31:334-335.
- ⁹⁶ Krogh CME, Jeffery RD, Aramini J, Horner B. Wind turbines can harm humans: a case study. Presentation at 2012 Internoise conference, August 2012. Available from: [http://docs.wind-watch.org/Krogh et al. - Wind Turbines - Risk of Harm.pdf](http://docs.wind-watch.org/Krogh%20et%20al.%20-%20Wind%20Turbines%20-%20Risk%20of%20Harm.pdf). [Last accessed on 2016 July 20].
- ⁹⁷ Nissenbaum MA, Aramini JJ, Hanning CD. Effects of industrial wind turbine noise on sleep and health. *Noise & Health*, 2012;14:237-243.
- ⁹⁸ Pedersen, E. Effects of wind turbine noise on humans. Presentation at Third International Meeting on Wind Turbine Noise, June 2009. Available from: <http://www.google.com/url?sa=t&rct=j&q=&esrc=s&source=web&cd=1&cad=rja&uact=8&ved=0CB4QFjAA&url=http%3A%2F%2Fwww.diva-portal.org%2Fsmash%2Fget%2Fdiva2%3A240110%2FFULLTEXT01.pdf&ei=crJTVOWIFpP3yQTomYCIbw&usg=AFQjCNGWc9olvAaMXMa-If7gi3yK9DAHUA&sig2=UBo9Smw5E7w3xJFYx01hbg&bvm=bv.78677474,d.aWw>. [Last accessed on 2016 July 20].
- ⁹⁹ Pedersen E. Health aspects associated with wind turbine noise—results from three field studies. *Noise Control Engineering Journal* 2011;59:47-53.
- ¹⁰⁰ Pierpont N. Wind Turbine Syndrome and the brain. Keynote address at First International Symposium on the Global Wind Industry and Adverse Health Effects: Loss of Social Justice?, November 15, 2010. Available from: <http://www.windturbinesyndrome.com/img/WTSbrain-color.pdf>. [Last accessed on 2016 July 20].
- ¹⁰¹ Punch J, James R, Pabst D. Wind turbine noise: what audiologists should know. *Audiology Today* 2010:20-31.
- ¹⁰² Roberts JD, Roberts MA. Wind turbines: is there a human health risk? *Journal of Environmental Health* 2013;75: 8-13, 16-17.
- ¹⁰³ Shepherd D, Billington R. Mitigating the acoustic impacts of modern technologies: acoustic, health, and psychosocial factors informing wind farm placement. *Bulletin of Science, Technology & Society* 2011;31:389-398.
- ¹⁰⁴ Shepherd D, McBride D, Welch D, Dirks KN, Hill EM. Evaluating the impact of wind turbine noise on health-related quality of life. *Noise & Health* 2011;13:333-339.

-
- ¹⁰⁵ Timmerman NS. Wind turbine noise. *Acoustics Today* 2013;9:22-29.
- ¹⁰⁶ Abbasi M, Monnazzam MR, Zakerian SA, Yousefzadeh A. Effect of wind turbine noise on workers' sleep disorder: a case study of Manjil Wind Farm in Northern Iran. *Fluctuation and Noise Letters* 2015;14(2):1-15.
- ¹⁰⁷ Abbasi M, Monazzam MR, Akbarzadeh A, Zakerian SA, Ebrahimi MH, Impact of wind turbine sound on general health, sleep disturbance and annoyance of workers: a pilot-study in Manjil wind farm, Iran. *Journal of Environmental Health Science & Engineering* 2015,13:71-79.
- ¹⁰⁸ Persson Waye KP, Clow A, Edwards S, Hucklebridge F, Rylander R. Effects of low frequency noise on the cortisol response to awakening and subjective sleep quality. *Life Sciences* 2003;72:863-875.
- ¹⁰⁹ Bronzaft AL. The noise from wind turbines: potential adverse impacts on children's wellbeing. *Bulletin of Science, Technology & Society* 2011;31:291-295.
- ¹¹⁰ Fiumicelli D. Wind farm noise dose response. *Acoustics Bulletin* November/December 2011:26-35.
- ¹¹¹ Physicians for Human Rights. Leave no marks: enhanced interrogation techniques and the risk of criminality. August 2007. Available from: https://s3.amazonaws.com/PHR_Reports/leave-no-marks.pdf. [Last accessed on 2016 July 20].
- ¹¹² Kasprzak C. The influence of infrasound noise from wind turbines on EEG signal patterns in humans. *Acoustic and Biomedical Engineering* 2014;125:A-20-A23.
- ¹¹³ Paller C, Bigelow P, Majowicz S, Law J, Christidis T. Wind turbine noise, sleep quality, and symptoms of inner ear problems. Presentation at Symposia of the Ontario Research Chairs in Public Policy. ND. Available from: http://docs.wind-watch.org/Paller_Poster_15Oct2013.pdf. [Last accessed on 2016 July 20].
- ¹¹⁴ Howe Gastmeier Chapnik Limited. Low frequency noise and infrasound associated with wind turbine generator systems: a literature review. December 10, 2010. Ontario Ministry of the Environment RFP No. OSS-078696. Available from: <https://dr6j45jk9xcmk.cloudfront.net/documents/1160/88-noise-and-wind-turbine-generator-systems-en.pdf>. [Last accessed on 2016 July 20].
- ¹¹⁵ Pawlaczyk-Luszczynska M, Dudarewicz A, Waszkowska M, Szymczak W, Śliwińska-Kowalska M. The impact of low frequency noise on human mental performance. *International Journal of Occupational Medicine and Health* 2005;18(2):185-198.
- ¹¹⁶ Rand RW, Ambrose SE, Krogh ME. Occupational health and industrial wind turbines: a case study. *Bulletin of Science, Technology & Society* 2011;31:359-362.
- ¹¹⁷ Palmer W. Wind turbine sound prediction – the consequence of getting it wrong. Presentation at ICA 2013 meeting of Acoustical Society of America, June 2013. Available from: <http://www.google.com/url?sa=t&rct=j&q=&esrc=s&source=web&cd=3&ved=0CDUQFjAC&u>

-
- rl=http%3A%2F%2Fs3.amazonaws.com%2Fwindaction%2Fattachments%2F1791%2FPMA040066_Palmer.pdf&ei=E12RUyLFIS2rQHp-oDYAQ&usg=AFQjCNGQ45VRuryLV19x2-T81J8z3qdukQ&bvm=bv.56988011,d.aWM. [Last accessed on 2016 July 20].
- ¹¹⁸ Castelo Branco NAA, Alves-Pereira M. Vibroacoustic disease. *Noise & Health* 2004;6(23):3–20.
- ¹¹⁹ Castelo Branco NA. The clinical stages of vibroacoustic disease. *Aviation, Space, and Environmental Medicine* 1999;70(3, Pt 2):A32-39.
- ¹²⁰ Kennedy RS, Allgood GO, Van Hoy BW, Lilienthal MG. Motion sickness symptoms and postural changes following flights in motion-based flight trainers. *Journal of Low Frequency Noise and Vibration* 1987;6(4):147-153.
- ¹²¹ von Gierke HE, Parker DE. Differences in otolith and abdominal viscera graviceptor dynamics: implications for motion sickness and perceived body position. *Aviation, Space, and Environmental Medicine* 1994;65:747-751.
- ¹²² Berger RG, Ashtiani P, Ollson CA, Whitfield Aslund M, McCallum LC, Leventhall G, et al. Health-based audible noise guidelines account for infrasound and low-frequency noise produced by wind turbines. *Frontiers in Public Health* 2015;3:1-14.
- ¹²³ Carey J, Amin N. Evolutionary changes in the cochlea and labyrinth: solving the problem of sound transmission to the balance organs of the inner ear. *The Anatomical Record Part A*, 2006;288A:482-90.
- ¹²⁴ Persinger MA. Infrasound, human health, and adaptation: an integrative overview of recondite hazards in a complex environment. *Natural Hazards* 2013;70:501-525.
- ¹²⁵ Salt AN. Infrasound: your ears “hear” it but they don't tell your brain. Presentation at Symposium on Adverse Health Effects of Industrial Wind Turbines. Available from: http://www.google.com/url?sa=t&rct=j&q=&esrc=s&source=web&cd=1&cad=rja&uact=8&ved=0CCcQFjAA&url=http%3A%2F%2Ffoto2.wustl.edu%2Fcochlea%2FWTPicton_salt_final.pdf&ei=H1hqU7XUA4iyyATMpoGoBQ&usg=AFQjCNHzz_0mBFhOP1GKgv4b0ncCC_iW7g&sig2=UxKESjK4Yr-lulkP7o2xmQ&bvm=bv.66111022,d.aWc. [Last accessed on 2016 July 20].
- ¹²⁶ Salt AA, Hullar TE. Responses of the ear to low-frequency sounds, infrasound and wind turbines. *Hearing Research* 2010;268:12-21.
- ¹²⁷ Salt AN, Lichtenhan JT. How does wind turbine noise affect people? *Acoustics Today* 2014;10:20-28.
- ¹²⁸ Salt AN, Kaltenbach JA. Infrasound from wind turbines could affect humans. *Bulletin of Science, Technology & Society* 2011;31:296-302.
- ¹²⁹ Salt AN, Lichtenhan JT. Responses of the inner ear to infrasound. Presentation at Fourth International Meeting on Wind Turbine Noise, April 2011. Available from: <http://oto2.wustl.edu/cochlea/saltlichtenhan.pdf>. [Last accessed on 2016 July 20].

-
- ¹³⁰ Salt AN, Lichtenhan JT. Perception-based protection from low-frequency sounds may not be enough. Presentation at 2012 Internoise conference, August 2012. Available from: <http://oto2.wustl.edu/cochlea/saltlichtenhaninternoise2012.pdf>. [Last accessed on 2016 July 20].
- ¹³¹ Salt AN, Lichtenhan JT, Gill RM, Hartsock JJ. Large endolymphatic potentials from low-frequency and infrasonic tones in the guinea pig. *Journal of the Acoustical Society of America* 2013;133:1561-1571.
- ¹³² Salt AN. Wind Turbines can be hazardous to human health. Available from: http://www.google.com/url?sa=t&ret=j&q=&esrc=s&source=web&cd=1&ved=0CCcQFjAA&url=http%3A%2F%2Foto2.wustl.edu%2Fcochlea%2Fwind.html&ei=PSl6U-fkMIedqAbWlYLIaw&usq=AFQjCNE7m2g3uKmdL4OgN4es_-gymFbe-g&sig2=a8SmsvCVRQ2Ib_TC4Idjfw&bvm=bv.66917471,d.b2k&cad=rja. [Last accessed on 2016 July 20].
- ¹³³ Oohashi T, Nishina E, Honda M, Yonekura Y, Fuwamoto Y, Kawai N., et al. Inaudible high-frequency sounds affect brain activity: hypersonic effect. *Journal of Neurophysiology* 2000; 83:3548-3558.
- ¹³⁴ Bauer M, Sander-Thömmes T, Ihlenfeld A, Kühn S, Kühler R, Koch C. Investigation of perception at infrasound frequencies by functional magnetic resonance imaging (fMRI) and magnetoencephalography (MEG). Presentation at 22nd International Congress on Sound and Vibration. Available from: https://stopthese things.files.wordpress.com/2015/07/full_paper_koch-v2-1.pdf. [Last accessed on 2016 July 14.]
- ¹³⁵ He M, Krahe D. EEG reaction under low frequency noise exposure. Presentation at 22nd International Congress on Sound and Vibration. Available from: <http://waubrafoundation.org.au/wp-content/uploads/2016/02/He-Krahe-EEG-Reaction-Under-Low-Frequency-Noise-Exposure.pdf>. [Last accessed on 2016 July 15.]
- ¹³⁶ Kugler K, Wiegrebe L, Grothe B, Kössl M, Gürkov R, Krause E, et al. Low-frequency sound affects active micromechanics in the human inner ear. *Royal Society Open Science* October 2014. Available from: <http://dx.doi.org/10.1098/rsos.140166>. [Last accessed on 2016 July 20].
- ¹³⁷ Kemp DT. Stimulated acoustic emissions from within the human auditory system. *Journal of the Acoustical Society of America* 1978;64:1386-1391.
- ¹³⁸ Schomer PD, Erdreich J, Pamidighantam PK, Boyle JH. A theory to explain some physiological effects of the infrasonic emissions at some wind farm sites. *Journal of the Acoustical Society of America* 2015;137,1356-1365.
- ¹³⁹ Michaud DS, Feder K, Keith SE, Voicescu SA, Marro L, Than J, et al. Effects of wind turbine noise on self-reported and objective measures of sleep. *Sleep* 2016;39(1):97-109.
- ¹⁴⁰ Michaud D. Health and well-being related to wind turbine noise exposure: Summary of results. *Journal of the Acoustical Society of America* 2015;137:2368.

-
- ¹⁴¹ Michaud DS, Feder K, Keith SE, Voicescu SA, Marro L, Than J, et al. Exposure to wind turbine noise: perceptual responses and reported health effects. *Journal of the Acoustical Society of America* 2016;139:1443-1454.
- ¹⁴² Michaud DS, Keith SE, Feder K, Voicescu SA, Marro L, Than J, et al. Personal and situational variables associated with wind turbine noise annoyance *Journal of the Acoustical Society of America* 2016;139:1455-1466.
- ¹⁴³ Michaud DS, Feder K, Keith SE, Voicescu SA, Marro L, Than J, et al. Self-reported and measured stress related responses associated with exposure to wind turbine noise. *Journal of the Acoustical Society of America* 2016;139:1467-1479.
- ¹⁴⁴ Voicescu SA, Michaud DS, Feder K, Marro L, Than J, Guay M, et al. Estimating annoyance to calculated wind turbine shadow flicker is improved when variables associated with wind turbine noise exposure are considered. *Journal of the Acoustical Society of America* 2016;139:1480-1492.
- ¹⁴⁵ Michaud DS. An evaluation of how nightly variations in wind turbine noise levels influence wrist actigraphy measured sleep patterns. *Journal of the Acoustical Society of America* 2016;139:2150.
- ¹⁴⁶ Pedersen E, van den Berg F, Bakker R, Bouma J. Response to noise from modern wind farms in The Netherlands. *Journal of the Acoustical Society of America* 2009;126:634-643.
- ¹⁴⁷ Position of the National Institute of Public Health – National Institute of Hygiene on wind farms. March 8, 2016. Available from: <http://en.friends-against-wind.org/health/position-of-the-polish-public-health-institute-on-wind-farms>. [Last accessed on 2016 July 14.]
- ¹⁴⁸ Knopper LD, Ollson CA, McCallum LC, Whitfield Aslund ML, Berger RG, Souweine K, McDaniel M. Wind turbines and human health. *Frontiers in Public Health* 2014;19.
- ¹⁴⁹ Pedersen E, Persson Waye KP. Wind turbine noise, annoyance and self-reported health and wellbeing in different living environments. *Occupational and Environmental Medicine* 2007;64(7):480-486.
- ¹⁵⁰ Tempest W. Loudness and annoyance due to low frequency sound. *Acustica* 1973;29: 205-209.
- ¹⁵¹ Bastasch M, van Dam J, Søndergaard B, Rogers A. Wind turbine noise: an overview. *Canadian Acoustics* 2006;34:7-15.
- ¹⁵² Ruotolo F, Senese VP, Ruggiero G, Maffei L, Masullo M, Iachin T. Individual reactions to a multisensory immersive virtual environment: the impact of a wind farm on individuals. *Cognitive Processing* 2012; Suppl 1, S319-23.
- ¹⁵³ Rylander R. Physiological aspects of noise-induced stress and annoyance. *Journal of Sound and Vibration* 2004;277:471-478.

-
- ¹⁵⁴ Fast S, Mabee W, Baxter J, Christidis T, Driver L, Hill S, et al. Lessons learned from Ontario wind energy disputes. *Nature Energy* 2016. Available from: <http://www.nature.com/articles/nenergy201528>. [Last accessed on 2016 July 18.]
- ¹⁵⁵ McCallum LC, Whitfield Aslund ML, Knopper LD, Ferguson GM, Ollson CA. Measuring electromagnetic fields (EMF) around wind turbines in Canada: is there a human health concern? *Environmental Health* 2014;13:1-6.
- ¹⁵⁶ Röösl M. Radiofrequency electromagnetic field exposure and non-specific symptoms of ill health: a systematic review. *Environmental Research* 2008;107(2):277-287.
- ¹⁵⁷ Rubin GJ, Das Munshi J, Wessely S. Electromagnetic hypersensitivity: a systematic review of provocation studies. *Psychosomatic Medicine* 2005;67(2):224-232.
- ¹⁵⁸ Fletcher H, Munson WA. Loudness, its definition, measurement and calculation. *Journal of the Acoustical Society of America* 1933;5:82-108.
- ¹⁵⁹ Pedersen E, Persson Wayne KP. Wind turbines—low level noise sources interfering with restoration? *Environmental Research Letters* 2008;3:1-5.
- ¹⁶⁰ Bray W. Relevance and applicability of the soundscape concept to physiological or behavioral effects caused by noise at very low frequencies which may not be audible. Presentation at 164th meeting of Acoustical Society of America, October 2012. Available from: http://acoustics.org/pressroom/httpdocs/164th/Bray_2aNS6.html. [Last accessed on 2016 July 20].
- ¹⁶¹ McMurtry RY. Toward a case definition of adverse health effects in the environs of industrial wind turbines: facilitating a clinical diagnosis. *Bulletin of Science, Technology & Society* 2011; 31:316-320.
- ¹⁶² McMurtry RY, Krogh CME. Diagnostic criteria for adverse health effects in the environs of wind turbines. *Journal of the Royal Society of Medicine Open* 2014;5:1-5.
- ¹⁶³ McCunney RJ, Morfeld P, Colby WD, Mundt KA. Wind turbines and health: An examination of a proposed case definition. *Noise & Health* 2015;17:175-181.
- ¹⁶⁴ Halperin A. Big wind is better than big oil, but just as bad at P.R. June 15, 2014. Available from: <https://newrepublic.com/article/118138/big-wind-needs-address-wind-turbine-syndrome>. [Last accessed on 2016 July 20].
- ¹⁶⁵ Berglund B, Hassmen P, Soames Job RF. Sources and effects of low-frequency noise. *Journal of the Acoustical Society of America* 1996;99:2985-3002.
- ¹⁶⁶ ISO 1996-1:2016. Acoustics—Description, measurement and assessment of environmental noise—Part 1: Basic quantities and assessment procedures. Available from: http://www.iso.org/iso/home/store/catalogue_ics/catalogue_detail_ics.htm?csnumber=59765. [Last accessed on 2016 July 11].

-
- ¹⁶⁷ ANSI/ASA S12.9—2005/Part 4 (R2015). Quantities and procedures for description and measurement of environment sound—Part 4: Noise assessment and prediction of long-term community response. Available from: [http://webstore.ansi.org/RecordDetail.aspx?sku=ANSI%2fASA+S12.9-2005%2fPart+4+\(R2015\)](http://webstore.ansi.org/RecordDetail.aspx?sku=ANSI%2fASA+S12.9-2005%2fPart+4+(R2015)). [Last accessed on 2016 July 11].
- ¹⁶⁸ Hill AB. The environment and disease: association or causation? *Proceedings of the Royal Society of Medicine* 1965;58:295-300.
- ¹⁶⁹ Phillips CV. Properly interpreting the epidemiologic evidence about the health effects of industrial wind turbines on nearby residents. *Bulletin of Science, Technology & Society* 2011;31:303-315.
- ¹⁷⁰ World Health Organization Health topics: epidemiology. Available from: <http://www.who.int/topics/epidemiology/en/>. [Last accessed on 2016 July 20].
- ¹⁷¹ Songer T. Basic epidemiology: study designs in epidemiologic research. Available from: <http://www.google.com/url?sa=t&ret=j&q=&esrc=s&source=web&cd=2&ved=0CCsQFjAB&url=http%3A%2F%2Fwww.pitt.edu%2F~super7%2F19011-20001%2F19101.ppt&ei=LRibU4PAPMyiyATpioGwDQ&usq=AFQjCNG5R1wNMj3ipEws4rzLaG7kHvH0CQ&sig2=T1hDZwtlnN7BGvsvpCIfgQ&bvm=bv.68911936,d.aWw&cad=rja>. [Last accessed on 2016 July 20].
- ¹⁷² University of Ottawa. Society, the individual and medicine: study designs. Available from: http://www.med.uottawa.ca/sim/data/Study_Designs_e.htm. [Last accessed on 2016 July 20].
- ¹⁷³ Chapman S, St. George A, Waller K, Cakic V. The pattern of complaints about Australian wind farms does not match the establishment and distribution of turbines: support for the psychogenic, 'Communicated Disease' hypothesis. *PLoS ONE* 2013;8(10). Available from: <http://www.ncbi.nlm.nih.gov/pmc/articles/PMC3797792/>. [Last accessed on 2016 July 20].
- ¹⁷⁴ Crichton F, Dodd G, Schmid G, Gamble G, Petrie KJ. Can expectations produce symptoms from infrasound associated with wind turbines? *Health Psychology* 2013;33:360-364.
- ¹⁷⁵ Punch J. Review of Crichton et al. (Can expectations produce symptoms from infrasound associated with wind turbines?). March 28, 2013. Available from: <http://www.wind-watch.org/documents/review-of-crichton-et-al-can-expectations-produce-symptoms-from-infrasound-associated-with-wind-turbines/>. [Last accessed on 2016 July 20].
- ¹⁷⁶ Williams T. The effects of expectations on perception: experimental design issues and further evidence. Working paper series, Federal Reserve Bank of Boston, No. 07-14. Available from: <http://www.bostonfed.org/economic/wp/wp2007/wp0714.pdf>. [Last accessed on 2016 July 20].
- ¹⁷⁷ Crichton F, Dodd G, Schmid G, Gamble G, Cundy T, Petrie KJ. The power of positive and negative expectations to influence reported symptoms and mood during exposure to wind farm sound. *Health Psychology* 2013; 33:1588-1592.

-
- ¹⁷⁸ Chen HA, Narins P. Wind turbines and ghost stories: the effects of infrasound on the human auditory system. *Acoustics Today* 2012;8:51-56.
- ¹⁷⁹ Tonin R, Brett J, Colagiuri B. The effect of infrasound and negative expectations to adverse pathological symptoms from wind farms. *Journal of Low Frequency Noise, Vibration and Active Control* 2016;35(1):77-90.
- ¹⁸⁰ Taylor J, Eastwick C, Wilson R, Lawrence C. The influence of negative oriented personality traits on the effects of wind turbine noise. *Personality and Individual Differences* 2013;54:338-343.

3 of 3

RECEIVED

MAY 03 2018

**SOUTH DAKOTA PUBLIC
UTILITIES COMMISSION**

To: Amanda Reiss