



# Crowned Ridge Wind II

**South Dakota PUC  
Public Input Meeting  
Watertown, SD  
August 26, 2019**



# Applicant Overview

- ▶ **Crowned Ridge Wind II, LLC (CRW II) is a wholly owned, indirect subsidiary of NextEra Energy Resources, LLC (NEER)**
  - » American owned and operated, NEER is the world's largest generator of renewable energy from the wind and sun
- ▶ **CRW II possesses a Purchase and Sale Agreement (PSA) with Northern States Power (NSP)**
  - » NEER is responsible for the development, permitting and construction of CRW II
  - » NSP will own and operate CRW II upon the Project's proposed Commercial Operations Date (COD) of Q4 2020




**world's  
#1  
generator of wind  
and solar energy  
2018**

# Project Overview – Purpose of Project

- ▶ **Crowned Ridge Wind II, LLC is seeking Energy Facility Permit approval for the proposed up to 300.6 MW Project located in Codington, Deuel and Grant Counties, South Dakota ...**
  - » To satisfy renewable energy requirements within NSP's service territory by delivering zero-emission, competitively priced electricity to the Midcontinent Independent System Operator, Inc (MISO) regional grid
  - » Demand was recognized/approved by the Minnesota Public Utilities Commission and the North Dakota Public Service Commission
  - » To supplement NSP's pursuit of a higher renewable energy generation mix across their generation portfolio


# Project Overview

- ▶ **CRW II Energy Facility Application**
  - » PUC filing date: July 9, 2019
  - » PUC Status: Under review
- ▶ **CRW II is seeking Energy Facility Permit approval to construct the up to 300.6 MW wind Project**
  - » CRW II would commence construction in Q2 2020 assuming the South Dakota PUC's 9-month review/approval timeline
- ▶ **The Project reflects a \$400 million investment in the state of South Dakota**
  - » Located in Codington County, Deuel County and Grant County




# Project Overview – Site Map

- ▶ **Project Size:** 300.6 MW
- ▶ **Project Area:** 60,996 acres
- ▶ **Participation:** 40,911 acres
- ▶ **Project Turbines:** 132 GE turbines
  - » 66 locations proposed in Codington
  - » 66 locations proposed in Deuel
  - » 2 locations proposed in Grant County
- ▶ **Additional Project Facilities:**
  - » Access roads to Project facilities
  - » Underground collection cabling
  - » Two permanent MET tower locations
  - » An Operations and Maintenance (O&M) Facility



# Project Overview – Land


- ▶ Land acquisition process is near complete pending approval of three easements
  - » One turbine location pending easement approval
  - » One collection corridor pending easement approval
  - » One construction access road pending easement approval
- ▶ CRW II anticipates all necessary easements to be obtained by Sep. 20, 2019
  - » Easements obtained post filing of application to support two turbine locations formerly pending approval



# Project Overview – Turbine Technology

**GE 2.3 MW Turbine**


Count	Rotor Diameter	Hub Height
117	116 meters	90 meters



485 feet

**GE 2.1 MW Turbine**

Count	Rotor Diameter	Hub Height
15	116 meters	80 meters



452 feet

# Community Benefits

## ► Boost to local economy

- » 250 temporary construction jobs will increase local spend (hotels, dining, places to conduct general business)
- » Up to 12 full time, long term O&M jobs created for the life of the Project
- » Improvements to existing county and township roads

## ► Landowner benefits

- » Additional revenue stream
- » Approx. \$40 million in payments to landowners over life of the Project





# Community Benefits

## Crowned Ridge Wind II – 25 year expected tax revenues generated

<b>Deuel County Jurisdictions</b>	<b>Estimated Tax Revenue</b>
Deuel County	\$ 4,460,000
Goodwin Township	\$ 1,720,000
Rome Township	\$ 620,000
Deuel School District	\$ 5,540,000
	<b>\$ 12.3 million</b>
<b>Codington County Jurisdictions</b>	<b>Estimated Tax Revenue</b>
Codington County	\$ 4,320,000
Waverly Township	\$ 860,000
Kranzburg Township	\$ 570,000
Waverly School District	\$ 5,630,000
Watertown School District	\$ 1,580,000
	<b>\$ 12.9 million</b>
<b>Grant County Jurisdictions</b>	<b>Estimated Tax Revenue</b>
Grant County	\$ 140,000
Troy Township	\$ 50,000
	<b>\$ 190,000</b>

# Community Benefits

- ▶ Local support of organizations, groups and events
  - » Crystal Springs Rodeo
  - » South Dakota Wind for Schools
  - » Kite Day at the Capitol
  - » SDSU Wind Application Center
  - » Mitchell Tech / Lake Area Tech
  - » Molded Fiber Glass (Aberdeen, SD)
  - » Farley Fest (Milbank, SD)



FEATURED

## New contract keeps MFG open; 60 jobs to be added

By Elisa Sand, [esand@aberdeennews.com](mailto:esand@aberdeennews.com) Jul 2, 2018 0 1 min to read

# Stakeholder Outreach

- ▶ Stakeholder outreach involved communication with landowners, local tribes, wildlife agencies and government officials:
  - » Open House
  - » Codington, Deuel and Grant County Planning and Zoning Boards
  - » Codington, Deuel and Grant County Commissions
  - » Sisseton Wahpeton Oyate Tribe
  - » United States Fish & Wildlife Service
  - » South Dakota Game, Fish & Parks
  - » South Dakota State Historical Society



# Project Compliance

- ▶ CRW II has worked diligently to make the necessary changes to the Project site plan to meet and exceed local and state wind energy siting requirements

	<b>Codington</b>	<b>Grant</b>	<b>Deuel</b>
<b>Setbacks</b>	<ul style="list-style-type: none"> <li>- 550' from participant</li> <li>- 1,500' from non-participant</li> <li>- 1-mile from municipal boundary</li> </ul>	<ul style="list-style-type: none"> <li>- 1,500' from participant</li> <li>- 1,500' from non-participant</li> <li>- 1 mile from municipal boundary</li> </ul>	<ul style="list-style-type: none"> <li>- 1,500' from participant</li> <li>- 4 times turbine height from non-participant</li> <li>- 1 mile from municipality of Goodwin</li> <li>- 1 mile from lake district at Bullhead Lake</li> </ul>
<b>Noise</b>	<ul style="list-style-type: none"> <li>- Shall not exceed 50 dBA; measured at property line of existing non-participating residence</li> </ul>	<ul style="list-style-type: none"> <li>- Shall not exceed 45 dBA; measured 25 feet from perimeter of non-participating residences</li> <li>- Shall not exceed 50 dBA, measured 25 feet from perimeter of participating residences</li> </ul>	<ul style="list-style-type: none"> <li>- Shall not exceed 45 dBA; measured from perimeter of non-participating residences</li> </ul>
<b>Flicker Analysis</b>	<ul style="list-style-type: none"> <li>- Flicker at any receptor shall not exceed thirty (30) hours per year</li> </ul>	<ul style="list-style-type: none"> <li>- Flicker at any receptor shall not exceed thirty (30) hours per year</li> </ul>	<ul style="list-style-type: none"> <li>- Flicker at any receptor shall not exceed thirty (30) hours per year</li> </ul>

# Wind Farm Description

- ▶ **The Project will consist of up to 132 turbines, a collector substation, underground collection lines and an O&M facility:**
  - » **Turbines** – 117 GE 2.3 MW, 90m HH and 15 GE 2.1 MW 80m HH
  - » **Associated Collector Substation** – 34.5 kV to 230 kV fenced area with breakers, switches, control house and two power transformers
  - » **Underground Collection Lines** – 34.5 kV power cables buried at least 48 inches below the surface to connect the turbines to the substation, and includes pad mount transformers and junction boxes
  - » **O&M Facility** – Fenced area with a main building that accommodates offices, spare parts storage, maintenance shop and parking facilities

# Construction Overview

- ▶ The construction process begins with a detailed engineering design for all facets of the Project including; access roads, turbine foundations, tower erection and electrical systems
- ▶ Turbine Foundation
  - » Remove and stockpile top soil for future reclamation
  - » Install straw waddles and silt fences to control run-off during rain events
  - » Excavate turbine foundation to approx. 8' depth
  - » Install rebar and bolt cage
  - » Pour concrete supplied by on-site batch plant



# Construction Overview

- ▶ Turbine towers are erected using special cranes capable of lifting up to 1,800 tons and reaching a height of 350 feet
  - » Install down tower assembly including turbine converter
  - » Install tower base including torqueing anchor bolts
  - » Install mid and top tower sections
  - » Install nacelle, hub and fly rotor



# Construction Overview

- ▶ **The collection lines are installed using a trencher or horizontal direction bores**
  - » Cables and communication lines are laid simultaneously while trench is being cut
  - » Trenches are back filled with native soil and compacted
- ▶ **The collector substation is designed and constructed to meet all applicable codes and standards**
  - » Clear and grub site, grade and compact site
  - » Install below grade infrastructure, equipment foundations, wire and termination
  - » Test and commission equipment





# Operations Overview

- ▶ **The Project will be monitored 24/7 by a Supervisory Controls and Data Acquisitions (SCADA) system**
  - » NSP's Commercial Operations Center, a fulltime remote monitoring and control facility located in Denver Colorado, ensures safe and reliable operations by providing remote real-time monitoring and controlling of the entire Project, including the wind turbines
- ▶ **The O&M building (approx. 8,000 sq. ft.) will provide accommodation for the operations personnel**
  - » Up to 12 permanent employees, consisting of an operations manager and wind technicians, will operate the windfarm and substation after construction is completed
  - » During operations, the site team will perform scheduled, preventive maintenance on wind turbines
  - » The O&M will house operating personnel, offices, operations and communication equipment, parts storage, outdoor lighting and perimeter fencing

# Decommissioning Overview

- ▶ **CRW II, under the ownership of NSP, is responsible for Project decommissioning and all costs with decommissioning the associated facilities**
  - » Removal of 132 wind turbines and all existing above ground facilities
  - » Removal of all ancillary, underground equipment to a depth of 4 feet
  - » Removal of roads and staging areas unless the private landowners desire for roads and staging areas to be retained
  - » Restoration to pre-construction conditions to the extent possible including:
    - › Vegetation, drainage and other environmental features
  - » Repair to county/township roads impacted by movement of heavy vehicles and frequent vehicle trips

# Contact Information

## Crowned Ridge Wind II, LLC

Tyler Wilhelm

*Senior Project Manager*

[Tyler.Wilhelm@NextEraEnergy.com](mailto:Tyler.Wilhelm@NextEraEnergy.com)

## South Dakota PUC Website

<https://puc.sd.gov>

