

The re-route runs approximately two miles south of the original crossing of the James River. This re-route adds approximately two miles of length to the project while avoiding three waterbody crossings. If a cultural site is identified during surveys, DAPL would reroute to avoid the site while not crossing any additional landowners. Respective landowner notifications were sent out on March 17 2015, and many of the landowners on this re-routed segment were landowners on the original route.

Dakota Access Pipeline James River Reroute Options								
James River Alternate Routes	Length of Pipeline Reroute (mi)	Powerline Crossings	Pipeline Crossings	NWI Lake/Pond Crossings	NWI Lake/Pond Total Distance Crossed (ft)	NHD Stream Crossings	NWI PEM Wetlands Crossed	PEM Wetland Total Crossing Distance (mi)
Previous Route	6.3	0	1	1	61.0	5	10	0.30
Proposed Route	8.2	0	1	0	0	3	17	0.25

