

**BEFORE THE PUBLIC UTILITIES COMMISSION  
OF THE STATE OF SOUTH DAKOTA**

**IN THE MATTER OF THE APPLICATION BY SCS CARBON TRANSPORT LLC FOR  
A PERMIT TO CONSTRUCT A CARBON DIOXIDE TRANSMISSION PIPELINE**

**SD PUC DOCKET NO. \_\_\_\_\_**

**PRE-FILED DIRECT TESTIMONY OF DR. JON A. SCHMIDT, PHD  
ON BEHALF OF SCS CARBON TRANSPORT LLC**

November 19, 2024

1 **Q. Please state your name and business address for the record.**

2 **A.** My name is Jon Schmidt. My business address is 2510 Miccosukee Road, Suite 200,  
3 Tallahassee, Florida 32308.

4 **Q. Can you briefly describe your education and experience?**

5 **A.** I have a bachelor's, master's, and doctorate in biological sciences. I have been employed  
6 as an environmental consultant for 37 years. My primary experience has been the  
7 preparation of permit applications and regulatory filings for pipelines, powerlines, LNG  
8 facilities, and natural gas storage facilities throughout the U.S. Over my career, I have  
9 served as project task leader, project manager, project director, and owner's  
10 environmental representative for large infrastructure permitting projects covering multiple  
11 jurisdictions in the U.S.

12 **Q. Please describe your duties with SCS Carbon Transport LLC (SCS).**

13 **A.** As part of the Project team, I am EXP's Project Manager for providing environmental  
14 project management services to SCS Carbon Transport LLC (SCS). Specifically, I oversee  
15 environmental data collection, permit application preparation, and agency consultation.

16 **Q. Which sections of the application are you responsible for?**

17 **A.** I oversaw or participated in the preparation of the following sections of the Application:

- 18 • Section 1.8 – Other required permits and approvals;
- 19 • Section 5 – Environmental Information and Impact on Physical Environment;
- 20 • Section 6 – Community Impacts
- 21 • Section 7.2 – Monitoring of Impacts;
- 22 • Appendix 4 – Environmental Construction Plan;
- 23 • Appendix 5 – Map Books (Topographic, Land Use, Soils, Hydrology);
- 24 • Appendix 6 – South Dakota Agricultural Impact Mitigation Plan;
- 25 • Appendix 12 – Soil Crossing Tables;
- 26 • Appendix 14 – Wetland and Waterbody Crossings;
- 27 • Appendix 15 – Threatened and Endangered Species Report;
- 28 • Appendix 16 – Wetland Delineation Report;
- 29 • Appendix 17 – South Dakota Noxious Weeds Management Plan;

- 1 • Appendix 18 – Project Waterfowl Production Area Crossing Table;
- 2 • Appendix 19 – South Dakota Dust Control Plan;
- 3 • Appendix 22 – Environmental Agency Correspondence

4

5 **Q. What is the purpose of your Direct Testimony?**

6 **A.** The purpose of my testimony is to provide information concerning existing environmental  
7 conditions along the Project route, potential impacts of the Project on the existing  
8 environment, and how the Project will avoid, minimize, and/or mitigate potential impacts.  
9 In addition, I generally describe the environmental features found in the 300-foot survey  
10 corridor examined during field surveys, desk top analysis; general regional environmental  
11 conditions along the corridor; and federal and state agency correspondence and  
12 coordination.

13 **Q. What was the overall approach to environmental analysis for the Project?**

14 **A.** SCS initially completed site characterization and assessment analyses using a  
15 Geographic Information System (GIS) based routing program to identify and assess  
16 existing resources and features to inform selection of the Project’s route within a study  
17 corridor. The study corridor was approximately 1-2 miles wide to identify potential route  
18 alternatives. SCS then completed a desktop analysis of constraints and further  
19 opportunities to focus on a preferred route. Changes to this base route utilized agency  
20 supplied and desktop data to minimize impacts. Using the results of the desktop analysis,  
21 SCS then coordinated with state and federal agencies and conducted field  
22 surveys/studies. Surveys of the 300-foot corridor centered on the proposed route.  
23 Interested Tribes also participated in cultural resource surveys where access was granted.  
24 The results of these efforts were incorporated into the Project design to avoid or minimize  
25 impacts to protected or sensitive resources during Project construction and operations  
26 and confirm appropriate environmental permitting requirements, if any. These  
27 environmental efforts were coordinated with landowner discussions on routing and route  
28 placement as well as engineering analysis (e.g., stream crossing locations and crossing  
29 methods) that resulted in the route provided in this Application.

30 **Q. Please describe the environmental survey corridor used for the studies and**  
31 **surveys of the Project route.**

32 **A.** A survey corridor of 300-feet was centered along the proposed route. Along access roads,

1 the survey corridor was 50 to 100-feet centered on the centerline of the access road. Any  
2 aboveground facilities (e.g., pump station) were surveyed in their entirety for their footprint.

3 **Q. Is there any environmental study/survey work yet to be completed for the Project?**

4 A. Field surveys for biological resources (listed species and wetland/waterbody surveys)  
5 have been completed for 357.8 miles or 51.3% of the current alignment. Desktop  
6 wetland/waterbody delineations have been completed for the remainder of the project  
7 footprint. Cultural resource surveys have been completed for 495.2 miles or 70.9%.

8 **Q. Can you describe the permits in addition to the one sought in this Application  
9 which will be required for construction and operation of the pipeline.**

10 A. Yes. I oversaw the compilation of the table of permits that are required for the Project.  
11 Section 1.8 of the Application provides an overview of the permits required to construct  
12 and operate the Project.

13 **Q. How did SCS categorize land found along the pipeline?**

14 A. Using national land use databases, field surveys, and recent aerial imagery, SCS mapped  
15 the land uses depicted in Appendix 5.

16 **Q. Were any PUC land uses not documented along the pipeline?**

17 A. The Project does not cross existing and potential extractive nonrenewable resources,  
18 other major industries, residential, and municipal water supply and water sources for  
19 organized rural water systems.

20 **Q. What effects are anticipated on surrounding land from operation or construction  
21 of the pipeline?**

22 A. During construction there will be short-term periods of increased noise, dust, and  
23 additional traffic on local roads as the construction spread moves through an area. None  
24 of these impacts will be significant or long-term. During operations, there will be no  
25 impacts to existing land uses along the pipelines, except where above ground facilities  
26 are sited (MLVs), and there will be some increased noise from pump stations. However,  
27 SCS will site the pump stations to avoid proximity to houses or residential areas to reduce  
28 noise impacts.

29 **Q. Did the project analyze the effects of the Pipeline on land uses and if so, what are  
30 the impacts?**

1 **A.** Yes, Section 5.5 (Land Use And Local Land Controls) provides an assessment of the land  
2 uses impacted by the Project and the minimization and mitigation measures that will be  
3 implemented to address those impacts. The land uses crossed are also depicted on maps  
4 in Appendix 5 of the Application. Since the predominant land use crossed by the Project  
5 is rural agriculture, and because the pipeline will be buried a depth of four feet or more  
6 below pasture/rangeland and agricultural fields and agricultural use will be allowed after  
7 construction, the pipeline project will be compatible with the current land uses crossed.  
8 The route also crosses through fourteen rural water system territories or districts. During  
9 construction and maintenance, SCS will coordinate with the One-Call system and the rural  
10 water authority to identify and avoid impacts to underground utilities, including water lines.

11 **Q. What steps will SCS take to avoid, minimize, and/or mitigate potential impacts to**  
12 **the existing land uses?**

13 **A.** The steps SCS will take to avoid, minimize, and/or mitigate potential impacts to existing  
14 land uses are detailed in Section 5.5.5 (Impacts and Avoidance/Mitigation Measures). To  
15 avoid, minimize, and/or mitigate potential impacts to existing land uses, SCS will take the  
16 following steps as detailed in Section 5.5.5 (Impacts and Avoidance/Mitigation Measures):

- 17 • **Compliance:** Adhere to the permitting requirements identified in Table 2 of the  
18 Application and as discussed in Section 1.8 of the Application.
- 19 • **Pipeline Installation:** Bury the pipeline with a minimum of four feet of cover to  
20 avoid interfering with normal agricultural operations. Work with landowners to  
21 identify and install the pipeline below drain tiles, repairing any impacted tiles per  
22 Section 6.7 of the SD Agricultural Impact Mitigation Plan (SD AIMP) presented in  
23 Appendix 6 of the Application.
- 24 • **Compensation:** Compensate landowners for the construction and permanent  
25 right-of-row (ROW), crop losses, and other damage caused by construction.  
26 Restore ROW for grazing and livestock movement post-construction, with seed  
27 mixes for revegetation determined after consulting landowners and Natural  
28 Resources Conservation Service (NRCS) offices. Use irrigation methods as  
29 required per Section 7.2.4 of the Project's Environmental Construction Plan (ECP  
30 [Appendix 4 of the Application]).
- 31 • **Restoration Measures:** Follow measures in the Project's ECP and SD AIMP to  
32 promote ROW restoration, including topsoil removal/restoration and reseeded  
33 with approved seed mixtures.

- 1 • **Minimizing Wetland Impacts:** Adhere to Project's ECP measures to minimize  
2 wetland impacts, using horizontal direction drills (HDDs) where practicable to avoid  
3 impacts to wetlands, waterbodies, and grasslands.
- 4 • **Agency Coordination:** Work with the U.S. Department of Agriculture (USDA) to  
5 identify conservation parcels and ensure no landowner penalties under their  
6 easement contracts. Coordinate with the USDA and landowners on easement  
7 crossings to meet reclamation requirements or provide compensation.

8 SCS will also follow additional construction procedures, mitigation measures, and BMPs  
9 outlined in the Project's ECP, SD AIMP, Inadvertent Return Plan (Appendix 7 of the  
10 Application), and South Dakota Noxious Weeds Management Plan (Appendix 17 of the  
11 Application) to reduce construction and operation impacts through restoration processes.

12 **Q. Can you provide a summary of the Project's mitigation plans to use across the**  
13 **Project?**

14 A. SCS has developed or will develop several plans to minimize and/or mitigate the potential  
15 impacts of Project construction. The Project intends to update these mitigation plans as  
16 necessary after communication with various agencies. An overview of mitigation plans  
17 developed or to be developed for the Project is provided below.

- 18 • Environmental Construction Plan. SCS has prepared an ECP, which outlines  
19 construction-related environmental policies, procedures, and general protection  
20 measures for construction of the Project. The ECP identifies generally recognized  
21 BMPs SCS will implement to avoid, minimize, and/or mitigate potential impacts to  
22 wetlands, waterbodies, and agricultural areas. The ECP is included as Appendix  
23 4 to the Application. A Spills Prevention, Control, and Countermeasure (SPCC)  
24 Plan will be prepared during the stormwater construction permitting process once  
25 construction contractors are chosen and assigned to specific spreads.
- 26 • Agricultural Impact Mitigation Plan. SCS has prepared an SD AIMP (Appendix 6),  
27 which describes proposed measures SCS will implement to minimize potential  
28 impacts to and restore agricultural lands during and after construction of the  
29 Project. The SD AIMP details methods to preserve topsoil, prevent erosion, avoid  
30 and/or minimize impacts to drain tile, restore agricultural land following  
31 construction, and establish appropriate vegetation cover that will help ensure the  
32 Project is designed, constructed, and operated in a manner allowing the land to be  
33 returned to its pre-construction condition. The SD AIMP is included as Appendix 6

1 to the Application.

- 2 • South Dakota Noxious Weed Management Plan. SCS has prepared a South  
3 Dakota Noxious Weed Management Plan following the requirements of the SD  
4 Department of Agriculture & Natural Resources (DANR) and best practices, which  
5 outlines strategies and practices SCS will utilize to prevent and/or control the  
6 spread of noxious weeds during and following construction of the Project. The SD  
7 Noxious Weed Management Plan is included as Appendix 17 to the Application.
- 8 • Unanticipated Discoveries Plan. SCS has prepared an Unanticipated Discovery  
9 Plan (UDP) to be used in the unlikely event that previously unidentified cultural  
10 resources are encountered during construction. As described in the Direct  
11 Testimony of Erin Salisbury, SCS's UDP sets forth specific guidelines to be used  
12 if previously unknown archaeological resources and/or human remains are  
13 encountered during construction activities. The UDP is included as Appendix 21 to  
14 the Application.
- 15 • Stormwater Pollution Prevention Plan (SWPPP). SCS will prepare a SWPPP for  
16 the Project to meet the requirements outlined in the National Pollutant Discharge  
17 Elimination System (NPDES) Permit, the SD DANR's General Permit Authorizing  
18 Stormwater Discharges Associated with Construction Activities Under the South  
19 Dakota Surface Water Discharge System that SCS will obtain coverage under prior  
20 to ground disturbing activities. SCS and its construction contractor(s) will  
21 implement the SWPPP during the construction and restoration activities  
22 associated with the Project. The SWPPP will include measures SCS will employ  
23 to minimize and/or mitigate the potential environmental impacts of construction and  
24 will be filed prior to construction.
- 25 • Inadvertent Return Plan. SCS has prepared an Inadvertent Return Plan (Appendix  
26 7 to the Application), which will outlines operational procedures and responsibilities  
27 for the prevention, containment, and clean-up of inadvertent returns associated  
28 with the HDD crossing method, including: measures to minimize the potential for  
29 an inadvertent return of drilling fluids associated with HDD activities; procedures  
30 to ensure timely detection of inadvertent returns; measures to protect  
31 environmentally sensitive areas while responding to an inadvertent return;  
32 measures to ensure an organized, timely, minimum impact response in the event  
33 of an inadvertent return; and procedures to ensure all appropriate notifications are  
34 made.
- 35 • South Dakota Dust Control Plan. SCS has prepared a South Dakota Dust Control

1 Plan (Appendix 19 to the Application) that will be followed by the construction  
2 contractor to reduce fugitive dust during dry conditions or when otherwise needed  
3 along the construction ROW or access roads. Water trucks will manage to control  
4 dust in most situations, but temporary seeding or tackifiers may be used on soil  
5 piles in dry, windy conditions to prevent the loss of topsoil.

6 **Q. Does the project cross any public properties?**

7 **A.** There are approximately 698 miles of pipeline in the state. Of this, approximately 10.8  
8 miles (1.5% of the total miles) are Department of School and Public Lands. The remainder  
9 of the land crossed is privately owned. No tribal or federally owned lands are planned to  
10 be crossed by the pipeline routes.

11 **Q. What are the regional landforms in the Project area?**

12 **A.** In the Project area, the two physiographic provinces are divided into six subdivisions, the  
13 Missouri Coteau division of the Great Plains province; and the James River Lowland, Lake  
14 Dakota Plain, Prairie Coteau, Red River Lowland, and the Loess Hills subdivisions of the  
15 Central Lowlands province.

16 The Red River Lowland subdivision is characterized as a broad, gently rolling valley-like  
17 area with elevations ranging from 900 to 1,100 feet above sea level (asl). The region is  
18 economically important due to the presence of high-quality granite bedrock (typically  
19 approximately several thousand feet deep) that outcrops in some locations and is  
20 commercially quarried for building stone.

21 The Prairie Coteau subdivision is a highland area which is part of a plateau that extends  
22 north through North Dakota into Canada. The division slopes gently to the south and west;  
23 elevations range from 1,600 feet to 2,000 feet asl, and the division drains to the south via  
24 the Big Sioux River. West of the river the surface is dotted with lakes and depressions;  
25 east of the river few lakes occur.

26 The James River Lowland subdivision is a broad gently rolling lowland plain drained from  
27 north to south by the James River. The division lies between the Prairie Coteau subdivision  
28 to the east and the Missouri Coteau subdivision to the west at generally lower elevations  
29 ranging from 1,300 to 1,400 feet asl.

30 The Lake Dakota Plain subdivision is bounded by the James River Lowland subdivision  
31 and is characterized by a nearly level surface formed by sediment deposition when Glacial



1 Lake Dakota was filled with water during the last glacial retreat. The mainly featureless  
2 plain exhibits a change in relief of less than 10 feet with elevation at approximately 1,300  
3 feet asl.

4 The Missouri Coteau subdivision is a highland occurring in a north/south band through  
5 South Dakota, separated from the main body of the Missouri Plateau by the Missouri River  
6 which forms the division's western boundary. The topography of the subdivision is highly  
7 variable due to deposits of glacial drift underlain at great depth by Pierre Shale and older  
8 formations. Elevations range from approximately 1,750 feet asl to approximately 2,200  
9 feet asl.

10 The Loess Hills subdivision forms a narrow band of sharply dissected uplands along the  
11 east edge of the Missouri River valley. The loess uplands formed as glacial meltwater  
12 deposited fine sediment into the Missouri River valley which was carried east by wind  
13 activity and deposited as dune-like accumulations of clay, silt, and fine sand along the  
14 slope of the east valley wall.

15 Aerial photography and USGS topographic maps showing the Project route in South  
16 Dakota are provided in Appendix 5.

17 **Q. Have you included a topographic map of the Project area?**

18 **A.** Yes, topographic mapping is provided in Appendix 5 of the Application.

19 **Q. What geological features are in the Project area?**

20 **A.** Surficial overburden deposits expected to be found at the trench depth across glaciated  
21 Eastern South Dakota are composed primarily of Quaternary age alluvium, eolian  
22 deposits, lacustrine sediments, moraine (till), and outwash. Beneath the surficial  
23 overburden, which can range in thickness from a thin veneer up to 1,000 feet thick,  
24 is lithic bedrock (Tomhave et. al. 2004). Lithic bedrock in the Project area  
25 consists primarily of Late Cretaceous and Early Proterozoic rocks. Bedrock  
26 units in glaciated Eastern South Dakota are known to outcrop along rivers and creeks  
27 where the glacial sediment overburden has been eroded away; however, no known  
28 bedrock outcrops were identified along the Project route. Geosyntec (2024) determined  
29 that approximately 0.9 mile of project pipeline crosses shallow bedrock defined as bedrock  
30 less than five feet below ground surface. The depth to bedrock is assumed to be deeper  
31 than five feet for the remainder of the Project. No unique geological features protected by  
32 federal, state, or local governments will be disturbed by the Project. Construction of the

1 Project will include surface disturbance along the ROW and at ancillary facilities. Impacts  
2 to topography will be relatively minor and short-term since the Project will restore surface  
3 contours and drainage patterns as closely as possible to pre-construction conditions. No  
4 significant operational impacts to geological resources are expected.

5 **Q. Are any economic deposits found within the project area?**

6 **A.** The pipeline does not cross any active, inactive, or permitted mining or oil and gas  
7 extraction operations. None of the route crosses historic mining areas. The pipeline ROW  
8 does not cross or is in proximity to existing oil and gas wells. However, SCS would still  
9 follow the 811 utility call procedures to determine if unmapped flow lines or pipelines are  
10 in the area. Construction of the Project may result in short-term and localized demand for  
11 sand and gravel, but these demands will not significantly affect the long-term availability  
12 of construction materials in the area. No significant operational impacts to economic  
13 deposits are expected.

14 **Q. What mitigation measures will the Project implement to avoid or minimize impacts  
15 to topographical and geographical features and economic mineral deposits, if any?**

16 **A.** Because the project will restore topographic conditions after construction, there are no  
17 mitigation measures required. The very few acres of surface facilities that impact the  
18 surface are minor compared to the acreage extent of the project area. No mitigation  
19 measures are required for economic mineral deposits since none are impacted by the  
20 Project.

21 **Q. Has the Project analyzed soil characteristics within the project area?**

22 **A.** Yes. Project Maps depicting the limits of the soil map units within the Project area as  
23 delineated by the NRCS are provided in Appendix 5B. A description of the soils crossed  
24 is provided in Appendix 12 and a discussion of the key soil features and the Project  
25 impacts and mitigation measures is provided in Section 5.1.4 of the Application.

26 **Q. Is there prime farmland located along the pipeline route?**

27 **A.** Approximately 26.7 percent of the lands crossed by the Project have soils identified as  
28 prime farmland. Impacts on these areas of prime farmland soils will be minimized by  
29 mitigation measures to be implemented according to the ECP and SD AIMP. During  
30 construction activities, topsoil on agricultural land, including prime farmland areas  
31 associated with the pipeline ROW, will be stripped to the maximum depth of 12 inches and

1 segregated from the subsoil. Unless the landowner or land management agency requests  
2 otherwise, topsoil will be stripped from over the pipeline trench and the adjacent subsoil  
3 storage area. Segregated topsoil will be returned following backfilling of the subsoil, re-  
4 establishment of pre-construction contours, ensuring preservation of topsoil within the  
5 construction area. Short-term impacts such as excavation and handling, and small  
6 isolated spills of fuels or lubricants may temporarily alter the capability of prime farmland  
7 following construction. Following the completion of construction, areas of prime farmland  
8 disturbed by the installation of the pipelines and temporary access roads will be allowed  
9 to revert to pre-construction uses; therefore, construction activities in these areas will not  
10 adversely impact prime farmland. Impacts from maintenance activities in these areas will  
11 be minor and short-term.

12 **Q. Has the Project analyzed the project area for hydric soils?**

13 **A.** Yes. Approximately 6.3% of the lands that would be disturbed during construction have  
14 soils rated as hydric soils and approximately 3.8% of lands crossed by the Project are  
15 hydric and have fine texture and poorly drained to very poorly drained soils making them  
16 prone to compaction.

17 **Q. How does the Project intend to mitigate impacts regarding hydric soils?**

18 **A.** Soil compaction and rutting can occur with the movement of heavy construction vehicles  
19 along the pipeline ROW and on temporary access roads during construction. Compaction  
20 can damage soil structure, reduce infiltration, and increase runoff and erosion. The degree  
21 of compaction will depend on the moisture content and texture of the soil at the time of  
22 construction. Compaction will be most severe when heavy equipment operates on moist  
23 to wet soils with fine textures. Detrimental compaction also can occur on soils of various  
24 textures and moisture contents if multiple passes are made by heavy equipment. If soils  
25 are moist or wet where trench-line only topsoil trenching has occurred, topsoil will likely  
26 adhere to tires and/or tracked vehicles and be carried away. Rutting occurs when the soil  
27 strength is not sufficient to support the applied load from vehicle traffic. Ruts that exceed  
28 topsoil depth can mix topsoil with subsoil, thereby reducing soil productivity. Rutting affects  
29 the surface hydrology of a site as well as the rooting environment. The process of rutting  
30 physically cuts plant roots and reduces the aeration and infiltration of the soil, thereby  
31 degrading the rooting environment. Rutting also disrupts natural surface water hydrology  
32 by damming surface water flows, creating increased soil saturation upgradient from ruts,  
33 or by diverting and concentrating water flows creating accelerated erosion. As outlined in

1 the Project's ECP, compaction and rutting impacts will be mitigated in these  
2 areas using timber mats and special crossing techniques. Contractors will restrict certain  
3 construction activities and work in cultivated agricultural areas in excessively wet soil  
4 conditions to minimize rutting and soil compaction. Work may be suspended during wet  
5 weather when there is potential for material mixing soil horizons or the potential for  
6 excessive compaction. To minimize potential impact to soil resources, soil will be  
7 prepared after final grading to facilitate revegetation in undeveloped areas. This could  
8 include tilling compacted soil or other measures depending on the extent and severity of  
9 compaction.

10 **Q. Are there any restrictive soil layers or shallow bedrock found along the pipeline**  
11 **route?**

12 **A.** Approximately 0.9-mile of the proposed pipelines are underlain by bedrock that is less  
13 than five feet below ground surface (Geosyntec, 2024). Approximately 1.8 mile of lateral  
14 SDL-514 (in the Red River Lowlands subdivision) is underlain by granite bedrock;  
15 however, the granite bedrock is unlikely to be encountered within trench depth.

16 **Q. Are there any saline and sodic soils found along the Project route and what**  
17 **mitigation techniques will the Project utilize to minimize impacts, if necessary?**

18 **A.** Yes. A review of the 2024 SSURGO database indicates that approximately 174.4 acres  
19 (1.9%) of soils crossed by the Project are considered saline and approximately 111.7  
20 acres (1.2%) are considered sodic both occurring within the top six feet. In areas with  
21 the potential to find saline or sodic soils at trench depth, testing will be performed to  
22 identify the exact locations of the presence and extent of the soils. Triple lift soil  
23 excavation will be used to separate the topsoil from the subsoil and any layer of  
24 saline/sodic soils. After construction, the soil layers will be put back in the same order to  
25 prevent mixing and reduce the likelihood of reducing reclamation of the vegetation.

26 **Q. Please describe any measures which the project is taking with regard to erosion.**

27 **A.** The overall impact from soil erosion is anticipated to be minor because only 32.3 acres of  
28 the pipeline ROW have soils identified as susceptible to wind erosion (<1%)  
29 and 3,563.2 acres have soils identified as susceptible to water erosion (38.4%).  
30 The contractors will use erosion and sedimentation control devices to reduce impacts  
31 from erosion following the best management practices outlined in the ECP (Appendix 4).  
32 SCS will monitor the effectiveness of erosion mitigation measures to maximize

1 revegetation efforts following construction. Operations of permanent facilities will likely  
2 result in permanently altered soils or loss of soil resources within the specific  
3 facility footprint, accounting for less than one percent of the total acreage of the Project.  
4 Impacts from maintenance activities will be minor because disturbances will be isolated,  
5 short-term, and infrequent and include clearing the permanent pipeline ROW of vegetation  
6 (in areas outside wetlands, waterbodies, and agricultural land) and identifying corrosion  
7 through regular inspections. SCS will routinely monitor the pipeline ROW to identify areas  
8 where erosion occurs.

9 **Q. How will the Project revegetate the construction areas?**

10 **A.** More than 83% of the Project impacts are in agricultural production (crop, hayfield,  
11 improved pasture). All of this land will be allowed to revert to agricultural production in the  
12 year following construction. There will be no long-term impacts to the use of the land for  
13 agricultural purposes. What is not in agricultural production is barren, open water, or  
14 herbaceous vegetation, so impacts will be short term and herbaceous vegetation allowed  
15 to regrow across the ROW. Approximately 15.83 acres are classified as wooded and  
16 scrub-shrub, of which approximately 15.68 acres are a temporary impact and 0.15 acres  
17 are a permanent impact. Trees will be removed and either provided to the landowner for  
18 their use or sale or hauled and disposed of in an appropriate manner. The permanent  
19 ROW will be kept free of trees within 15 feet of either side of the pipeline to ensure integrity  
20 and ease of maintenance and aerial patrols. The ECP (Appendix 4) will be followed for  
21 soil handling, restoration, seeding and stabilization measures to allow vegetation in non-  
22 agricultural areas to regrow to previous conditions following construction.

23 **Q. Has the Project examined the impacts to hydrology from construction?**

24 **A.** Yes, the Project has considered impacts regarding surface water, ground water, and  
25 other water sources for construction and operation of the pipeline. Section 5.2 provides  
26 additional detailed assessment of the hydrologic features impacted by the route and the  
27 measures that will be undertaken to protect those resources. The measures outlined in  
28 the ECP (Appendix 4) describe the minimization of impacts that will occur with the best  
29 management practices described in that plan.

30 SCS has obtained information on springs from the U.S. Geological Survey (USGS), but  
31 the information is only a reflection of what is reported as opposed to a concerted effort to  
32 survey for the feature. A digital map of the surficial aquifer was also obtained from the  
33 South Dakota geological survey. SCS has prepared a Water Resources Map Book

1 included as Appendix 5 of the Application that includes the location of permitted water  
2 wells, and surface hydrology features (perennial, intermittent, and ephemeral drainages)  
3 as mapped in the field by SCS or via a desktop review for those parcels which survey  
4 access was denied. The U.S. Army Corps of Engineers (USACE) will be reviewing all  
5 drainage features as part of their review of the Nationwide Permit 58 permit application  
6 package.

7 **Q. How does the Project intend to mitigate impacts to surface water from construction**  
8 **and operation?**

9 **A.** Potential impacts to surface water drainage from Project construction could include  
10 altering surface contours which could alter surface water runoff paths; creating  
11 compaction or rutting, altering the volume and rate of surface water runoff; damaging  
12 existing drainage channels such as agricultural drainage tiles and culverts which could  
13 diminish surface drainage capabilities and result in ponding or flooding; and altering  
14 stream banks and beds which could encourage sedimentation or change the stream's  
15 scour pattern resulting in changes to runoff and discharge.

16 The following measures will be implemented during construction to reduce impacts to  
17 surface hydrology:

- 18 • Identify drain tile systems within the pipeline ROW prior to construction to avoid  
19 during construction. If drain tile systems are damaged during construction, SCS  
20 will implement repairs.
- 21 • Identify waterbodies and install erosion and sediment control devices for those  
22 with potential to receive stormwater discharge during construction. Install ECDs  
23 per the ECP to prevent erosion entering waterbodies.
- 24 • Conduct civil surveys prior to construction to document terrace elevations and  
25 contours. Preserve terrace drainage patterns and reduce terrace erosion during  
26 construction by installing ECDs as detailed in the ECP. Return all terraces to  
27 preconstruction conditions.
- 28 • Construct permanent slope breakers as detailed in the ECP across the ROW  
29 (except in actively tilled agricultural fields) where necessary to limit erosion. Slope  
30 breakers will divert surface runoff to adjacent stable vegetated areas or to energy-  
31 dissipating devices.

32 The pipeline will be constructed under river channels with potential for lateral scour.  
33 Engineering design will ensure that the pipeline will be buried at an adequate depth under

1 channels, adjacent floodplains, and flood protection levees to avoid pipe exposure  
2 caused by channel degradation and lateral scour. Determination of the pipeline burial  
3 depth will be based on site-specific channel and hydrologic investigations were deemed  
4 necessary.

5 Mitigation measures used at stream crossings include using the HDD crossing and bore  
6 crossing methods. Descriptions of HDD and other waterbody crossing methodologies are  
7 provided in the ECP. Other crossing methods, such as wet open cut, which will involve  
8 disturbance of stream banks and channel bottoms will be mitigated by using measures  
9 detailed in the ECP which include:

- 10 • Restoring banks to preconstruction contours unless too steep for restoration, in  
11 which case the banks will be restored to a stable angle of repose. Restoration  
12 includes grading, stabilization, and possibly revetments. These types of  
13 restorations will include bioengineering concepts which encourage the natural  
14 restoration of streambanks.
- 15 • Restoring stream bottoms to pre-construction conditions leaving no impediments  
16 to normal water flow.
- 17 • Restoring wetland edges to the preconstruction contours to maintain the  
18 hydrology of the wetland and stabilizing the wetland by installing permanent  
19 erosion control devices during final clean up.
- 20 • Installing trench breakers at wetland boundaries where the pipeline trench may  
21 cause a waterbody to drain.

22 After the installation of the pipeline, the disturbed ROW will be restored to its pre-  
23 construction elevations to avoid changes to the original surface drainage patterns.

24 SWPPPs will be prepared for the pipelines and all facilities (e.g., pump stations) in the  
25 course of obtaining General Stormwater Construction Permits and will identify how  
26 surface runoff will be managed.

27 More information can be found in the Application in Section 5.2.1.1 and Appendix 4.

28 **Q. Will the pipeline interfere with drainage patterns along the route?**

29 **A.** No, since the pipeline will be buried beneath stream channels or installed with a trenchless  
30 method, there will be no permanent impact to stream structure or the ability of the stream  
31 to maintain pre-construction flow characteristics. Wetland and waterbody crossing  
32 methodologies are provided in Table 10 of the Application and the Wetland and Waterbody

1 Crossing tables (Appendix 14) of the Application.

2 **Q. Will the Project use surface water and/or ground water in construction?**

3 **A.** SCS will require the temporary use of surface water or water from municipalities to  
4 hydrostatically test the pipelines before operation. Water is used as a test medium by filling  
5 the welded pipeline segment with water and bringing the water to a pressure greater than  
6 the operating pressure of the pipeline. This kind of test ensures operational integrity before  
7 the pipeline is put into service. The water is withdrawn from existing surface or municipal  
8 resources and after use, returned to the source (except municipal supplies). There are no  
9 additives or chemicals added to the water. During hydrostatic testing, the water is used  
10 only to put pressure on the pipeline to test its integrity. Water will also be used for dust  
11 control along the construction ROW and gravel or dirt access roads. Water use for each  
12 source is dictated by the availability from municipal or surface sources near the Project.  
13 Authorizations and/or permits will be acquired for water use for dust control. Water will be  
14 required for HDDs. Water for the HDD operation is used to mix drilling mud (e.g., bentonite  
15 clay) for drilling operation lubrication, hole stability and to remove drill cuttings. The Project  
16 will apply for the necessary permits required for water usage from the South Dakota  
17 Department of Agriculture and Natural Resources if surface water resources are used.

18 **Q. Will the project use surface water and/or ground water in operation?**

19 **A.** There will be no operational use of surface or groundwater for the Project.

20 **Q. Are there impacts to aquifers expected along the pipeline route?**

21 **A.** No, the pipelines will be buried a nominal depth with approximately four feet of cover. This  
22 would put the trench depth at 7-10 feet depending on the location and whether any  
23 crossings are necessary. The soil removed from the trench will be returned in the order it  
24 was removed, with topsoil last. This will ensure that recharge properties will not be  
25 impacted and the impacts to aquifers temporary and minor. Pipeline installed by the HDD  
26 method will be 25 feet or greater below the bottom of the feature crossed (highway, river  
27 bottom, etc.). In this case, the use of naturally occurring drilling mud (e.g., bentonite clay)  
28 will seal the hole drilled for the pipeline. This will ensure that the pipeline is not a conduit  
29 between aquifer zones or to introduce surface flows into the HDD hole. During operations,  
30 there will be no impacts to aquifers from operations. The pipeline is largely installed in the  
31 shallow confines of surficial aquifers and in the event of a release, the CO<sub>2</sub> would vent to  
32 the atmosphere since it is under pressure. These events are unlikely and would be



1 infrequent to result in no impacts on aquifers from operations.

2 **Q. What measures will the Project take to avoid, minimize, or mitigate potential**  
3 **impacts to hydrological resources?**

4 **A.** The Project has designed the route to avoid or minimize impacts to hydrologic resources.  
5 The Project has conducted, and is continuing to conduct, wetland and waterbody  
6 delineations. That data has been and will continue to be used to inform routing and design  
7 to avoid or minimize impacts to the extent practicable. Impacts to some waterbodies will  
8 be avoided with the use of HDD or bore crossing methods. The Project has been designed  
9 to limit permanent wetland impacts. The construction ROW will result in the permanent  
10 conversion of approximately 0.9 acres of palustrine scrub-shrub (PSS) wetlands and 0.7  
11 acres of palustrine forested (PFO) wetlands to palustrine emergent (PEM) wetlands in the  
12 permanent ROW. Herbaceous vegetation in PEM wetlands where temporary impacts  
13 occur is expected to re-establish to preconstruction conditions within one to five years  
14 following the completion of reclamation, resulting in a short-term loss of vegetation and  
15 available habitat for some wildlife species. Additionally, SCS has avoided siting  
16 aboveground facilities in delineated wetlands. Impacts to wetlands and Waters of the U.S.  
17 are anticipated to be minor and would be authorized under the USACE Nationwide Permit  
18 58. SCS will implement numerous measures to avoid or minimize impacts to hydrologic  
19 resources, including but not limited to working with landowners to identify and repair drain  
20 tile systems within the ROW, implementing appropriate erosion and sediment control  
21 BMPs, and utilizing appropriate crossing methods. The ECP and Application Sections 5.2.1  
22 and 5.4.1 also describes measures SCS will implement to restore wetlands and  
23 waterbodies impacted by construction of the Project, such as grading, stabilization, and  
24 revegetation.

25 **Q. What water quality permits are expected for the project?**

26 **A.** SCS will be required to obtain a general permit for stormwater discharge from the  
27 construction footprint, a general permit for the discharge of hydrotest water, a general  
28 permit for trench dewatering, and if necessary, permits to appropriate surface water for  
29 construction purposes.

30 **Q. Please describe the terrestrial setting of the project.**

31 **A.** A majority of the Project is located in agricultural land uses. This includes cropland,  
32 hayfields and grasslands (83%). The setting therefore is mainly of agricultural land use

1 and vegetative cover, with row crops (mainly corn and soybean) interspersed with  
2 hayfields and grasslands that are overseeded with legumes for grazing. Sporadically  
3 located along the Project are waterbodies (streams and rivers), barren areas, small tree  
4 lines or wind breaks, and transportation or utility corridors. General descriptions of these  
5 ecoregions and the proportion of the Project that will be within the ecoregion can be found  
6 in Table 14 of the Application.

7 **Q. What are the vegetation community types found along the project route?**

8 **A.** The majority of the pipelines in South Dakota will impact agricultural land uses, mainly row  
9 crop (70.2%), and hayfields and grasslands utilized for pastureland (12.9%). Areas used  
10 for the production of annual crops are usually planted in wheat, corn, and/or soybeans.  
11 Dominant vegetation observed in hayfields within the Project area consist of oat (*Avena*  
12 *sativa*), blue grama (*Bouteloua gracilis*), smooth brome (*Bromus inermis*), redroot  
13 (*Ceanothus americanus*), orchardgrass (*Dactylis glomerata*), creeping wildrye (*Elymus*  
14 *repens*), fox-tail barley (*Hordeum jubatum*), alfalfa (*Medicago sativa*), reed canarygrass  
15 (*Phalaris arundinacea*), Kentucky bluegrass (*Poa pratensis*), tall false ryegrass  
16 (*Schedeonorus arundinaceus*), and common dandelion (*Taraxacum*  
17 *officinale*). Grasslands used as pasture are areas dominated by graminoid or herbaceous  
18 vegetation. There are very few wetlands (4.8%) found along the pipeline routes, mostly  
19 herbaceous wetlands, and the Project avoids residential areas. Sections 5.3.1 and 5.5.1  
20 of the Application, along with the aerial imagery provided in Appendix 5, provides an  
21 overview of the land use/vegetative communities found along the Project.

22 **Q. Please briefly describe the impacts to vegetation and any mitigation measures**  
23 **which the project intends to adopt.**

24 **A.** The route traverses agriculture, grassland/rangeland, palustrine emergent/scrub-shrub  
25 wetlands, previously disturbed, riverine/open water, and upland forest. The dominant  
26 vegetation types traversed are agricultural. In agricultural lands, construction will result in  
27 relatively small, temporary loss of crops during construction. SCS will repair or restore any  
28 drain tiles, fences, and land productivity that are temporarily disturbed during construction.  
29 Grasslands/rangelands will be temporarily impacted during construction. SCS will adhere  
30 to their ECP and SD AIMP to restore these areas and allow vegetation to recover in the  
31 ROW. There will be no permanent impact to, nor maintenance of, the vegetation along the  
32 route in this community type except shrubs will not be allowed to grow over 15 feet high  
33 within 15 feet of either side of the centerline. Temporary impacts to emergent and scrub-

1 shrub wetland vegetation will occur during construction. To mitigate the potential impacts,  
2 SCS will implement specific procedures as outlined in the. Pipeline construction through  
3 wetlands must comply, at a minimum, with USACE Section 404 permit conditions.  
4 Construction of the pipeline will disturb approximately 15.8 acres of forested and  
5 scrub/shrub land in South Dakota. Construction of the pipeline will necessitate clearing of  
6 the ROW and permanent conversion of the affected wooded areas for the lifetime of the  
7 project. During operations, the majority of the ROW will be allowed to revert to pre-  
8 construction conditions. Woody vegetation in forested areas will be removed periodically  
9 above the pipeline (approximately 15 feet on each side of the centerline) to maintain  
10 visibility of the area above the pipeline for aerial pipeline observation and to permit access  
11 to all areas along the pipeline in the event of an emergency. Routine maintenance  
12 activities would not result in long-term alterations of vegetation since disturbances would  
13 be isolated, short-term, and infrequent.

14 SCS will implement procedures detailed within the South Dakota Noxious Weed  
15 Management Plan specific to the Project to prevent the spread of noxious weeds. The  
16 Contractor will clean the tracks, tires, and blades of equipment by water or compressed  
17 air to remove excess soil prior to moving the equipment out of weed or soil-borne pest  
18 infested areas. The Contractor may also utilize cleaning stations to remove vegetative and  
19 soil materials using water at a high pressure in lieu of compressed air. The duration  
20 between final grading and permanent seeding will be minimized to reduce the potential  
21 growth of nuisance species establishing. Certified weed-free hay or straw will be used for  
22 mulch and sediment barriers. Where required by weed control boards for specific species  
23 that require treatment ahead of construction, the topsoil will be stripped from the full width  
24 of the ROW where isolated weed populations exist and will be stored separately from other  
25 topsoil and subsoil. These locations will be identified and marked prior to construction  
26 activities by an Environmental Inspector (EI). Alternatively, approved herbicides may be  
27 used to prevent the growth and spread of weeds. Only non-residual herbicides will be  
28 used.

29 SCS will implement proposed measures within SD AIMP to minimize impacts to and restore  
30 agricultural lands during and after construction. Mitigation measures within the SD AIMP include  
31 procedures for segregating and replacing topsoil, trench backfilling, relieving areas compacted by  
32 heavy equipment, removing surface rock fragments, and implementing water and wind erosion  
33 control practices such as installation of seeding nets. In addition, SCS will work closely with  
34 landowners and soil conservation agencies to identify and implement recommended soil

1 conservation practices in specific areas where they are needed. Damaged irrigation and tile  
2 drainage systems will be repaired in accordance with the SD AIMP.

3 **Q. Has the project considered impacts to grassland and wetland easements?**

4 **A.** Yes. The Project has adjusted the route to avoid U.S. Fish and Wildlife (USFWS)  
5 grassland and wetland easements. Construction of the Project will not result in any surface  
6 disturbance within the grassland or wetland easements. SCS has committed to utilizing  
7 HDD or bore crossing of all of these easements if the Project route crosses them.

8 **Q. Has the Project analyzed whether noxious weeds are present along the Project  
9 and developed mitigation procedures for them?**

10 **A.** Yes. Surveys have not been conducted in the Project footprint, but the Project has  
11 received state lists of noxious weeds as well as lists of relevant weeds from each County  
12 weed board and will complete pre-construction surveys for those species prior to ground  
13 disturbance.

14 In addition, the Project will implement procedures to prevent the spread of noxious weeds.  
15 The Project has developed a noxious weeds management plan, which can be found in  
16 Appendix 17. In addition, the ECP also addresses noxious weeds. The Contractor will  
17 clean the tracks, tires, and blades of equipment by water or compressed air to remove  
18 excess soil prior to moving the equipment out of weed or soil-borne pest infested areas.  
19 The duration between final grading and permanent seeding will be minimized to reduce  
20 the potential growth of nuisance species establishing. Certified weed-free hay or straw will  
21 be used for mulch and sediment barriers. Where required by weed control boards for  
22 specific species that require treatment ahead of construction, the topsoil will be stripped  
23 from the full width of the ROW where isolated weed populations exist and will be stored  
24 separately from other topsoil and subsoil. These locations will be identified and marked  
25 prior to construction activities by an EI. Alternatively, approved herbicides may be used to  
26 prevent the growth and spread of weeds. Only non-residual herbicides will be used.

27 **Q. What kinds of wildlife are along the Project?**

28 **A.** Various big game and small game species are found along the Project. These include  
29 deer, pronghorn antelope, wild turkey, prairie grouse, ringneck pheasant, and waterfowl.  
30 In addition, threatened and endangered species could potentially occur in the counties,  
31 and non-game species are found along the route.

1 **Q. What the expected impacts to wildlife?**

2 **A.** Much of the habitat crossed by the route consists of agriculture or grassland/rangeland.  
3 Impacts in these habitats will be short-term and represent a small fraction of the total  
4 available habitat in the Project area. Consequently, the effects of long-term habitat loss  
5 on native wildlife populations will be minor. Since the Project involves very little forest or  
6 tree clearing, the potential for disturbance to raptors is minor. Impacts from increased  
7 noise and human presence during construction also will be temporary and minor. Big and  
8 small game wildlife will experience temporary impacts as they move away from the  
9 construction ROW. After construction, the agricultural land will be restored to the previous  
10 vegetative cover and land use. Very little forested area will be converted that would  
11 displace species using this habitat. Since the amount of habitat temporarily affected during  
12 construction represents a small fraction of the total available habitat, and species are  
13 mobile, impacts to game species will be minimal. Noise from operations (pump stations)  
14 will also be minor since there are so few and are sited mostly in agricultural land and  
15 housed in acoustic buildings.

16 **Q. What mitigation measures will be adopted to reduce expected impacts to wildlife?**

17 **A.** The Project team has conducted preliminary meetings with federal and state agencies and  
18 incorporated their recommended conservation measures to mitigate impacts to listed  
19 species and wildlife in general. These measures are outlined in the Threatened and  
20 Endangered Species Report (Appendix 15 to the Application) and Section 5.3.2 and 5.3.3  
21 of the Application.

22 **Q. What impacts and mitigation measures if any, can be anticipated for sensitive,  
23 threatened and endangered species?**

24 **A.** SCS completed general habitat surveys for listed species in the summer/fall of 2021,  
25 2022, 2023, and 2024. The results of those species surveys are provided in Appendix 15  
26 and discussed in Section 5.3.3 of the Application. A Biological Assessment (BA) will be  
27 prepared and filed with the USFWS and USACE in Q1 2025. Those agencies will finalize  
28 that document and conclude the Endangered Species Act consultation in the process.  
29 Reports of state listed species surveys will be provided to SD Game, Fish, and Parks (SD  
30 GFP) after the conclusion of the 2025 survey season for their review and concurrence.

31 A summary of the results through 2024 are provided below:

32 

- In July 2022, 2023, and 2024 experienced botanists surveyed approximately 428

1 cumulative acres for western prairie fringed orchid and suitable habitat. No  
2 western prairie fringed orchid individuals or populations were observed in any of  
3 the areas.

- 4 • Most of the surveyed habitat along the Project route in South Dakota is rated as  
5 either Unsuitable or Poor for western prairie fringed orchid. This lack of suitable  
6 habitat is consistent with the general loss of habitat for western prairie fringed  
7 orchid due primarily to cultivation and the dominance of non-native vegetation that  
8 has replaced high-quality native prairie. Survey will be completed in July 2025 on  
9 approximately 67 acres of potentially suitable habitat in Codington, Grant, Lake,  
10 and Lincoln counties if access is available. Additional details can be found in  
11 Appendix 15 of the Application.
- 12 • SCS has completed survey for Dakota skipper habitat and individuals along the  
13 Project in South Dakota in 2022, 2023, and 2024. No Dakota skipper were  
14 observed in any year. Most of the sites surveyed in 2022 and 2023 are no longer  
15 on the current route. Two general areas of potentially suitable habitat have been  
16 identified along the route as currently configured; it is unknown if suitable habitat  
17 is actually present at these sites. Survey is scheduled for 2025 if access is  
18 available. If suitable habitat is present, then occupancy surveys will be completed  
19 consistently with the USFWS's protocol. Additional details can be found in  
20 Appendix 15 of the Application.
- 21 • Sixteen streams or rivers in South Dakota that support Topeka shiner would be  
22 crossed by the Project at 35 crossing locations since, in some cases, a single  
23 stream or river would be crossed in more than one location. Thirty-two stream  
24 crossings would be crossed using trenchless methods to avoid impacts to either  
25 species consistent with mitigation guidance received from the USFWS and  
26 SDGFP. Four streams do not support habitat at the crossing location and include:  
27 Middle Pearl Creek (SDM-104), Redstone Creek (north crossing, SDT-208),  
28 South Fork Pearl Creek (SDM-104), and West Fork Vermillion River (SDM-104).  
29 These streams may be crossed using standard waterbody construction  
30 procedures.
- 31 • The Project crosses four streams that currently support, or have historically  
32 supported, northern redbelly dace. One stream, the West Fork Vermillion River,  
33 would be crossed 3 times by different laterals. West Fork Vermillion River (SDM-  
34 104) does not support habitat at the crossing location and may be crossed using  
35 standard waterbody construction procedures.

- 1           • Surveys for lined snake were completed in 2022 on one accessible parcel; no  
2           lined snakes were observed, and suitable habitat was not present. The only area  
3           of potentially suitable habitat on the current route occurs at the Big Sioux River in  
4           Lincoln County; however, the likelihood that this area is occupied is low due to  
5           high tree cover. Further, this site will not be affected since the Big Sioux River will  
6           be crossed using HDD technology which will avoid this site.
- 7           • The proposed Project would traverse areas in South Dakota with various types of  
8           habitat for northern long-eared bat (NLEB). The desktop habitat assessment for  
9           NLEB is intended to assess the quality and type of habitat that a wooded area  
10          within the Project environmental survey area (ESA) and footprint in South Dakota  
11          could provide for NLEB. The Project in South Dakota occurs in a highly  
12          fragmented landscape with limited wooded areas. Most of the wooded areas that  
13          do occur within the Project ESA are comprised of small, isolated stands  
14          surrounded by large areas of cultivation; it is unlikely that these types of isolated  
15          wooded areas provide habitat for NLEB. Almost all wooded areas with Suitable  
16          Habitat for NLEB are located along creeks, rivers, wooded valleys, and associated  
17          tributaries; however, it is unknown if NLEB are actually present at these sites and  
18          the USFWS notes that based on the best available science, most Suitable Habitat  
19          is now expected to be unoccupied.
- 20          • Habitat for monarch butterflies is widely scattered across the Project in South  
21          Dakota based on the widely scattered milkweed observations that were recorded  
22          during wetland delineations and survey for Dakota skipper. Although milkweed  
23          occurs at several sites on the Project, only 3 monarchs have been observed in  
24          South Dakota over 3 years of survey.

25          Though suitable habitat for listed species is limited in the Project footprint, the SCS will  
26          implement mitigation measures to further reduce or avoid impacts. These measures  
27          include the following:

28          Forested areas:

- 29          • SCS will clear trees in suitable habitat during the state-specific inactive season  
30          dates for NLEB (South Dakota: October 1 – May 15).
- 31          • SCS will not remove 10 acres in any wooded stand or within a collection of stands  
32          that are within 1,000 feet of each other.
- 33          • No wooded area will be separated by more than 1,000 feet due to tree removal.

- 1                   • SCS will not install permanent artificial lighting in suitable habitat.

2           Native Prairie:

- 3                   • Suitable, commercially available native grasses and forbs will be seeded in areas  
4                   of native prairie if acceptable to the landowner.
- 5                   • Fugitive dust abatement measures will be utilized to minimize disturbing adjacent  
6                   habitats.
- 7                   • Restrict the use of insecticides during construction or operation within verified  
8                   habitats.
- 9                   • During construction chemicals (e.g., herbicides) will not be used during the  
10                  Dakota skipper adult flight period to avoid injurious impacts.

11           Waterbodies:

- 12                  • All rivers and major waterbodies will be crossed via HDD. No dredging or other  
13                  impacts will occur to major river systems.
- 14                  • Trenchless crossing methods (i.e., HDD or bore) and no in-stream work between  
15                  May 15 and July 31 at all streams identified by agencies as supporting Topeka  
16                  shiner or northern redbelly dace.
- 17                  • All temporarily impacted wetlands will be returned to pre-construction contours  
18                  and allowed to revegetate naturally upon completion of construction.

19           Whooping Crane:

- 20                  • Contractors performing work will be educated to identify a whooping crane and  
21                  be advised that if a crane appears within 1,000 feet of construction activities, all  
22                  work will cease until the crane(s) move outside that 1,000-foot buffer area or if  
23                  USFWS provides relief based upon site-specific circumstances. SCS's  
24                  environmental inspectors will coordinate with the USFWS on sightings during  
25                  construction as well as data the Service may have for the area.
- 26                  • During the migratory season, if equipment over 15 feet high is to be used for  
27                  Project work, the equipment will be flagged or marked to increase visibility to  
28                  whooping cranes and lessen the risk of collisions.
- 29                  • During nighttime hours and periods of low visibility all construction equipment  
30                  containing components that could reach 15 feet (i.e., track hoe boom) would be  
31                  lowered to prevent any potential interference with whooping crane individuals,  
32                  should they be traveling at lower altitudes in the vicinity of the Project area.



1 **Q. Approximately how many waterbody crossings have been identified?**

2 **A.** The Project footprint lies within five South Dakota River basins. Construction of the  
3 Project will involve 69 crossings of named waterbodies within these basins, including 4  
4 ephemeral stream crossings, 16 intermittent stream crossings, 43 perennial stream  
5 crossings, and 4 lake crossings, and 1 pond crossing. Project construction will involve  
6 258 additional crossing of other types of waterbodies including small ephemeral  
7 unnamed streams, named streams with no defined channel, roadside and field ditches,  
8 prairie potholes, and man-made ponds. A listing of all waterbody crossings is provided  
9 in Appendix 14. Additional information on the impact of these crossings is provided  
10 in Sections 5.2 Hydrology and 5.6 Water Quality and Uses. Typical drawings of  
11 waterbody crossings are found in Appendix B of the ECP.

12 **Q. What impacts to aquatic ecosystems are expected and what mitigation measures**  
13 **will be implemented?**

14 **A.** Potential impacts to surface water drainage from Project construction could result from  
15 such things as altering the contours of the ground thereby altering surface water runoff  
16 paths, changing the consistency and porosity of the surface which can alter the  
17 amount and rate of surface water runoff, blocking existing drainage channels such as  
18 agricultural drainage tiles and culverts which can lower surface drainage capabilities and  
19 result in ponding or flooding; or alteration of stream banks and bottoms which can cause  
20 the stream to widen, meander, or infill, resulting in changes to runoff and  
21 discharge. Construction of the Project will have only minor and temporary impacts on  
22 surface drainage. BMPs outlined in the ECP will be implemented to ensure that any  
23 impacts on surface drainage and hydrology are minor.

24 Most named waterbodies (31) will be crossed using HDD or bore (21) technologies. These  
25 methods do not require in-water work, avoiding disturbance of waterbody banks or  
26 channels and preventing sediment suspension. Descriptions of HDD and other waterbody  
27 crossing methods are provided in Section 2.2 and Appendix 4 of the application. Since  
28 HDD and bores avoid direct contact with the waterbody, channel bed, or banks, no  
29 significant impacts to hydrology, including from aquatic invasives, are expected at these  
30 crossings.

31 Restoration includes grading, stabilization, and revetment BMPs. These BMPs embrace  
32 bioengineering concepts, which encourage the restoration of natural streambanks. After  
33 the installation of the pipeline, the disturbed ROW will be backfilled and restored to its pre-

1 construction grade thus avoiding any change to the pre-existing surface water drainage  
2 patterns. The pipeline will be constructed under river channels with potential for lateral  
3 scour. Engineering design will ensure that the pipeline will be buried at an adequate depth  
4 under channels, adjacent floodplains, and flood protection levees to avoid pipe exposure  
5 caused by channel degradation and lateral scour. Determination of the pipeline burial  
6 depth will be based on site-specific channel and hydrologic investigations were deemed  
7 necessary.

8 Segments of the Big Sioux River, James River, Webber Gulch, and Whetstone River  
9 crossed by the Project have been designated by the State with the beneficial use of  
10 “warmwater semipermanent fish life propagation water.” The Willow Creek, Moccasin  
11 Creek, East Fork Vermillion River, and West Fork Vermillion River stream segments and  
12 Lake Henry crossed by the Project have been designated the beneficial use value of  
13 warmwater marginal fish life propagation. Only two waterbodies, Brant Lake and the North  
14 Fork Yellow Bank River, crossed by the Project have a designation with warmwater  
15 permanent fish life propagation. The North Fork Yellow Bank River and Brant Lake will be  
16 crossed via HDD and impacts will be avoided as further discussed in Section 5.4.2. All  
17 other waterbody crossings are considered to be low quality fishery waters. Warmwater  
18 fish species are generally more resistant to increased sediments than coldwater species.  
19 Timing construction to avoid spawning periods further minimizes impacts. The Fisheries  
20 in these prairie streams are adapted to frequent sediment loads from spring melt and  
21 agricultural runoff. The Federal Energy Regulatory Commission’s (FERC’s) procedures  
22 for waterbody and wetland crossings, followed in the ECP, help minimize construction  
23 impacts and support adequate resource recovery.

24 Timing the construction to avoid periods when aquatic fauna is spawning is another way  
25 to minimize impacts. The FERC also provides a comprehensive set of procedures to follow  
26 for waterbody and wetland crossings and the ECP follows these best practices.

27 SDGFP reports infestations with aquatic invasive species in three waterbodies within the  
28 Project footprint. These waterbodies include segments of the Big Sioux River (Lincoln  
29 County), East Fork Vermillion River (Turner County), and James River (Beadle, Brown,  
30 Sanborn, and Spink counties). None of the rivers/streams identified with invasive or exotic  
31 species will be crossed with an open cut construction method and will therefore avoid the  
32 possibility of spreading those species. Any water withdrawals from those waterbodies will  
33 utilize screens to prevent the uptake of any invasive species and the water will be returned  
34 to the source, avoiding spreading the invasive species to another waterbody.

1 Construction of the Project will have only minor and temporary impacts on aquatic habitat  
2 and fisheries. The primary impact will be the re-suspension of sediments in the water  
3 column which will temporarily reduce water quality and could result in the destruction of  
4 sessile benthic organisms during excavation or mortalities to benthic organisms due to re-  
5 deposition of the suspended sediments most of which are silty clay. Fish eggs and larvae  
6 could be negatively affected in a similar manner. Motile adult fish will be displaced from  
7 the work area as they will move away from areas of increased turbidity. Displacement  
8 could briefly interfere with spawning or feeding and reduce fishing opportunities or  
9 success. However, these impacts will be temporary as the crossings are small and will be  
10 conducted rapidly - in a matter of a couple of days. Impacts such as increased suspended  
11 sediments will dissipate within hours of completion of the crossing. Twenty (20) of the 68  
12 named stream crossings will occur in stream segments with ephemeral or intermediate  
13 flow regimes, which indicates significant spawning does not take place in these locations.

14 **Q. What wetland vegetation types are found along the pipeline route?**

15 **A.** Wetlands within the Project area were classified into three categories: PEM wetlands,  
16 PSS wetlands, and PFO wetlands (Cowardin et al. 1979). Wetlands within the Project area  
17 in South Dakota are limited to approximately 42.8 miles of PEM wetlands, 0.11 mile of  
18 PFO wetlands, and 0.13 mile of PSS wetlands. PEM wetlands generally are dominated by  
19 fowl blue grass (*Poa palustris*) and fox tail (*Hordeum jubatum*) in areas that typically  
20 contain water for several weeks after spring snowmelt. Shallow-marsh vegetation such as  
21 spikerush (*Eleocharis palustris*) and wheat sedge (*Carex antherodes*) dominate areas  
22 where water typically persists for a few months each spring, and deep-marsh vegetation  
23 like cattails (*Typha latifolia*), and hardstem bulrush (*Scirpus acutus*) occupies areas where  
24 water persists throughout the year (USDA NRCS 2008b; USEPA 2008a; USGS  
25 2006b). Dominant woody vegetation in PSS wetlands in the Project survey area consists  
26 of white willow (*Salix alba*), narrowleaf willow (*S. Interior*), and common lilac  
27 (*Syringa vulgaris*). The dominant woody vegetation in PFO wetlands in the Project survey  
28 area consists of eastern cottonwood (*Populus deltoides*), crack willow (*S. fragilis*), white  
29 willow, peachleaf willow (*S. amygdaloides*), green ash (*Fraxinus*  
30 *pennsylvanica*), and common buckthorn (*Rhamnus cathartica*). The report provided  
31 in Appendix 16 provides complete lists of dominant species in the wetlands as well as  
32 descriptions of soils and hydrology.

33 **Q. What impacts to wetlands are expected and how did SCS Carbon Transport LLC**  
34 **work to minimize impacts?**

1 **A.** Impacts on wetland vegetation will be greatest during and immediately following  
2 construction. The USACE has determined pipeline crossings of wetlands do not result in  
3 long term or significant impacts in the reissuance of the Nationwide Permit program,  
4 specifically Nationwide Permit Number 58 (NWP 58). Woody vegetation in PFO wetlands  
5 will be removed during construction (approximately 0.1 acre) and will regrow within the  
6 temporary workspace over many years. Construction will result in the permanent  
7 conversion of approximately 0.7 acres of PFO wetlands and 0.9 acres of PSS wetlands to  
8 PEM wetlands in the permanent ROW (approximately 0.017% of Project impact acreage),  
9 which would result in loss of the incremental portion of functional value associated with  
10 loss of tree cover, but these wetlands would retain other wetland values such as water  
11 retention, water filtration, and aquatic habitat. To mitigate the potential for these impacts,  
12 SCS will implement specific procedures as outlined in the ECP. All wetland areas within  
13 USFWS grassland and wetland easements will be avoided through routing or using  
14 HDD/bore.

15 For wetlands outside of USFWS easements, SCS will restore soil grade and replace  
16 topsoil to allow wetlands affected by construction activities to naturally revegetate. The  
17 Project will restore soil horizons by placing subsoil into the trench followed by topsoil to  
18 allow wetlands affected by construction activities to naturally revegetate. This is the  
19 preferred method of restoration based on decades of success that has resulted in the  
20 USACE NWP conditions that specify this requirement in their approvals. SCS conducted  
21 an extensive desktop and field survey data collection and analysis effort to identify and  
22 avoid, or minimize impacts to, wetlands and waterbodies. This is reflected in the absence  
23 of impacts to grassland and wetland easements, and minimal impacts to wetland  
24 easements as well as wetlands altogether (approximately 411 acres of PEM wetland  
25 impacts, and approximately 0.6 acres of permanent loss of PEM wetland).

26 **Q. What analysis was used regarding impacts to flora and fauna?**

27 **A.** Consistent with Council on Environmental Quality (CEQ) regulations that characterize the  
28 analyses required for a National Environmental Policy Act (NEPA) document, the Project  
29 focused the assessment on impacts that were considered significant or specifically stated  
30 in the PUC regulations. Pipeline construction and operation has been shown in numerous  
31 NEPA documents and South Dakota Public Utility Commission (SD PUC) proceedings to  
32 result in minor, localized impacts to surface resources when coupled with the execution of  
33 best management practices. This is borne out in the fact that federal and state agencies  
34 only require general permits for construction across wetlands and waterbodies, water use,

1 construction stormwater discharges, and water discharge.

2 **Q. What air quality impacts are expected from pipeline construction or operation?**

3 **A.** Construction equipment used on the Project will be compliant with emission requirements  
4 for on and off-road vehicle classification. Because construction moves along in a linear  
5 fashion, emission impacts will be minor and transitory. There are no operational emissions  
6 from operation of the electric pumps at the pump stations. Periodic blowdowns at mainline  
7 valves or pig launcher/receivers will be minor and infrequent.

8

9 **Q. Q. Does this conclude your written pre-filed direct testimony?**

10 **A.** Yes.

11

12 Dated this 19<sup>th</sup> day of November, 2024.

13       /s/ Jon A. Schmidt

14 Jon A. Schmidt, Ph.D.