

## **NOTES:**

- 1. Maintain a 10 foot vegetative buffer if possible between the disturbed area and the stream.
- 2. Limit clearing to only the area needed for construction.
- 3. Install timber mats for equipment staging as necessary.
- Install silt fence and/or other sediment barriers based on site specific conditons.
- No refueling within 100 feet of a stream. 5.
- Install trench breakers and permanent slope breakers as needed.
- Actual site layout may be modified based on site specific conditions. 7.
- Temporary equipment crossing will be installed outside of high water mark.



**DEER CREEK** PIPELINE PROJECT **Basin Electric** 

STREAM CROSSING TYPICAL HORIZONTAL DIRECTIONAL DRILL (HDD) SITE PLAN & PROFILE



**Exhibit 3.9-3 Typical Waterway Horizontal Directional Drilling Plan**