

BEFORE THE PUBLIC UTILITIES COMMISSION
OF THE STATE OF SOUTH DAKOTA

IN THE MATTER OF THE)
APPLICATION BY CROCKER WIND) EL 17-028
FARM, LLC FOR A PERMIT OF A)
WIND ENERGY FACILITY AND A 345)
KV TRANSMISSION LINE IN CLARK)
COUNTY, SOUTH DAKOTA, FOR)
CROCKER WIND FARM)

DIRECT TESTIMONY OF

ROB COPOULS

ON BEHALF OF

CROCKER WIND FARM, LLC

TABLE OF CONTENTS

I.	Witness Introduction.....	1
II.	Purpose and Coverage of Testimony.....	3-4
III.	Section 15.5.6 Electromagnetic Interference – Wind Farm.....	4-5
IV.	Section 19.3 Equipment Procurement, Manufacture and Delivery.....	5
V.	Section 19.4 Construction.....	5
VI.	Section 20.1.3.1 – Surface Transportation.....	5-6
VII.	Section 20.2.4.1 – Ground Transportation.....	6-7
VIII.	Section 23.0 – Decommissioning of Wind Energy Facilities.....	7-10
IX.	Section 24.2.1 – Electromagnetic Fields and Stray Voltages.....	10-12
X.	Section 26.0 – Transmission Facility Layout and Construction.....	12-17
XI.	Section 27.0 – Information Concerning Transmission Facilities.....	17-21

1 **Q. Please state your name and business address for the record.**

2 A. Rob Copouls. Westwood Professional Services. 7699 Anagram Drive, Eden Prairie MN
3 55344

4 **Q. Can you briefly describe your education and experience?**

5 A. I have Bachelors of Science in Civil Engineering from Valparaiso University and I am a
6 Professional Engineer licensed in several states. I have been working for Westwood
7 Professional Services for over 12 years. For 10 years I have been in the renewable
8 energy field working on wind and solar projects. I have been part of over 100 projects
9 with roles ranging from project engineer to Senior Project Manager. I am currently the
10 Operations Manager for our Division which includes over 170 people and works on wind,
11 solar and power delivery projects.

12 **Q. Have you attached a resume or CV.**

13 A. Yes

14 **Q. Have you previously submitted or prepared testimony in this proceeding in South
15 Dakota?**

16 A. No

17 **Q. What is the purpose of your direct testimony?**

18 A. To answer questions related to the permit application and educate the general public on
19 my area of expertise.

20 **Q. Which sections of the application are you responsible for?**

21 A. I am responsible for the following sections:

22 15.5.6 Electromagnetic Interference – Wind Farm

23 19.3 Equipment Procurement, Manufacture and Delivery

24 19.4 Construction
25 20.1.3.1 – Surface Transportation
26 20.2.4.1 – Ground Transportation
27 23.0 – Decommissioning of Wind Energy Facilities
28 24.2.1 – Electromagnetic Fields and Stray Voltages
29 26.0 – Transmission Facility Layout and Construction
30 27.0 – Information Concerning Transmission Facilities

31 **Q. Could you briefly summarize the information that you are responsible for in Section**
32 **15.5.6 Electromagnetic Interference – Wind Farm?**

33 A. Because of their height, modern wind turbines have the potential to interfere with
34 existing communications systems licensed to operate in the United States.
35 Comsearch conducted a Licensed Microwave Study for the Crocker Wind Farm.
36 Turbines have been sited in a manner that avoids all identified microwave beam paths
37 and communication systems. The construction and operation of the Project will not result
38 in interference to microwave, radio, or navigation signals. Crocker Wind received a
39 response letter from the United States Department of Commerce National
40 Telecommunications and Information Administration (“NTIA”) on May 13, 2016
41 (Appendix G). The agency indicated that after a 45+ day period of review, no federal
42 agencies identified any concerns regarding blockage of their radio frequency
43 transmissions. The Department of Agriculture (“DOA”) and Department of Justice
44 (“DOJ”) provided responses to NTIA stating No Harmful Interference Anticipated. The
45 Department of Commerce (“DOC”) and the Department of Energy (“DOE”) expressed
46 concerns the Wind Farm Project may obstruct radio frequency transmissions or

47 weather radar. Crocker is coordinating with both agencies to assess potential impacts and
48 will continue to do so as the Project layout is finalized. If interference to a residence's or
49 business's television service is reported to Crocker, Crocker will work with affected
50 parties to determine the cause of interference and, when necessary, reestablish television
51 reception and service.

52 **Q. Could you briefly summarize the information that you are responsible for in Section**
53 **19.3 Equipment Procurement, Manufacture and Delivery?**

54 A. Crocker previously began procurement of project specific equipment and is in the
55 process of procuring turbines for the Project. Turbines will be allocated to the Project
56 after meteorological and economic studies are completed to achieve the best match
57 of turbines for the Project. Equipment could start arriving on site as early as third
58 quarter 2018.

59 **Q. Could you briefly summarize the information that you are responsible for in Section**
60 **19.4 Construction?**

61 A. Crocker personnel will oversee the primary contractors performing onsite Project
62 construction, including, but not limited to, roads, wind turbine assembly, electrical, and
63 communications work. The construction will take approximately twelve months to
64 complete; however, depending upon seasonal or weather-related constraints (i.e., minimal
65 work would occur during winter months) it may take more or less time. Construction
66 could commence on site as early as third quarter 2018.

67 **Q. Could you briefly summarize the information that you are responsible for in Section**
68 **20.1.3.1 Surface Transportation?**

69 A. In general, the existing roadway infrastructure in and around the Wind Farm Project Area

70 and Transmission Line Route is characterized by state, county, and township roads
71 that generally follow section lines. Various county and township roads provide access to
72 the Project and include both two-lane and gravel roads. In the agricultural areas, many
73 landowners use private, single-lane farm roads and driveways on their property.
74 Roads within the Wind Farm Project Area are summarized in Table 20-2. The
75 Transmission Line Route parallels 419 th Avenue, State Highway 20, a two-track, and
76 property lines for most of the route.

77 **Q. Could you briefly summarize the information that you are responsible for in Section**
78 **20.2.4.1 Ground Transportation?**

79 A. During the construction phase, temporary impacts are anticipated on some public roads
80 within the Wind Farm Project Area and Transmission Line Route. Roads will be
81 affected by the transportation of equipment to and from the Project. Construction traffic
82 will use the existing county and state roadway system to access the Project and
83 deliver construction materials and personnel. Some roads may also be temporarily
84 expanded along specific routes as necessary to facilitate the movement of equipment.
85 Crocker expects to enter into road use agreements with the county and townships, and
86 to have a bond set by the Commission in accord with state law. Construction
87 activities will increase the amount of traffic using local roadways, but such use is not
88 anticipated to result in adverse traffic impacts. Operation and maintenance
89 activities will not noticeably increase traffic in the Project vicinity. The Project may
90 also temporarily affect traffic numbers in the area due to construction traffic. During the
91 construction phase, several types of light, medium, and heavy-duty construction
92 vehicles will travel to and from the Project Area, as well as private vehicles used by

93 construction personnel. The Applicant estimates that there will be 375 large truck trips
94 per day and up to 875 small-vehicle (pickups and automobiles) trips per day in the area
95 during peak construction periods. After construction is complete, traffic impacts during
96 the operations phase of the Project will be minimal. A small maintenance crew driving
97 through the area in pickup trucks on a regular basis will monitor and maintain the wind
98 turbines and transmission lines, as needed. There would be a slight increase in traffic for
99 occasional turbine, substation repair, and transmission line repair, but traffic function will
100 not be impacted as a result.

101 **Q. Could you briefly summarize the information that you are responsible for in Section**
102 **23.0 Decommissioning of Wind Energy Facilities?**

103 A. At the end of commercial operation, Crocker or the Project owners will be
104 responsible for removing wind facilities, and removing the turbine foundations to a depth
105 of four feet below grade. In this case, a decision may be made on whether to continue
106 operation with existing equipment or to retrofit the turbines and power system with
107 upgrades based on newer technologies. The anticipated Project life is approximately
108 thirty (30) years beyond the date of first commercial operation. The estimated
109 decommissioning cost in current dollars is expected to be between \$100,000 -
110 \$150,000 per turbine after salvage value, including associated facilities. Crocker
111 will be responsible for all costs to decommission the Project and associated
112 facilities. The cost to decommission will depend upon the prevailing rates for salvage
113 value of the equipment and labor costs. Because of the uncertainties surrounding
114 future decommissioning costs and salvage values, Crocker will review and update
115 the cost estimate of decommissioning and restoration for the Project every five years

116 after Project commissioning. Consistent with the terms of the wind lease and easement
117 agreements with individual landowners, Crocker will complete the following list of
118 decommissioning and restoration activities: Turbine removal - Access roads to turbines
119 will be widened to a sufficient width to accommodate movement of appropriately - sized
120 cranes, trucks and other machinery required for the disassembly and removal of the
121 turbines. Control cabinets, electronic components, and internal cables will be removed.
122 The rotor, nacelle and tower sections will be lowered to the ground where they may be
123 transported whole for reconditioning and reuse, or disassembled/cut into more easily
124 transportable sections for salvageable, recyclable, or disposable components. Turbine
125 and substation foundation removal - Topsoil will be removed from an area surrounding
126 the foundation and stored for later replacement, as applicable. Turbine foundations
127 will be excavated to a depth sufficient to remove all anchor bolts, rebar, conduits, cable,
128 and concrete to a depth of 48 inches below grade. The remaining excavation will be filled
129 with clean subgrade material of quality comparable to the immediate surrounding area.
130 The sub - grade material will be compacted to a density similar to surrounding sub -
131 grade material. All unexcavated areas compacted by equipment used in
132 decommissioning shall be de - compacted in a manner to adequately restore the
133 topsoil and sub - grade material to the proper density consistent and compatible
134 with the surrounding area. Underground collection cables - The cables and conduits
135 contain no materials known to be harmful to the environment. As part of the
136 decommissioning, these items will be removed to a depth of at least 48 inches. All cable
137 and conduit buried greater than 48 inches will be left in place and abandoned. Substation
138 and interconnection facilities - Disassembly of the substation and interconnection

139 facilities will include only the areas owned by Crocker. Components (including steel,
140 conductors, switches, transformers, fencing, control houses, etc.) will be removed from
141 the Project Area and reconditioned and reused, sold as scrap, recycled, or disposed of
142 appropriately, at Crocker's sole discretion. To remove foundations and underground
143 components without damaging or impacting adjacent facilities to the extent possible, such
144 foundations and underground components will be removed to a depth of 48 inches
145 and the excavation area filled, contoured and re - seeded, if necessary (e.g., the area
146 will not be subject to row crop agriculture after restoration). Access roads - Unless
147 otherwise requested by the landowner, permanent access roads constructed to
148 accommodate the Project will be removed. Ditch crossings connecting access roads to
149 public roads will be removed unless the landowner requests they remain in place.
150 Improvements to township and county roads that were not removed after construction
151 will remain in place. Crocker will restore and reclaim the site to its pre - Project
152 topography and topsoil quality using BMPs consistent with those outlined by 2012
153 USFWS Land- Based Wind Energy Guidelines. The goal of decommissioning will be to
154 restore natural hydrology and plant communities to the greatest extent practical while
155 minimizing new disturbance and removal of native vegetation. The
156 decommissioning BMPs that will be employed on the Project to the extent practicable
157 with the intent of meeting this goal include: 1. Minimize new disturbance and removal of
158 native vegetation to the greatest extent practicable. 2. Remove foundations to four feet
159 below surrounding grade, and cover with soil to allow adequate root penetration for
160 native plants, and so that subsurface structures do not substantially disrupt ground water
161 movements. 3. Reuse topsoil that is removed during construction and use as topsoil when

162 restoring plant communities. Once decommissioning activity is complete, restore topsoils
163 to assist in establishing and maintaining pre - construction native plant communities to
164 the extent possible, consistent with landowner objectives. 4. Stabilize soil and re -
165 vegetate with native plants appropriate for the soil conditions and adjacent habitat, and
166 use local seed sources where feasible, consistent with landowner objectives. 5. Restore
167 surface water flows to pre - disturbance conditions, including removal of stream
168 crossings, roads, and pads, consistent with storm water management objectives and
169 requirements. Conduct survey, using qualified experts, to detect populations of invasive
170 species, and implement and maintain comprehensive approaches to preventing and
171 controlling invasive species as necessary. 7. Remove any unnecessary overhead
172 electrical lines and associated poles. 8. After decommissioning, install erosion control
173 measures in all disturbance areas where potential for erosion exists, consistent with
174 storm water management objectives and requirements. 9. Remove fencing unless the
175 landowner requests it stay. 10. Remediate any petroleum product leaks and chemical
176 releases prior to completion of decommissioning. Decommissioning and restoration
177 activities will be completed within 12 months after the date the Project ceases to operate.

178 **Q. Could you briefly summarize the information that you are responsible for in Section**
179 **24.2.1 Electromagnetic Fields and Stray Voltages?**

180 A. The term electromagnetic field (“EMF”) refers to electric and magnetic fields that are
181 present around any electrical device. Electric fields arise from the voltage or
182 electrical charges and magnetic fields arise from the flow of electricity or current that
183 travels along transmission lines, power collection (feeder) lines, substation transformers,
184 house wiring, and electrical appliances. The intensity of the electric field is related

185 to the voltage of the line and the intensity of the magnetic field is related to the
186 current flow through the conductors (wire). EMF can occur indoors and outdoors.
187 However, there are no discernible health impacts from power lines (NIEH, 1999). The
188 proposed interconnection transmission line will be located adjacent to the O&M facility.
189 Wind turbine generators and associated interconnection cables will be setback from
190 residences in excess of state standards, where EMF will be at background levels. In those
191 instances where distribution lines have been shown to contribute to stray voltage, the
192 electric distribution system directly serving the farm or the wiring on a farm was directly
193 serving the farm or the wiring on a farm was directly under and parallel to the
194 transmission line. These circumstances are considered in installing transmission lines
195 and can be readily mitigated. Problems related to distribution lines are also readily
196 managed by correctly connecting and grounding electrical equipment. While the
197 general consensus is that electric fields pose no risk to humans, the question of whether
198 or not exposure to magnetic fields potentially causes biological responses or even health
199 effects continues to be the subject of research and debate. EMF from underground
200 electrical collection lines dissipates very close to the lines because they are installed
201 below ground within insulated shielding. The electrical fields are negligible, and there is
202 a small magnetic field directly above the lines that, based on engineering analysis,
203 dissipates within 20 feet on either side of the installed cable. EMF associated with the
204 transformers at the base of each turbine completely dissipates within 500 ft, so the 2,000
205 ft minimum turbine setback from non-participating residences and 1,000 ft setback from
206 participating residences will be adequate to avoid any EMF exposure to homes. Stray
207 voltage is a natural phenomenon that is the result of low levels of electrical current

208 flowing between two points that are not directly connected. Electrical systems, including
209 farm systems and utility distribution systems, must be adequately grounded to the earth to
210 ensure continuous safety and reliability, and to minimize this current flow. Potential
211 effects from stray voltage can result from a person or animal coming in contact with
212 neutral-to-earth voltage. Stray voltage does not cause electrocution and is not related to
213 ground current, EMF, or earth currents. Stray voltage is a particular concern for dairy
214 farms because it can impact operations and milk production. Problems are usually related
215 to the distribution and service lines directly serving the farm or the wiring on a farm
216 affecting confined farm animals. No impacts due to electromagnetic fields or stray
217 voltage are anticipated and no mitigation is proposed.

218 **Q. Could you briefly summarize the information that you are responsible for in Section**
219 **26.0 Transmission Facility Layout and Construction?**

220 A. The Transmission Line Route will be designed to meet or surpass applicable electrical
221 codes, and comply with good utility practices. Surveyors will stake the
222 construction corridor within the approved right-of-way and the pole locations of the
223 approved alignment in preparation for the construction crew arriving on site. Once the
224 construction crew arrives; they will begin by clearing and grubbing out the right-of-
225 way to ensure that vegetation meets the standards and that the construction crew
226 will have easy access to the construction site. Crocker will coordinate with landowners
227 on clearing and grubbing to ensure minimal impact to wind breaks, landscaping, and
228 other vegetative buffers. The crew will use chain saws, lifts, tractors and bulldozers only
229 where needed to clear vegetation. The crew will install temporary culverts and field
230 approaches where needed to access the route and to maintain adequate access and

231 drainage throughout construction. Construction will begin after applicable federal, state,
232 and local approvals have been obtained, property and right-of-way are acquired, soil
233 conditions are established and final design is completed. The precise timing of
234 construction will take into account various requirements that may be in place due to
235 permit conditions, system loading issues, weather and available workforce and materials.
236 The Applicant will work with an experienced contractor to construct and maintain the
237 transmission line in conjunction with the construction and operation of the Crocker Wind
238 Farm. Construction will follow industry best practices. These best practices address
239 transmission specifics such as right-of-way clearing, staging, and erecting transmission
240 line structures and stringing transmission lines. They also address general construction
241 best practices including but not limited to safety and storm water pollution prevention
242 planning. Crocker will be considering the proposed schedule for activities, permit
243 requirements, safety measures, prohibitions, maintenance guidelines, inspection
244 procedures, and terrain characteristics throughout the Project's development,
245 construction, and operations. In some cases these activities, such as schedules, are
246 modified to minimize impacts to sensitive animals or environments or to enhance safety.
247 Transmission line structures are generally designed for installation at existing grades.
248 Typically, structure sites with ten percent or less slope will not be graded or leveled. Sites
249 with more than ten percent slope will have working areas graded level or fill brought in
250 for working pads. Crocker anticipates that only minimal grading will be needed because
251 the route has very little elevation change. If the landowner permits, it is preferred to
252 leave the leveled areas and working pads in place for use in future maintenance activities.
253 If permission is not obtained, the site will be graded back to as close to its original

254 condition as possible, and all imported fill, including temporary culverts and road
255 approaches, will be removed from the site and disturbed areas will be returned to pre-
256 disturbance conditions. Typical construction equipment used on a project consists of tree
257 removal equipment, mowers, cranes, backhoes, digger-derrick line trucks, track-
258 mounted drill rigs, dump trucks, front end loaders, bucket trucks, bulldozers, flatbed
259 tractor-trailers, flatbed trucks, pickup trucks, concrete trucks and various trailers. Many
260 types of excavation equipment are set on wheel or track-driven vehicles. Poles are
261 transported on tractor-trailers. Staging areas are generally established when constructing
262 a transmission project. In the case of the Project, the staging area will likely be partially
263 shared with the associated Crocker Wind Farm. Staging involves delivering the
264 equipment and materials to construct the new transmission line facilities. Structures are
265 delivered to staging areas, sorted and loaded onto structure trailers for delivery to the
266 staked location. The materials are stored until they are needed for the Project. In some
267 cases, additional space (temporary laydown areas) may be required. These areas will be
268 selected for their location, access, security, and ability to efficiently and safely warehouse
269 supplies. The areas are chosen to minimize excavation and grading. Sufficient rights to
270 use the temporary laydown areas outside of the transmission line right-of-way will
271 be obtained from affected landowners through rental agreements. Insulators and other
272 hardware are attached to the structure while it is on the ground in the laydown area.
273 When it is time to install the poles, structures are moved from the staging areas, delivered
274 to the staked location and placed within the right-of-way until the structure is set.
275 Typically, access to the transmission line right-of-way corridor is made directly from
276 existing roads or trails that run parallel or perpendicular to the transmission line right-of-

277 way. In all cases where construction traffic and activities are within close proximity to
278 local, county or state roadways, the contractor will coordinate with the governing body
279 on traffic control and safety measures. In some situations, private field roads or trails are
280 used. Permission from the property owner is obtained prior to accessing the
281 transmission line corridor outside of public rights-of-way. Where necessary to
282 accommodate the heavy equipment used in construction (including cranes, concrete
283 cement trucks, and hole-drilling equipment), existing access roads may be upgraded
284 or new roads may be constructed. Once construction is complete the temporary
285 field approaches and access roads installed for the Transmission Line Route will be
286 removed and revegetated. Previously removed woody vegetation will be allowed to
287 regrow so long as it does not encroach on NESC prescribed clearances. At this time,
288 the Applicant anticipates the predominant method for securing the poles for the
289 Project to be concrete foundations. Monopole structures are generally placed on
290 foundations measuring between 6 to 11 feet in diameter and will typically be between
291 100 and 120 feet tall. Spacing intervals will be between 400 and 1,000 feet. The spoils
292 will be removed from site unless other arrangements are made with the landowner.
293 Crocker will not dispose of spoil materials within remnant prairie lands, areas restored
294 to native plant communities, wetlands, protected water bodies, protected
295 watercourses, or in a manner that could impact these areas through erosion or transport of
296 the spoil materials. Concrete foundations will be used when warranted by site specific
297 design criteria or circumstances. For concrete foundations, the excavation process
298 will utilize temporary steel casing and rebar, concrete and anchor bolts will be placed in
299 the hole. The standard projection of a concrete foundation is one foot above grade. The

300 ground will be disturbed during the normal course of work (as is typical of most
301 construction projects), which can take several weeks in any one location. The Applicant
302 will take the steps necessary to lessen the impact of the Transmission Line Route on the
303 surrounding environment by restoring areas disturbed by construction in accordance
304 with BMPs and the Project's permit conditions. This will begin with a pre-
305 construction survey that will identify areas requiring special restoration procedures.
306 During construction, crews will also attempt to limit ground disturbance wherever
307 possible. As construction on each parcel of land is completed, disturbed areas will be
308 restored to its original condition to the maximum extent practicable. In addition, a
309 management plan will be developed to prevent the spread of noxious and invasive weeds
310 during construction and ongoing operations. The Applicant or their contractor will
311 contact each property owner after construction is completed to identify and address any
312 damage that may have occurred as a result of the construction of the Project. If damage
313 has occurred to crops, fences or the property, the Applicant will fairly compensate
314 the landowner for the damages sustained in accordance with the terms and conditions
315 agreed upon in the Transmission Easement Agreement entered into by Crocker and the
316 landowner. In some cases, the Applicant may engage an outside contractor to restore the
317 damaged property to its original condition to the extent practicable. Portions of
318 permanent vegetation that are disturbed or removed during construction of
319 transmission lines will be reestablished to pre-disturbance conditions. Resilient
320 species of common grasses and shrubs typically reestablish naturally with few problems
321 after disturbance. Areas with significant soil compaction and disturbance from
322 construction activities along the route will require assistance in reestablishing the

323 vegetation stratum and controlling soil erosion. Commonly used BMPs to control soil
324 erosion and assist in reestablishing vegetation that may be used on the Transmission Line
325 Route include, but are not limited to: Erosion control blankets with embedded seeds, silt
326 fences, hay bales, hydro seeding, planting individual seeds or seedlings of non-invasive
327 native species. Transmission lines are designed to operate for decades. Typically, they
328 require only moderate maintenance, particularly in the first few years of operation. The
329 estimated service life of the proposed Transmission Line is approximately forty years.
330 However, high-voltage transmission lines are seldom completely retired. The Applicant
331 anticipates that the line could potentially, and would likely be broadly integrated into the
332 transmission system over time, ultimately providing wider utility than just
333 interconnecting the Crocker Wind Farm into the electrical grid. The principal operating
334 and maintenance cost for transmission facilities is the cost of inspections, which will be
335 performed monthly by either truck or by air. Inspections will be conducted to ensure
336 that the transmission line is fully functional and that no vegetation has encroached so as
337 to violate required clearances. Annual operating and maintenance costs for 345 kV
338 transmission lines in South Dakota and the surrounding states are expected to be
339 approximately \$300 to \$600 per mile. Actual line-specific maintenance costs depend
340 on the setting, the amount of vegetation management necessary, storm damage
341 occurrences, structure types, materials used, and the age of the line.

342 **Q. Could you briefly summarize the information that you are responsible for in Section**
343 **27.0 Information Concerning Transmission Facilities?**

344 A. Crocker will design the structures to best blend with the broader visual environment.
345 Typical structures for the Transmission Line Route will be primarily self-supporting

346 galvanized or weathering steel, wood, or concrete. Monopole structures will be used
347 unless conditions require the use of a more custom structure like an H-frame.
348 Additionally, some guying may be required and will be determined once geotechnical
349 investigations and structural design is completed. Crocker anticipates using Type 2-
350 bundle 954 aluminum conductor steel reinforced (“ACRS”) conductors or conductors
351 of comparable capacity. Monopole structures are generally placed on concrete
352 foundations measuring between 6 to 11 feet in diameter and will typically be between
353 100 and 120 feet tall. Spacing intervals will be between 400 and 1,000 feet. As
354 previously mentioned, transmission lines are designed to operate for decades. Typically,
355 they require only moderate maintenance, particularly in the first few years of operation.
356 The estimated service life of the proposed Transmission Line is approximately forty
357 years. Transmission infrastructure includes very few mechanical elements, which results
358 in reliability. It is built to withstand weather extremes, with the exception of severe
359 weather such as tornadoes and heavy ice storms. Transmission lines are automatically
360 taken out of service by the operation of protective relaying equipment when a fault is
361 sensed on the system. Such interruptions are usually momentary. Scheduled
362 maintenance outages are also infrequent. As a result, the average annual availability of
363 transmission infrastructure is very high, in excess of 99 percent. The Transmission Line
364 Route will be designed in compliance with local, State, and good utility standards
365 regarding clearance to ground, clearance to utilities, clearance to buildings, strength of
366 materials, and right-of-way widths. The Applicant’s contracted crews will comply with
367 local, state, and good utility standards regarding installation of facilities and standard
368 construction practices. Crocker will use proper signage and guard structures when

369 stringing wire across roads and railroads. Installation of the guard structures and
370 signage will be coordinated with the owner of the transportation corridor being protected.
371 Guard structures can be temporary wood poles with a cross arm or line trucks with their
372 booms used to hold the wire and protect the lanes of traffic. The proposed transmission
373 line will be equipped with protective devices, such as breakers and relays, to safeguard
374 the public from the transmission line if a transmission line or pole falls or other accident
375 occurs. Breakers and relays are located where the line connects to the substation, and will
376 de-energize the line in the event of an emergency. In addition to protective devices,
377 proper signage will be posted warning the public of the safety risks associated with the
378 energized equipment. The frequency of transmission line EMF in the United States is 60
379 hertz and falls in the extremely low frequency (“ELF”) range of the electromagnetic
380 spectrum (any frequency below 300 hertz). For the lower frequencies associated with
381 power lines, the electric and magnetic fields are typically evaluated separately. The
382 intensity of the electric field is related to the voltage of the line, while the intensity of the
383 magnetic field is related to the current flow along the conductors. Concerns about health
384 effects of EMF from power lines were first raised in the late 1970s. Since then,
385 considerable research has been conducted to determine if exposure to magnetic fields,
386 such as those from high-voltage power lines, causes biological responses and health
387 effects. Initial epidemiological studies completed in the late 1970s showed a weak
388 correlation between surrogate indicators of magnetic field exposure (such as wiring codes
389 or distance from roads) and increased rates of childhood leukemia (Wertheimer et. al,
390 1979). Toxicological and laboratory studies have not shown a biological mechanism
391 between EMF and cancer or other adverse health effects. In 2007, the World Health

392 Organization (“WHO”) concluded a review of health implications from magnetic fields
393 and concluded, “...virtually all of the laboratory evidence and the mechanistic evidence
394 fail to support a relationship between low-level ELF magnetic fields and changes in
395 biological function or disease status” (WHO, 2007). Natural and human-made
396 electromagnetic fields are present everywhere in our environment. Natural electric
397 fields in the atmosphere range from background static levels of 10 to 120 volts per meter
398 (“V/m”) to well over several kilovolts per meter (“kV/m”) produced by the build-up of
399 electric charges in thunderstorms. The Earth itself has a magnetic field that ranges
400 from approximately 300 to 700 milligauss (“mG”). In addition to the presence of the
401 earth’s steady state electric field, an average home experiences additional magnetic fields
402 of 0.5 mG to 4 mG which arise from the general wiring and appliances located in a
403 typical home. Crocker conducted an EMF study for the transmission line and estimated
404 the maximum magnetic field at 62.98 mG, which occurs at approximately 10 feet from
405 the proposed transmission line centerline. The maximum electric field for the Crocker
406 transmission line is calculated to be 6.73 kV/m at 15 feet from the proposed transmission
407 line centerline. At 75 feet from the proposed transmission line centerline (the edge of the
408 proposed right-of-way), the calculated electric field is 1.11 kV/m. The results of this
409 study are presented in Appendix I. Impacts from stray voltage are typically related to
410 improper grounding of electrical service to the farm (distribution lines) or on-farm
411 electrical wiring. Transmission lines do not, by themselves, create stray voltage because
412 they do not connect to businesses or residences and they are typically grounded properly.
413 However, transmission lines can induce stray voltage on a distribution circuit that is
414 parallel to and immediately under the transmission line. Appropriate measures, such as

415 proper grounding, will be taken to prevent stray voltage problems. Crocker must acquire
416 easement rights to route facilities across private property. During the route development
417 process, the Applicant reached out to landowners to obtain feedback on proposed routes
418 and to negotiate land rights. The Transmission Line Route covers approximately 102
419 acres, all of which are privately owned parcels subject to easement agreements between
420 Crocker and Clark County landowners. Crocker will also coordinate with the appropriate
421 agencies where the Transmission Line Route shares right-of-way with other public
422 utilities or public roads. This coordination is anticipated to be complete by the first
423 quarter of 2018. The Transmission Line will be built primarily with monopole structures,
424 which typically require a 150 foot right-of-way for the length of the route. Diagrams of
425 typical structures to be used on this Project are shown in Appendix J. The Transmission
426 Line has been routed to minimize tree clearing to the extent feasible. Isolated trees may
427 need to be cleared to allow safe operation of the Transmission Line. Refer to Section 26.1
428 for information on route clearing. No portion of the Transmission Line will require
429 underground transmission.

430 **Q. Does this conclude your written pre-filed direct testimony?**

431 A.

432

433

434 Dated this 21 day of September, 2017.

435

436 /s/Rob Copouls

437 Rob Copouls

438