

**BEFORE THE PUBLIC UTILITIES COMMISSION
OF THE STATE OF SOUTH DAKOTA**

**IN THE MATTER OF THE APPLICATION BY ENGIE NORTH AMERICA, INC. FOR
A PERMIT FOR A WIND ENERGY FACILITY IN HYDE COUNTY, SOUTH
DAKOTA, FOR MERIDIAN WIND PROJECT**

SD PUC DOCKET EL 20-013

PRE-FILED DIRECT TESTIMONY OF BLAKE CROSBY, OF ENGIE NORTH AMERICA,
INC.

April 24, 2020

TABLE OF CONTENTS

I. Witness Introduction.....1

II. Purpose and Coverage of Testimony.....3-4

III.

1 **Q. Please state your name, employer and business address for the record.**

2 A. Blake Crosby, ENGIE North America Inc., 8181 Arista Place, Suite 100, Broomfield, CO
3 80021

4 **Q. Briefly describe your educational background.**

5 A. Bachelors Degree in Mechanical Engineering from USMA, West Point, NY. Masters
6 Degree in Civil Engineering from University of Missouri Rolla.

7 **Q. Briefly describe your professional experience.**

8 A. US Army Engineer from 2002 to 2009. Renewable energy and utility construction from
9 2009 to present. Served in various capacities from estimator through senior project manager.

10 **Q. Have you attached a resume or CV.**

11 A. Yes, my resume is attached.

12 **Q. Have you previously submitted or prepared testimony in this proceeding in South
13 Dakota?**

14 A. No, I have not.

15 **Q. What is the purpose of your direct testimony?**

16 A. My testimony will support the portions of the application which discuss and illustrate the
17 construction and potential decommissioning of the project. Those sections are 4.2, 4.4 through
18 4.12, 16, 17, 19, and 20.2

19 **Q. What type of foundation will be used?**

20 A. Meridian plans to use a spread foundation design. Foundations for the towers will be
21 approximately 2732 square feet, with a depth of up to 10 feet. Except for approximately 6 inches
22 that will remain aboveground to allow the tower to be appropriately bolted to the foundation, the
23 tower foundation will be underground. A specific foundation design will be chosen based on soil

24 borings conducted at each turbine location.

25 The excavated area for the turbine foundations will typically be approximately 69 feet in
26 diameter (34.5 -foot radius, or approximately 4.01 acres for 64 turbines). During construction, a
27 larger area up to 150-foot radius (up to 77 acres for 64 turbines) may be used to lay down the
28 components of the turbines and assemble the rotors and maneuver cranes during turbine
29 assembly.

30 **Q. How will construction impact the roads in the project area?**

31 A. Where practicable, existing public roads, private roads and field paths will be utilized to
32 access Project components. The existing roads may require improvements before, during or
33 following construction. Where necessary, new access roads will be constructed between existing
34 roadways and Project components. The new and improved access roads will be all-weather,
35 gravel surfaced and generally up to approximately 16 feet in width. During construction, some of
36 the access roads will be widened to accommodate movement of the turbine erection crane, with
37 temporary widths of up to 40 feet with the access road in the center.

38 Separate access may be required for the cranes used to erect the wind turbines. In such
39 cases, temporary crane paths will be constructed between turbine locations. Following
40 completion of construction, the temporary crane paths will be removed and the area will be
41 restored pursuant to the contractual easement obligations. The final access road design will be
42 dependent on geotechnical information obtained during the engineering phase.

43 Large construction cranes may spend as little as one day at each turbine site before
44 moving on to the next. Cranes are sometimes moved cross-country rather than by using the
45 developed access roads. There are a number of reasons for such cross-country movement
46 including efficiency and economics. Taking a more direct route saves time. Breaking down the

47 crane is time-consuming. This type of cross-country walking enables the crane to be moved
48 without complete de-rigging and disassembly. We avoid walking cranes on county roads or state
49 highways as that could impede traffic and damage roads. Many crane walk routes are designed
50 around topography. Finally, cranes cannot cross a property that is not under easement. Where
51 cranes are required to travel cross-country, workers will lay down some form of cribbing,
52 bedding or mats where needed to support the weight of the crane without impacting the
53 underlying ground. The cribbing or mats will be removed immediately following passage of the
54 crane, to be re-used elsewhere.

55 **Q. Will the project utilize a laydown area? If so, what can you tell us about that?**

56 A. Meridian will grade a temporary laydown/staging area of up to approximately 13 acres
57 within the Project Area on land under lease. Potential locations for the laydown/staging area
58 have yet to be determined. The laydown/staging area will provide parking for construction
59 personnel, staging area for large equipment deliveries and potentially maintain an on-site
60 temporary concrete batch plant during construction. If a temporary batch plant is determined to
61 be required for the Project, to prepare concrete for foundations onsite, it will be strategically
62 placed to avoid cultural resources and will temporarily impact up to 4 acres of the 13-acre
63 laydown/staging area.

64 The laydown/staging area will also be used to conduct maintenance on construction
65 equipment and vehicles and to store fuel. On-site fuel storage will have secondary containment
66 and will be inspected regularly, with containment being remediated promptly in accordance with
67 the Project's Spill Prevention, Control and Countermeasures (SPCC) Plan. Fuel handling
68 activities and spill remediation will also adhere to the procedures outlined in the Project's SPCC
69 Plan.

70 **Q. Will you construct an operations and maintenance facility?**

71 A. No, a new O&M facility will not be constructed. The Triple H Wind Project located to
72 the west of Meridian is utilizing a new O&M facility that is currently under construction along
73 Highway 47. This facility will also support the Meridian Wind Project.

74 **Q. What will the project use to connect the towers electrically?**

75 A. The proposed collector system layout based on the proposed turbine configuration is
76 shown on Figure 2a (Appendix A). From the step-up transformers, power will run through an
77 underground system of collection cables, collector buses and feeder breakers, referred to as a
78 collector system, that connects to the Project collection substation. Up to 38.6 miles of
79 underground circuits will be installed by trenching, plowing or, where required, directionally
80 boring the cables underground to avoid sensitive environmental conditions or meet other
81 requirements. Generally, the electrical collector lines will be buried with marking tape and tracer
82 wire to meet the appropriate national electrical code. Meridian will register the appropriate
83 underground facilities with the South Dakota One-Call system.

84 **Q. Will communications systems connect the towers? If so, tell us about them?**

85 A. When installing the collector system, Meridian will also install fiber optic communication
86 systems connecting each of the Project's wind turbines to the Project collection substation and
87 provide for communication among the wind turbines, collection substation, O&M facility and
88 electrical grid as part of SCADA (see Section 4.2.1.1). If underground, the electrical and fiber
89 optic cables will be placed in the same trench wherever possible and will include occasional
90 aboveground junction boxes.

91 **Q. What type of substation will be used by the project?**

92 A. The collection substation will be located generally in the center of the Project Area and

93 will consist of one substation transformers, circuit breakers, switching devices, auxiliary
94 equipment, a control enclosure containing equipment for proper control, protection, monitoring
95 and communications and associated equipment and facilities. The principal function of the
96 substation is to increase the voltage from the 34.5 kV at the collector system to the voltage of the
97 345 kV transmission line, which will transport the electricity of the entire Project to the grid via
98 the interconnection switching station. The collection substation will be located within a fenced
99 area. The fence will be designed in accordance with industry standards to provide safety and
100 security.

101 Up to 5 acres of land will be purchased to facilitate construction and operation of the
102 collection substation. The proposed location for the substation is shown in the figures within the
103 application. As discussed in Section 4.2, Meridian requests that the permit allow Project
104 facilities, including the collection substation, to be modified as needed provided that the new
105 locations are on land leased for the Project, cultural resource impacts are avoided and conditions
106 specified in the Energy Facility Permit.

107 **Q. What land requirements have you identified?**

108 A. Temporary construction and long-term operational land requirements are identified
109 below. Table 6-1 presents impact calculations.

110 **Q. Please briefly describe the construction process.**

111 A. Meridian plans to commence construction within 30 days of receiving all required
112 federal, state and local permits and approvals. Construction is expected to require a period of
113 between 8 to 10 months to complete. Meridian anticipates that the civil construction will begin in
114 early 2021 and be completed prior to winter.

115 **Q. Have you identified impacts to the surrounding residents and communities from**

116 **construction? If so, please discuss them.**

117 A. During the construction phase, temporary impacts are anticipated on some public roads
118 in the vicinity of the Project Area, however local traffic will continue to have safe access though
119 the area. Roads will be affected by the transportation of equipment to and from the Project.
120 Construction traffic will use the existing county and state roadway system to access the Project
121 and deliver construction materials and personnel. During the construction phase, several types of
122 light, medium and heavy-duty construction vehicles will travel to and from the Project Area, as
123 well as private vehicles used by construction personnel. Meridian estimates that there will be up
124 to approximately 46 large truck trips per day, per foundation and up to 100 small-vehicle
125 (pickups and automobiles) trips per day in the area during peak construction periods. Some roads
126 may also be temporarily expanded along specific routes as necessary to facilitate the movement
127 of equipment.

128 Construction activities will increase the amount of traffic using local roadways, but
129 such use is not anticipated to result in adverse traffic impacts. Project personnel and contractors
130 will be instructed and required to adhere to speed limits commensurate with road types, traffic
131 volumes, vehicle types and site-specific conditions to ensure safe and efficient traffic flow.

132 **Q. How many workers will you need? Where will they live during construction?**

133 A. The Project is expected to employ approximately 125 temporary construction workers
134 during an estimated 4 month peak construction period to support Project construction. It is likely
135 that general skilled labor is available in the surrounding counties or the state to serve the basic
136 infrastructure and site development needs of the Project. Specialized labor will be required for
137 certain components of Project construction. It is likely that this labor will be imported from other
138 areas of the state or from other states, as the relatively short duration of construction makes

139 special training of local or regional labor impracticable.

140 The estimated number of construction jobs by classification and annual employment
141 expenditures during construction are included in Table 17-1; however, the exact number of jobs
142 during the peak of construction may be higher.

143 **Q. Can you speak about decommissioning?**

144 A. Yes. A Decommissioning Plan and estimated cost analysis was prepared for the Project
145 and is included in Appendix L. The estimated net decommissioning costs for the Project are
146 summarized in Appendix A of the Decommissioning Plan. The net decommissioning cost (in
147 2020 US dollars) is estimated to be \$5,545,587 assuming salvage and no resale of Project
148 components. The current cost of decommissioning the Project is estimated to be approximately
149 \$86,650 per turbine or \$31,856 per MW (based on 2.72 MW turbines) in 2020 dollars. This cost
150 includes a partial offset from the salvage value of the towers, turbine components and electrical
151 equipment. The detailed reclamation cost estimate is provided in Appendix B of the Plan.

152 **Q. How will you coordinate activities with local emergency response?**

153 A. Meridian and its construction team will coordinate with first responders, including but
154 not limited to air ambulance, local sheriff's office(s) and local fire services to develop an
155 emergency management plan during construction and operation of the Project. Meridian will also
156 be in contact with local first responders to offer information about the Project and to answer any
157 questions response teams may have regarding Project plans and details.

158 Dated this 24th day of April, 2020.

159

160 /s/ Blake Crosby

161 Blake Crosby, ENGIE North America Inc.