

Proposal



1750 E. North St. • Rapid City, SD 57701

(605) 348-8744 • Fax (605) 348-7730

PROPOSAL SUBMITTED TO: PLANET CONSTRUCTION	PHONE	DATE: 2-6-2024
STREET ATTN JON	JOB NAME: INSTALLING NEW SERVICE	
CITY, STATE AND ZIP CODE:	JOB LOCATION: 1721 EGLIN ST, RAPID CITY, SD	

We hereby submit specifications and estimates for:

MATERIAL AND LABOR TO INSTALL A NEW 400 AMP 480 VOLT 3 PHASE SERVICE. DISCONNECT ELECTRICAL CIRCUITS, INSTALL TEMPORARY RECEPTACLES, TEMPORARY LIGHTING AND RUN FIRE ALARM WIRE FROM EXISTING SPACE INTO RISER ROOM.

PRICE INCLUDES CT CAN, METER CAN, 400 AMP 3 PHASE DISCONNECT, 400 AMP 480 VOLT 3 PHASE PANEL WITH 1 - 110 AMP 3 POLE BREAKER AND 3 - 60 AMP 3 POLE BREAKERS. 1 - 75 KVA TRANSFORMER, 1 - 225 AMP 3 PHASE 208/120 VOLT PANEL WITH 20 - 20 AMP SINGLE POLE BREAKERS, CONDUIT, WIRE FROM POWER COMPANIES TRANSFORMER TO CT CAN. CONDUIT, WIRE FROM CT CAN TO DISCONNECT AND TO NEW 400 AMP PANEL INSIDE BUILDING. BUILD STAND TO MOUNT SERVICE TO. CUTTING, REMOVING OF ASPHALT AND TRENCHING, INSTALLING GRAVEL AND PACKING TRENCH. INSTALL 4 TEMPORARY RECEPTACLES, DISCONNECT CIRCUITS SO ELECTRICAL IS SAVE TO BE REMOVED BY OTHERS. INSTALL LIGHTS , 2 RECEPTACLES AND 1 ELECTRIC HEATER IN RISER ROOM. INSTALL EXIT/EMERGENCY LIGHT BY BACK DOOR, HOOK UP POWER TO 3 TEMPORARY GAS FURNACES AND DISCONNECT POWER TO ROOF TOP UNITS. DOES NOT INCLUDE ASPHALT FOR TRENCH AREA, EXCISE TAX OR ELECTRICAL PERMIT.

PRICE \$ 53,040.00

TRENCHING, REMOVING ASPHALT AND FILLING IN WITH GRAVEL.

PRICE \$ 7000.00

TOTAL PRICE \$ 60,040.00

CT CAN, METER CAN, 400 AMP DISCONNECT AND THE TRANSFORMER ARE IN STOCK. THE 400 AMP PANEL AND THE 200 AMP PANEL ARE ABOUT 8 WEEKS OUT. THEY TOLD ME THE PANELS COULD BE EXPEDIATED FOR AN ADDITIONAL FEE.

We Propose: hereby to furnish material and labor – complete in accordance with above specifications, for the sum of: _____ dollars (\$ _____).

Payment to be made as follows:

All materials are guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practice. Any alteration or deviation from the above specifications involving extra costs will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry fire, tornado and other necessary insurance. Our workers are fully covered by Workmen's Compensation Insurance.

Authorized Signature

Jeff Beards

Note: This proposal may be Withdrawn by us if not accepted within: 30 days.

Acceptance of Proposal: The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Signature _____

Date of Acceptance: _____

Signature _____