

RULE 20:10:13:56
 SCHEDULE D-2
 Plant Addition and Retirement for Test Period
 Test Year Ending December 31, 2013
 Utility: MidAmerican Energy Company
 Docket No. NG14-XXX

Individual Responsible: Mary Jo Anderson

Line No	Description (a)	In-Service Date (b)	South Dakota Amount (c)
Major Additions			
1	Gas Meter Blanket	Monthly	941,814
2	Purchase additional gas residential, commercial and industrial meter and correcting instrument for new business, replacement and/or meter sample program change outs.		
3	Cast Iron Rebuild Willow to Grange	11/16/2013	783,921
4	2013 CI Project, Willow-Grange, 2nd-33rd Str. Install 1,000 ft 8" stl, 16,885 ft PE (2,4,6"), one new DRS for system support and upgrade/replace 332 services. Move out 135 meters.		
5	Lamesa and 60th Phase 1	11/27/2013	680,478
6	Design and construction of 1 mile of 6-inch diameter steel main with a MOAP of 250 psig to improve system pressures and capacity for the NW area of the Sioux Falls distribution system. The pipeline will be designed and tested for a MAOP of 500 psig due to the potential of high pressure customers.		
7	Cast Iron Rebuild Area 4 - 19th Street	10/1/2013	1,392,532
8	Install 6,700 ft of 12" steel and 810 ft 4" steel to replace CI and DI/bare steel 65 psig system. Install new reg station on Spring Ave for Central Sioux Falls support.		
9	Cast Iron Rebuild Area 2 26th to 33rd	10/1/2013	593,932
10	Install 15600 ft. of 2-inch PE and 2700 ft 4-inch PE to replace cast iron mains and associated services. This project will replace 333 residential services with 165 meter move outs.		
11	Cast Iron Rebuild Area 1 26th to 33rd	12/31/2013	381,357
12	Install 5970 ft. of 2-inch PE and 3399 ft of 4-inch main to replace bare steel and cast iron mains and associated services. This project will replace 210 residential services with 82 meter move outs.		
13	Gas Mains New South Dakota	Monthly	1,406,144
14	Blanket project to construct new gas mains in 2013.		
15	Gas Services New South Dakota	Monthly	2,053,650
16	Blanket project to construct new services in 2013.		

RULE 20:10:13:56
 SCHEDULE D-2
 Plant Addition and Retirement for Test Period
 Test Year Ending December 31, 2013
 Utility: MidAmerican Energy Company
 Docket No. NG-14-XXX

Individual Responsible: Mary Jo Anderson

Line No	Description (a)	In-Service or Retirement Date (b)	South Dakota Amount (c)
Major Additions			
17	Gas Mains Rebuild South Dakota	Monthly	353,956
18	Blanket project to rebuild existing gas mains in 2013.		
Major Retirements			
19	Gas Meter Blanket - 2012	1/23/2013	(235,498)
20	Retire gas residential, commercial and industrial meter and correcting instrument.		

Source: Continuing Property Records (CPR) query